arXiv:1109.4835v1 [math.SG] 22 Sep 2011

A STABLE ∞-CATEGORY OF LAGRANGIAN COBORDISMS

DAVID NADLER AND HIRO LEE TANAKA

Abstract. Given an exact symplectic manifold M and a support Lagrangian $\Lambda \subset M$, we construct an ∞-category $\mathsf{Lag}_\Lambda(M)$ which we conjecture to be equivalent (after specialization of the coefficients) to the partially wrapped Fukaya category of M relative to Λ. Roughly speaking, the objects of $\mathsf{Lag}_\Lambda(M)$ are Lagrangian branes inside of $M \times T^*\mathbb{R}^n$, for large n, and the morphisms are Lagrangian cobordisms that are non-characteristic with respect to Λ. The main theorem of this paper is that $\mathsf{Lag}_\Lambda(M)$ is a stable ∞-category, or equivalently its homotopy category is triangulated, with mapping cones given by an elementary construction. In particular, its shift functor is equivalent to the familiar shift of grading for Lagrangian branes.

Contents

1. Introduction 2
1.1. Main constructions 3
1.2. Conjectures and further directions 8
1.3. Outline of the paper 13
1.4. Acknowledgements 13
2. Geometric setup 14
2.1. Symplectic manifold 14
2.2. Support Lagrangian 15
2.3. Lagrangian branes 15
2.4. Product structures 16
2.5. Euclidean space 16
3. Lagrangian cobordisms 23
3.1. Cubical collaring 23
3.2. Convex preliminaries 23
3.3. Factorization 25
3.4. Time symmetries 27
3.5. Non-characteristic propagation 28
3.6. Basic examples 30
4. ∞-category of Lagrangian cobordisms 32
4.1. Weak Kan property 32
4.2. Zero object 37
4.3. Non-characteristic objects 38
4.4. Stabilization 41
4.5. Space symmetries 43
4.6. Tilting 44
5. Construction of kernel 45

5.1. Kernel object 45
5.2. Kernel morphism 46
5.3. Kernel homotopy 48
6. Proof of universal property 54
6.1. Formal reductions 54
6.2. Anatomy of lift 58
6.3. Map to kernel 60
6.4. Proof of Proposition 6.1.8 63
6.5. Proof of Proposition 6.1.9 72
7. The loop functor 76
7.1. Definition of loop functor 76
7.2. Loop functor for Lag 77
8. Appendix: ∞-categories 79
8.1. Simplicial sets, horns, quasi-categories 79
8.2. Mapping spaces 80
8.3. Limits and terminal objects 81
8.4. Dual notions 82
8.5. The simplicial nerve 83
9. Appendix: Hamiltonian isotopies as cobordisms 86
9.1. Deformations of Lagrangians 86
9.2. Hamiltonian isotopies 87
9.3. Hamiltonian cobordisms 88
9.4. Hamiltonian morphisms 89
9.5. Higher Hamiltonian morphisms 89
References 92

1. Introduction

This paper introduces a stable theory of Lagrangian cobordisms in exact symplectic manifolds. Fukaya categories [FOOO09, S08] provide a geometric (or analytic) approach to quantum symplectic geometry, while deformation quantization [DL83, F94, K03] provides an algebraic approach. We hope that Lagrangian cobordisms will provide a missing topological (or homotopical) viewpoint. By their nature, Lagrangian cobordisms involve the intuitive geometry of Lagrangian submanifolds and the flexibility of Hamiltonian isotopies. They also bypass unnatural choices of coefficients and the challenging partial differential equations of pseudo-holomorphic disks. Our inspirations include Floer's original vision [Fl88a, Fl88b, Fl89] of Morse theory of path spaces, the notion of non-characteristic propagation [KS84, GM88, N09] and the homotopical setting of stable ∞-categories [J02, LTop06, DAGI].

Given an exact symplectic target M equipped with a (not necessarily smooth or compact) support Lagrangian $\Lambda \subset M$, we construct an ∞-category $\mathsf{Lag}_\Lambda(M)$ whose objects are Lagrangian branes inside of $M \times T^*\mathbb{R}^n$, for large n, and whose morphisms are Lagrangian cobordisms that are non-characteristic with respect to Λ. Our main result states that $\mathsf{Lag}_\Lambda(M)$ is a stable ∞-category (Theorem 1.1.14) with concretely realized mapping cones (Theorem 1.1.16). In the rest of the Introduction to follow, we outline the construction of $\mathsf{Lag}_\Lambda(M)$ and the proof of our main result. We conclude the Introduction with the discussion of a sequence of motivating conjectures centered around the following topics:

(1) Calculation of $\mathsf{Lag}_{pt}(pt)$ (conjectures of Section 1.2.1).

(2) Relation of $\mathsf{Lag}_X(T^*X)$ to modules over chains on the based loop space of X, and more generally, for conic $\Lambda \subset T^*X$, relation of $\mathsf{Lag}_\Lambda(T^*X)$ to constructible sheaves on X (conjectures of Section 1.2.2).

(3) Gluing together $\mathsf{Lag}_\Lambda(M)$ from the assignment $U \mapsto \mathsf{Lag}_{U\cap\Lambda}(U)$ for appropriate open sets $U \subset M$ (Conjecture 1.2.17).

(4) Relation of $\mathsf{Lag}_\Lambda(M)$ to the partially wrapped Fukaya category of M with respect to Λ (see Conjecture 1.2.18).

1.1. **Main constructions.**

It is possible that Lagrangian cobordisms could be profitably considered in a diverse range of settings. There is a long history of the subject [Ar80, Au85, Au87, ArNo01, Ch97, E84] with many recent advances [Oh, Co]. We will restrict to a geometric setup (which we learned from the well-known references [EG91, E97]) where we have some intuition for the situation.

Throughout this paper, M will be an exact symplectic manifold, with symplectic form ω_M, fixed primitive $\omega_M = d\theta_M$, and Liouville vector field Z_M defined by $\omega_M(Z_M, -) = \theta_M(-)$. It is a useful level of generality to assume that Z_M is complete, and so the flow generated by Z_M provides an $\mathbb{R}_{>0}$-action on M. We will use the term *dilation* to refer to the $\mathbb{R}_{>0}$-action, and the term *conical* to refer to sets that are $\mathbb{R}_{>0}$-invariant.

Example 1.1.1. Here are some examples of the exact symplectic manifolds we have in mind (roughly speaking, the first is a mildly degenerate instance of the second):

(1) *Cotangent bundles*: fix a smooth (not necessarily compact) base manifold X, and let $M = T^*X$ be its cotangent bundle equipped with θ_M the canonical one-form. The Liouville vector field Z_M generates the fiberwise dilation. More generally, we could take a conical open subset $U \subset M = T^*X$.

(2) *Weinstein manifolds*: suppose M admits a proper, bounded-below Morse function $h : M \to \mathbb{R}$ such that Z_M is gradient-like with respect to h. Such data naturally arises when $M \subset \mathbb{C}^n$ is a Stein or smooth affine complex variety: one can take h to be a perturbation of the restriction of the standard unitary norm on $\mathbb{C}^n$, and θ_M to correspond to the gradient of h via the symplectic form. More generally, we could consider a conical open subset $U \subset M$.

To control the noncompact nature of M, it is useful to assume various taming hypotheses near infinity. We refer the reader to Section 2 below for the approach we adopt in this paper (though no doubt there are worthwhile alternative approaches depending on the application). In particular, we assume M is the interior of a manifold with corners $\overline{M}$ so that the closures in $\overline{M}$ of any two disjoint conical subsets of M continue to be disjoint. Some convenient notation: we will write $M^\infty = \overline{M} \setminus M$ for the boundary of $\overline{M}$, and given a subset $A \subset M$, we will write $\overline{A}$ for the closure of A inside of $\overline{M}$, and $A^\infty = \overline{A} \setminus A = \overline{A} \cap M^\infty$ for the part of $\overline{A}$ lying in the boundary M^∞.

We will also work with background structures enabling us to speak about Lagrangian submanifolds of M equipped with brane structures.

1.1.1. *Lagrangian cobordisms.* Roughly speaking, cobordisms are manifolds $\mathfrak{X}$ with boundary $\partial\mathfrak{X} = X_{in} \coprod X_{out}$ the disjoint union of an incoming and outgoing manifold. They naturally arise when one cuts global manifolds into simpler local pieces or studies algebraic structures in a homotopical context. For these and other reasons, cobordisms are now ubiquitous in algebraic topology, representation theory, mathematical physics, and many other areas of current interest. Our viewpoint on them is most influenced by topological field theory and specifically gauge theory, where one finds a striking synthesis of abstract formalism and concrete applications.

We will study cobordisms for which the boundary manifolds are Lagrangian branes in the exact symplectic manifold M. More precisely, we will consider (closed but not necessarily compact) exact graded Lagrangian submanifolds $L \subset M$ equipped with a function $f : L \to \mathbb{R}$ realizing the exactness in the sense that $\theta|_L = df$, and a function $\alpha : L \to \mathbb{R}$ realizing the grading, and a relative pin structure q. To control the possibly noncompact nature of L, we will always assume taming hypotheses as discussed in Section 2. All in all, the basic object of study is the quadruple $\mathsf{L} = (L, f, \alpha, q)$, but we will sometimes abuse notation and denote it by L alone (the possible primitives $f : L \to \mathbb{R}$ form a torsor for $H^0(L, \mathbb{R})$, and the moduli of the other data is a torsor for a discrete group).

Our cobordisms will be represented by Lagrangian branes in the exact symplectic manifold $M \times T^*\mathbb{R}_t$. Here we write $\mathbb{R}_t$ both to denote the real line with coordinate t, and to convey that we think of it as the timeline of evolution. More precisely, we will consider (closed with boundary but not necessarily compact) appropriately collared Lagrangian branes $P_{01} \subset M \times T^*\mathbb{R}_t$ living over say $[0, 1] \subset \mathbb{R}_t$ and with boundary $\partial P_{01} = L_0 \coprod L_1$, where for $i = 0, 1$, we have

$$L_i \subset M \times \{(i, 0)\} \subset M \times \mathbb{R}_t \times \mathbb{R}_t^\vee \simeq M \times T^*\mathbb{R}_t.$$

To control the possibly noncompact nature of P_{01}, we will always assume taming hypotheses as discussed in Section 2. Thanks to the collaring requirements, we can and will replace P_{01} with the extended (boundaryless but not compact) brane

$$P = (L_0 \times \{(r < 0, 0)\}) \cup P_{01} \cup (L_1 \times \{(r > 1, 0)\}) \subset M \times T^*\mathbb{R}_t.$$

It is then convenient to forget the original interval $[0, 1] \subset \mathbb{R}_t$ and only remember that P is constant away from a compact subset of $\mathbb{R}_t$.

As with manifolds and usual cobordisms, one needs to be careful with the notion of equivalence. One familiar approach is to consider the space of cobordisms between two fixed manifolds, or at the very least its set of connected components. We will take a much more flexible approach and consider cobordisms between two fixed Lagrangians, and then cobordisms between cobordisms, and so on. One might attempt to organize such data into an "(∞, ∞)-category" (and in the process formulate what such a structure would entail). Fortunately, for our purposes, we will be content to invert all higher morphisms and work with the resulting $(\infty, 1)$-category. Before discussing this further, we need to discuss more precisely which Lagrangian cobordisms we will take as morphisms.

1.1.2. *Non-characteristic cobordisms.* An important notion in symplectic geometry is that of *support Lagrangian.* It is the fundamental invariant in quantum algebra and the microlocal study of sheaves and PDE. (The theory of polarizations and their metaplectic symmetries studies the implications of a choice of support Lagrangian. The theory of moduli of stability conditions can also be phrased in terms of moduli of support Lagrangians.) We will incorporate the notion of support Lagrangian into our study of Lagrangian cobordisms in the following way.

Fix once and for all a (not necessarily compact, possibly singular) closed Lagrangian subvariety $\Lambda \subset M$. To control the possibly noncompact nature of Λ, we will always assume taming hypotheses as discussed in Section 2.

Example 1.1.2. Continuing Example 1.1.1, here are some examples of the support Lagrangians we have in mind:

(1) *Conical Lagrangians in cotangent bundles*: take $\Lambda \subset M = T^*X$ to be any closed conical Lagrangian subvariety. In particular, we could take Λ to be the zero section alone. More generally, if $U \subset M = T^*X$ is a conical open subset, we can take the restriction $\Lambda \cap U \subset U$ as support Lagrangian inside of U.

(2) *Conical Lagrangians in Weinstein manifolds*: let $\Lambda^{sk} \subset M$ be the "Lagrangian skeleton" of stable manifolds associated to the exhausting Morse function $h : M \to \mathbb{R}$ (for details, see [Bi01]). We can then take Λ to be the union of Λ^{sk} together with the "cone" with respect to dilation over any Legendrian subvariety in M^∞. More generally, if $U \subset M$ is a conical open subset, we can take the restriction $\Lambda \cap U \subset U$ as support Lagrangian inside of U. In particular, Λ can be singular.

Although we have not discussed any non-conical examples, there is nothing to exclude such a choice.

Once Λ is fixed, we will only consider Lagrangian branes $L \subset M$ that *are disjoint from* Λ *at infinity* in the sense that $L^\infty = \overline{L} \cap M^\infty$ is disjoint from $\Lambda^\infty = \overline{\Lambda} \cap M^\infty$.

Example 1.1.3. Let X be a non-compact smooth manifold. With the choice $\Lambda = T^*_X X$, Λ is not within the class of branes we consider because it intersects itself at infinity. If X were compact, Λ would be a brane we consider.

Taking the product of the support Lagrangian Λ with the zero section $\mathbb{R}_t \subset T^*\mathbb{R}_t$, we obtain a corresponding support Lagrangian $\Lambda \times \mathbb{R}_t \subset M \times T^*\mathbb{R}_t$. We say that a Lagrangian cobordism $P \subset M \times T^*\mathbb{R}_t$ is *non-characteristic* if there is a closed one-form $\eta \in \Omega^1(\mathbb{R}_t)$ and a constant $T > 0$ such that $\eta = dt$ in the distant past and future when $|t| > T$, and the shifted Lagrangian cobordism

$$P + \Gamma_\eta \subset M \times T^*\mathbb{R}_t$$

is disjoint from the extended support Lagrangian $\Lambda \times \mathbb{R}_t$. Here $\Gamma_\eta \subset T^*\mathbb{R}_t$ denotes the graph of the one-form η, and the sum denotes the fiber-wise sum of sets in the factor $T^*\mathbb{R}_t$. An analogous definition makes sense for Lagrangian cobordisms between Lagrangians cobordisms, and so on.

Definition 1.1.4 (see Section 3 for a precise version)**.** Given a fixed support Lagrangian $\Lambda \subset M$, we define an ∞-category $\mathsf{Lag}^{\diamond 0}_\Lambda(M)$ with objects Lagrangian branes $L \subset M$, and 1-morphisms non-characteristic Lagrangian cobordisms $P \subset M \times T^*\mathbb{R}_t$.

Remark 1.1.5. While there are many models for ∞-categories, or synonymously $(\infty,1)$-categories, we will utilize the model of a weak Kan complex, or synonymously quasi-category, as appears in the work of Joyal and Lurie. For a discussion of some relevant basic notions, one could refer to the overview of the Appendix.

For the reader unfamiliar with this notion, the following rough analogy is useful to keep in mind:

$$\text{algebra: } E_1\text{-algebra :: category : } \infty\text{-category}$$

Informally speaking, the E_1-structure on $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$ is given by placing Lagrangian cobordisms one after the other along the real line $\mathbb{R}_t$.

The following result is the first hint of the role of the support Lagrangian $\Lambda \subset M$ in our story (and lends some justification to its name). Recall that a *zero object* in an ∞-category is an object which is both initial and terminal, and any two zero objects are canonically equivalent. By the zero category, we will mean the category with a single object $*$ with the single morphism given by the identity of $*$.

Proposition 1.1.6. *The empty Lagrangian $L_\emptyset \subset M$ is a zero object in the ∞-category $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$. When the support Lagrangian Λ is empty, the ∞-category $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$ is equivalent to the zero category.*

In fact, the following stronger result holds (which is compatible with the discussed relation with the partially wrapped Fukaya category leading up to Conjecture 1.2.18). It is proven in Section 4.3.

Proposition 1.1.7. *Let $L \subset M$ be a brane satisfying $L \cap \Lambda = \emptyset$. Then L is a zero object in $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$.*

1.1.3. *Stabilization.* Though $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$ has a zero object, one can check that in any generality it is not stable. The main result of this paper is a concrete geometric construction of a stabilization.

Definition 1.1.8 ([L11])**.** An ∞-category $\mathcal{C}$ is said to be *stable* if it satisfies the following:

(1) There exists a zero object $0 \in \mathcal{C}$.
(2) Every morphism in $\mathcal{C}$ admits a kernel and a cokernel.
(3) Any commutative diagram in $\mathcal{C}$ of the form

$$\begin{tikzcd} a \arrow[r] \arrow[d] & b \arrow[d] \\ 0 \arrow[r] & c \end{tikzcd}$$

is Cartesian if and only if it is cocartesian.

The third condition states that the diagram presents a as a kernel of $b \to c$ if and only if it presents c as a cokernel of $a \to b$.

Remark 1.1.9. Any stable ∞-category $\mathcal{C}$ is linear over the sphere spectrum, and hence may be localized with respect to any E_∞-ring spectrum. In particular, we can forget all positive characteristic information and consider the rational stable ∞-category $\mathcal{C} \otimes \mathbb{Q}$.

The theories of rational stable ∞-categories, pre-triangulated rational A_∞-categories, and pre-triangulated rational differential graded categories are all equivalent. (For various notions of enhanced category, see for example the surveys of [B06] and [Ke06].)

Remark 1.1.10. Strictly speaking, we do not directly establish properties (2) and (3) of the above definition. Rather, we appeal to the following theorem of Lurie.

Theorem 1.1.11 ([L11]). *An ∞-category $\mathcal{C}$ is a stable ∞-category if and only if the following three properties are satisfied:*

1. *There exists a zero object $0 \in \mathcal{C}$.*
2. *Every morphism in $\mathcal{C}$ admits a kernel.*
3. *Let $\Omega : \mathcal{C} \to \mathcal{C}$ be the functor induced by sending every object X to the kernel of the zero map $0 \to X$. Then Ω is an equivalence.*

It is the above three properties which we verify.

We have asserted above that the empty Lagrangian is a zero object of $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$. To guarantee the existence of kernels and cokernels, we consider the following symplectic version of a stabilization procedure familiar from algebraic topology.

Consider the symplectic manifold $T^*\mathbb{R}^n_x$ with fixed support Lagrangian the zero section $\mathbb{R}^n_x \subset T^*\mathbb{R}^n_x$. We will also equip $T^*\mathbb{R}^n_x$ with canonical grading background structures (arising from the fact that it is a cotangent bundle). For notational simplicity, we set

$$\mathsf{Lag}_\Lambda^{\diamond n}(M) = \mathsf{Lag}_{\Lambda\times\mathbb{R}^n}^{\diamond 0}(M \times T^*\mathbb{R}^n),$$

which for $n = 0$, agrees with our previous notation. Successively taking the product with the conormal Lagrangian $T^*_{\{0\}}\mathbb{R}_x \subset T^*\mathbb{R}_x$ provides a tower of faithful functors

$$\begin{tikzcd} \cdots \arrow[r] & \mathsf{Lag}_\Lambda^{\diamond n}(M) \arrow[r] & \mathsf{Lag}_\Lambda^{\diamond n+1}(M) \arrow[r] & \cdots \end{tikzcd}$$

Definition 1.1.12. Given $\Lambda \subset M$, we define the ∞-category $\mathsf{Lag}_\Lambda(M)$ to be the colimit

$$\mathsf{Lag}_\Lambda(M) = \operatorname{colim}_{n\to\infty} \mathsf{Lag}_\Lambda^{\diamond n}(M)$$

in the ∞-category of stable ∞-categories.

Remark 1.1.13. In the Joyal model structure, fibrant-cofibrant objects are quasi-categories, and cofibrations are level-wise injections. Hence the homotopy colimit $\mathsf{Lag}_\Lambda(M)$ can be calculated by the naive increasing union of simplicial sets

$$\mathsf{Lag}_\Lambda(M) \simeq \cup_{n\to\infty} \mathsf{Lag}_\Lambda^{\diamond n}(M).$$

Now the following is an abstract form of our main result.

Theorem 1.1.14. *The ∞-category $\mathsf{Lag}_\Lambda(M)$ is stable.*

Remark 1.1.15. While we have used the term *stabilization* to refer to the construction of $\mathsf{Lag}_\Lambda(M)$, the same term is used in [L11] as a general procedure for producing stable ∞-categories from non-stable ones. We expect that $\mathsf{Lag}_\Lambda(M)$ is the universal stabilization of $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$ but tackling this question is beyond the scope of this paper.

1.1.4. *Mapping cones.* One often refers to the cokernel of a morphism in a stable ∞-category as a mapping cone. Part of the value of the above theorem is its proof in which the mapping cone is concretely constructed.

We briefly summarize here the structure of the mapping cone $C(f) \in \mathsf{Lag}_\Lambda(M)$ of a morphism $f : L_0 \to L_1$. We will restrict our discussion to objects L_0, L_1 and a morphism f coming from $\mathsf{Lag}^{\diamond 0}_\Lambda(M)$. So the objects L_0, L_1 are represented by Lagrangian branes in M, and the morphism f is represented by a Lagrangian cobordism $P \subset M \times T^*\mathbb{R}_t$ living over say $[0,1] \subset \mathbb{R}$.

For the above setup, the mapping cone $C(f)$ will come from an object of $\mathsf{Lag}^{\diamond 1}_\Lambda(M)$. To construct it, we form the Lagrangian submanifold

$$C(f) = (L_0 \times \Gamma_0) \cup P \cup (L_1 \times \Gamma_1) \subset M \times T^*\mathbb{R}$$

where $\Gamma_0, \Gamma_1 \subset T^*\mathbb{R}$ are the graphs of closed one-forms df_0, df_1 defined over $(-1, 0], [1, 2)$ respectively. Roughly speaking, f_0 is decreasing with $\lim_{x \to -1} f(x) = +\infty$, $f^{(k)}(0) = 0$, for all $k \geq 0$, and f_1 is decreasing with $\lim_{x \to 2} f(x) = -\infty$, $f^{(k)}(1) = 0$ for all $k \geq 0$.

We show that $C(f)$ admits the structure of a graded exact brane and can be considered an object in $\mathsf{Lag}_\Lambda(M)$. The following is an important step in the proof of Theorem 1.1.14.

Theorem 1.1.16. *In the stable ∞-category $\mathsf{Lag}_\Lambda(M)$, for a morphism $f : L_0 \to L_1$, the object $C(f)$ is a mapping cone of f.*

1.2. **Conjectures and further directions.**

1.2.1. *Ground case.* Here we discuss the structure of $\mathsf{Lag}_\Lambda(M)$ when M and Λ are simply a point. Because of our stabilization procedure, this is not as trivial as it might initially sound (for instance, it can be shown to contain the stable Pontryagin-Thom theory of ordinary cobordisms).

In a stable ∞-category $\mathcal{C}$, for any objects $a, b \in \mathcal{C}$, the morphism spaces $\mathrm{Hom}_\mathcal{C}(a, b[k])$, for $k \in \mathbb{Z}$, assemble into a spectrum which we will denote by $\mathcal{H}om_\mathcal{C}(a, b)$. When $a = b$, composition equips the morphism spaces $\mathrm{Hom}_\mathcal{C}(a, a[k])$, for $k \in \mathbb{Z}$, with the additional structure of an E_1-algebra in spectra which we will denote by $\mathcal{E}nd_\mathcal{C}(a)$.

Definition 1.2.1. Let $\mathcal{C}$ be a stable ∞-category.

(1) An object $a \in \mathcal{C}$ is *compact* if $\mathrm{Hom}_\mathcal{C}(a, -)$ preserves coproducts.

(2) An object $a \in \mathcal{C}$ is a *generator* if for any $c \in \mathcal{C}$, $\mathrm{Hom}_\mathcal{C}(a, c[k]) \simeq 0$, for all k, implies $c \simeq 0$.

If $a \in \mathcal{C}$ is a compact generator, then we can recover $\mathcal{C}$ as the image of the Yoneda functor

$$\mathcal{C} \longrightarrow \mathcal{E}nd_\mathcal{C}(a)\text{-mod} \qquad c \longmapsto \mathcal{H}om_\mathcal{C}(a, c)$$

where $\mathcal{E}nd_\mathcal{C}(a)$-mod denotes the stable, presentable ∞-category of $\mathcal{E}nd_\mathcal{C}(a)$-modules in spectra.

On the one hand, if $\mathcal{C}$ is a stable, presentable ∞-category with a compact generator $a \in \mathcal{C}$, then the Yoneda functor is an equivalence $\mathcal{C} \simeq \mathcal{E}nd_\mathcal{C}(a)$-mod. On the other hand, suppose $\mathcal{C}$ is a stable ∞-category with a generator $a \in \mathcal{C}$ such that every object is a finite colimit of objects of the form $a[k]$, for $k \in \mathbb{Z}$. Then it is immediate that a

is compact, and the Yoneda functor induces an equivalence $\mathcal{C} \simeq \mathcal{E}nd_{\mathcal{C}}(a)$-perf, where $\mathcal{E}nd_{\mathcal{C}}(a)$-perf denotes the stable ∞-category of perfect $\mathcal{E}nd_{\mathcal{C}}(a)$-modules in spectra (the full subcategory of modules which are finite colimits of free modules).

Conjecture 1.2.2. *Take $M = \Lambda = pt$, consider $\mathsf{Lag}_{pt}(pt)$, and set $\mathcal{E} = \mathcal{E}nd_{\mathsf{Lag}_{pt}(pt)}(pt)$.*

(1) The object $pt \in \mathsf{Lag}_{pt}(pt)$ is a generator.

(2) Every object of $\mathsf{Lag}_{pt}(pt)$ is a finite colimit of objects of the form $pt[k]$, for $k \in \mathbb{Z}$. Consequently, the Yoneda functor induces an equivalence

$$\mathsf{Lag}_{pt}(pt) \simeq \mathcal{E}\text{-perf}$$

By the conjecture, the study of $\mathsf{Lag}_{pt}(pt)$ reduces to the calculation of the endomorphism algebra $\mathcal{E} = \mathcal{E}nd_{\mathsf{Lag}_{pt}(pt)}(pt)$. By construction, $\mathcal{E}$ is only an E_1-algebra, but in fact it naturally comes from an E_∞-algebra. To see this, observe that external product induces a functor

$$\mathsf{Lag}_{\Lambda_1}(M_1) \otimes \mathsf{Lag}_{\Lambda_2}(M_2) \longrightarrow \mathsf{Lag}_{\Lambda_1 \times \Lambda_2}(M_1 \times M_2).$$

When we take $M_1 = M_2 = \Lambda_1 = \Lambda_2 = pt$, this equips $\mathsf{Lag}_{pt}(pt)$ with a symmetric monoidal structure. (And when we only restrict $M_1 = \Lambda_1 = pt$, this equips any $\mathsf{Lag}_{\Lambda_2}(M_2)$ with the structure of $\mathsf{Lag}_{pt}(pt)$-module.) Furthermore, it is apparent that the object $pt \in \mathsf{Lag}_{pt}(pt)$ is the unit for this structure. Thus it follows that its endomorphism algebra $\mathcal{E}$ is in fact an E_∞-ring spectrum.

Conjecture 1.2.3. *Take $M = \Lambda = pt$, consider $\mathsf{Lag}_{pt}(pt)$.*

The E_∞-ring spectum $\mathcal{E} = \mathcal{E}nd_{\mathsf{Lag}_{pt}(pt)}(pt)$ is connective with $\pi_0(\mathcal{E}) \simeq \mathbb{Z}$.

Remark 1.2.4. If we drop the relative pin structures from our branes, then we expect the corresponding base spectrum to be connective with component group $\mathbb{Z}/2\mathbb{Z}$.

Remark 1.2.5. One import of the above conjecture is that we could then form the base change $\mathsf{Lag}_\Lambda(M) \otimes_{\mathcal{E}} \mathbb{Q}$ to obtain a rational stable ∞-category, or equivalently a rational pre-triangulated differential graded or A_∞-category. This then could be compared to well-known geometric differential graded or A_∞-categories. See Conjecture 1.2.18 below.

Remark 1.2.6. We expect the analysis of the E_∞-ring spectrum $\mathcal{E}$ to follow along the lines of "modern" Pontryagin-Thom theory as developed in [GMTW09, Ga06, Ay08].

1.2.2. *Cotangent bundles.* Here we discuss the structure of $\mathsf{Lag}_\Lambda(M)$ when $M = T^*X$ and $\Lambda \subset T^*X$ is a conical Lagrangian.

Let us first discuss the distinguished case when $\Lambda = X$ is the zero section itself. The above development for $M = \Lambda = pt$ admits a natural generalization which should also be amenable to similar techniques.

Conjecture 1.2.7. *Take $M = T^*X$, $\Lambda = X$ the zero section, and consider $\mathsf{Lag}_X(T^*X)$. Assume for simplicity that X is connected, choose a point $x \in X$, and let $T^*_xX \subset T^*X$ be the corresponding conormal Lagrangian.*

(1) The object $T^*_xX \in \mathsf{Lag}_X(T^*X)$ is a generator.

(2) Every object of $\mathsf{Lag}_X(T^*X)$ is a finite colimit of objects of the form $T^*_xX[k]$, for $k \in \mathbb{Z}$.

(3) The endomorphism algebra $\mathcal{E}nd_{\mathsf{Lag}_X(T^*X)}(T^*_xX)$ *is equivalent to the* E_1*-algebra* $\Omega_x X_* \wedge \mathcal{E}$ *of* $\mathcal{E}$*-chains on the based loop space* $\Omega_x X$*, where* $\mathcal{E} = \mathcal{E}nd_{\mathsf{Lag}_{pt}(pt)}(pt)$*, and* $\Omega_x X_* = \Omega_x X \amalg \{*\}$*.*

Consequently, the Yoneda functor induces an equivalence

$$\mathsf{Lag}_X(T^*X) \simeq \Omega_x X_* \wedge \mathcal{E}\text{-perf}$$

Remark 1.2.8. Together with Conjecture 1.2.3, this would imply that the base change $\mathsf{Lag}_X(T^*X) \otimes_{\mathcal{E}} \mathbb{Q}$ is equivalent to the differential graded category of perfect modules over the differential graded algebra of chains $C_{-*}(\Omega_x X, \mathbb{Q})$. This would be parallel to work [AS06a, AS06b, A09, A10a, A10b] on the wrapped Fukaya category. See Conjecture 1.2.18 below.

Now we would like to generalize Conjecture 1.2.7 when we take a more general conical Lagrangian $\Lambda \subset T^*X$. It will be convenient to adopt the point of view on constructible topology developed in the appendix of [DAGVI]. Let us first reformulate Conjecture 1.2.7 in these terms.

Let $\mathrm{Sing}(X)$ denote the Kan simplicial set of singular simplices on X. We can regard it as an ∞-categorical version of the familiar Poincaré groupoid. If X is connected with base point $x \in X$, then $\mathrm{Sing}(X)$ is equivalent to the ∞-groupoid with a single object x and endomorphisms $\Omega_x X$.

Definition 1.2.9. Let $\mathcal{A}$ be an E_∞-ring spectrum.

(1) The stable ∞-category of *constructible sheaves* of $\mathcal{E}$-modules on X is the continuous functor ∞-category

$$\mathrm{Shv}(X, \mathcal{A}) = \mathrm{Hom}(\mathrm{Sing}(X)^{op}, \mathcal{A}\text{-mod}).$$

(2) The full stable ∞-subcategory $\mathrm{Perf}(X) \subset \mathrm{Shv}(X)$ of *perfect constructible sheaves* of $\mathcal{E}$-modules on X is that generated under finite limits and colimits by representable functors.

Remark 1.2.10. A caution about terminology: the above notion of perfect constructible sheaves does not imply any finiteness on the fibers. For example, the pushforward of the constant sheaf along a map $x \to X$ is perfect though its stalk at x will be $\mathcal{A}$-cochains on the based loop space $\Omega_x X$. In fact, perfect constructible sheaves are precisely what one can obtain by finite limits and colimits of such sheaves.

The following conjecture is equivalent to Conjecture 1.2.7.

Conjecture 1.2.11. *Take* $M = T^*X$*,* $\Lambda = X$ *the zero section, and set* $\mathcal{E} = \mathcal{E}nd_{\mathsf{Lag}_{pt}(pt)}(pt)$

There is a canonical equivalence of stable ∞*-categories*

$$\mathrm{Perf}(X, \mathcal{E}) \xrightarrow{\sim} \mathsf{Lag}_X(T^*X)$$

which sends the constant sheaf on a point $x \in X$ *to the conormal Lagrangian* $T^*_x X \subset T^*X$*.*

Now we are prepared to generalize Conjecture 1.2.7 when we take conical Lagrangians $\Lambda \subset T^*X$ of the following general form. Suppose X is Whitney stratified by strata

$X_\alpha \subset X$, for $\alpha \in A$, and take $\Lambda \subset T^*X$ to be the union of the conormals

$$\Lambda = \coprod_{\alpha \in A} T^*_{X_\alpha} X.$$

Following [DAGVI], let $\mathrm{Sing}^A(X)$ denote the ∞-category of singular simplices adapted to the strata $X_\alpha \subset X$, for $\alpha \in A$. We can regard it as an ∞-categorical version of the "exit path category" of [T09] with morphisms paths exiting singular strata for less singular strata.

Definition 1.2.12. Let $X_\alpha \subset X$, for $\alpha \in A$, be a Whitney stratification, and let $\mathcal{A}$ be an E_∞-ring spectrum.

(1) The stable ∞-category of *A-constructible sheaves* of $\mathcal{E}$-modules on X is the continuous functor ∞-category

$$\mathrm{Shv}_A(X, \mathcal{A}) = \mathrm{Hom}(\mathrm{Sing}^A(X)^{op}, \mathcal{A}\text{-mod}).$$

(2) The full stable ∞-subcategory $\mathrm{Perf}_A(X) \subset \mathrm{Shv}_A(X)$ of *perfect A-constructible sheaves* of $\mathcal{E}$-modules on X is that generated under finite limits and colimits by representable functors.

Conjecture 1.2.13. *Take $M = T^*X$, $\Lambda = \coprod_{\alpha \in A} T^*_{X_\alpha} X$ the union of conormals to a Whitney stratification $X_\alpha \subset X$, for $\alpha \in A$, and set $\mathcal{E} = \mathcal{E}nd_{\mathsf{Lag}_{pt}(pt)}(pt)$.*

There is a canonical equivalence of stable ∞-categories

$$\mathrm{Perf}_A(X, \mathcal{E}) \xrightarrow{\sim} \mathsf{Lag}_\Lambda(T^*X).$$

Remark 1.2.14. Together with Conjecture 1.2.3, this would imply that the base change $\mathsf{Lag}_\Lambda(T^*X) \otimes_{\mathcal{E}} \mathbb{Q}$ is equivalent to the differential graded category of perfect A-constructible sheaves of $\mathbb{Q}$-vector spaces. This would be parallel to work [NZ09, N09] on the Fukaya category of the cotangent bundle. See Conjecture 1.2.18 below.

Finally, before continuing, let us state a refined microlocal version of the above conjecture. We continue with $\Lambda = \coprod_{\alpha \in A} T^*_{X_\alpha} X$ the union of conormals to a Whitney stratification $X_\alpha \subset X$, for $\alpha \in A$.

Consider a conical open subset $U \subset T^*X$. Then we have two ∞-categories which reflect the local geometry of U and are independent of the ambient cotangent bundle. On the one hand, we have the stable ∞-category $\mathsf{Lag}_{U \cap \Lambda}(U)$. On the other hand, we have the ∞-category $\mathrm{Micro}_\Lambda(U, \mathcal{E})$ of perfect microlocal sheaves of $\mathcal{E}$-modules supported along $U \cap \Lambda$. It can be constructed by quotienting sheaves on X with singular support in $\Lambda \cup (T^*X \setminus U)$ by those with singular support in $T^*X \setminus U$. (See [KS84, KS85] for a comprehensive discussion.) Then one must impose finiteness conditions akin to the representability in our notion of perfect constructible sheaf.

Conjecture 1.2.15. *Take $M = T^*X$, $\Lambda = \coprod_{\alpha \in A} T^*_{X_\alpha} X$ the union of conormals to a Whitney stratification $X_\alpha \subset X$, for $\alpha \in A$. Let $U \subset T^*X$ be a conical open subset, and set $\mathcal{E} = \mathcal{E}nd_{\mathsf{Lag}_{pt}(pt)}(pt)$.*

There is a canonical equivalence of stable ∞-categories

$$\mathrm{Micro}_\Lambda(U, \mathcal{E}) \xrightarrow{\sim} \mathsf{Lag}_{U \cap \Lambda}(U).$$

1.2.3. *Locality.* Here we discuss the possibility of recovering $\mathsf{Lag}_\Lambda(M)$ by gluing together $\mathsf{Lag}_{U\cap\Lambda}(U)$, for small open sets $U \subset M$. Such a local-to-global sheaf property is at the technical core of homological algebraic geometry but unfortunately unavavailable in much of homological symplectic geometry, in particular for the partially wrapped Fukaya category (with the exception of some tantalizing developments [FO97, V99, KO99, KO01, Kap05, KW07, NZ09, N09, K09, AS10a, S10, N11] among others). As we understand it, the main obstruction is the presence of instantons (or long distance interactions) in the form of pseudoholomorphic disks, or solutions to related elliptic PDEs. While Lagrangian cobordisms can cover long distances, the idea that they may be assembled from short distance Lagrangian cobordisms is far more elementary than any similar statement for global elliptic PDEs. For example, we expect to have the following evident functoriality of which an analogue in Floer theory is a sophisticated question (for example, see the recent progress [AS10a]).

Conjecture 1.2.16. *Suppose $U \subset M$ is a conical open subset, then inclusion induces a functor*

$$\mathsf{Lag}_{\Lambda\cap U}(U) \longrightarrow \mathsf{Lag}_\Lambda(M).$$

Let $Open^+(M)$ be the category of conical open subsets $U \subset M$, with morphisms given by inclusions. Observe that the intersection of two such open sets is again such an open set.

By a cover $\coprod_{\alpha\in I} U_\alpha \to M$, we mean a finite collection of open sets $U_\alpha \subset M$ such that M is the colimit of the corresponding Cech simplicial space with k-simplices $\coprod_{\underline{\alpha}\in I^k} U_{\underline{\alpha}}$, where $U_{\underline{\alpha}} = U_{\alpha_1} \cap \cdots U_{\alpha_k}$, for $\underline{\alpha} = (\alpha_1, \ldots, \alpha_k)$.

Conjecture 1.2.17. *Let StCat denote the ∞-category of stable ∞-categories. Then the functor*

$$Open^+(M) \longrightarrow StCat \qquad U \longmapsto \mathsf{Lag}_{U\cap\Lambda}(U)$$

forms a cosheaf. In particular, $\mathsf{Lag}_\Lambda(M)$ can be calculated locally: for $\coprod_{\alpha\in I} U_\alpha \to M$ a cover by objects of $Open^+(M)$, $\mathsf{Lag}_\Lambda(M)$ is the colimit of the corresponding Cech simplicial stable ∞-category with k-simplices

$$\textstyle\coprod_{\underline{\alpha}\in I^k} \mathsf{Lag}_{U_{\underline{\alpha}}\cap\Lambda}(U_{\underline{\alpha}}),$$

where $U_{\underline{\alpha}} = U_{\alpha_1} \cap \cdots U_{\alpha_k}$, for $\underline{\alpha} = (\alpha_1, \ldots, \alpha_k)$.

1.2.4. *Relation to partially wrapped Fukaya categories.* Finally, we arrive at one of our primary motivations for considering Lagrangian cobordisms.

We continue with M an exact symplectic manifold with support Lagrangian $\Lambda \subset M$. We will proceed informally and write $WF_\Lambda(M)$ for the corresponding partially wrapped Fukaya category of M (with say rational coefficients). Its construction and basic properties are well-known to experts and explained in [Aur10, AurICM] building on the more well-known wrapped Fukaya category [FSS08b, AS10a]. It is a fundamental object in mirror symmetry and rgeometric representation theory but still mysterious and technically challenging.

Returning to the starting point of Floer theory as Morse theory of path spaces, it appears quite reasonable that Lagrangian cobordisms should play a role in understanding wrapped Floer theory. Roughly speaking, we expect a rough analogy along the lines:

Witten's Morse complex: singular cochains ::
Floer's instanton complex: families of Lagrangian cobordisms

Independently of such vague (and possibly indecipherable) ideas, with suitable assumptions on the Lagrangian branes under consideration, the technique of continuation maps provides a very concrete functor

$$\mathsf{Lag}_\Lambda(M) \longrightarrow WF_\Lambda(M).$$

In fact, the idea that there should be such a functor is the origin of our study of non-characteristic Lagrangian cobordisms.

Conjecture 1.2.18. *Let M be an exact symplectic manifold with Lagrangian support $\Lambda \subset M$. The functor given by continuation maps induces an equivalence of stable ∞-categories*

$$\mathsf{Lag}_\Lambda(M) \otimes_{\mathcal{E}} \mathbb{Q} \xrightarrow{\sim} WF_\Lambda(M)$$

Remark 1.2.19. Our Conjectures 1.2.3, 1.2.7, 1.2.13, and 1.2.18 are compatible thanks to the work [AS06a, AS06b, NZ09, N09, A09, A10a, A10b].

1.3. **Outline of the paper.**

We first take care of the geometric preliminaries and introduce Lagrangian branes in Section 2. For any technical assumptions, the reader can consult this section.

In Section 3, we introduce the notions of Lagrangian cobordism and higher Lagrangian cobordism. In particular we explain the role of the reference Lagrangian $\Lambda \subset M$, defining the notion of *non-characteristic* Lagrangians. We also define the collaring notions needed to define the ∞-category $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$.

In Section 4, we define the ∞-category $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$ organizing Lagrangian cobordisms, and prove it is a weak Kan complex with a zero object. We also explain the notion of compositions via time concatenation. We then construct the *stabilization* $\mathsf{Lag}_\Lambda(M)$.

We then construct a kernel K for any morphism $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$. The construction is carried out in Section 5, and the proof of its universal property is given in Section 6.

Finally, in Section 7, we study the shift functor $\Omega : \mathsf{Lag}_\Lambda(M) \to \mathsf{Lag}_\Lambda(M)$ to prove that $\mathsf{Lag}_\Lambda(M)$ is indeed stable.

In several appendices, we collect useful background material.

1.4. **Acknowledgements.**

We would like to thank Denis Auroux, Kevin Costello and Paul Seidel for their interest.

The first author was supported by NSF grant DMS-0901114 and a Sloan Research Fellowship, and the second author by an NSF Graduate Research Fellowship.

2. Geometric setup

2.1. **Symplectic manifold.** It is possible that Lagrangian cobordisms could be profitably considered in a diverse range of settings. We will restrict to a geometric setup (which we learned from the well-known references [EG91, E97]) where we have some intuition for the situation.

Throughout this paper, M will be an exact symplectic manifold, with symplectic form ω_M, fixed primitive $\omega_M = d\theta_M$, and Liouville vector field Z_M defined by $\omega_M(Z_M, -) = \theta_M(-)$. It is a useful level of generality to assume that Z_M is complete, and so the flow generated by Z_M provides an $\mathbb{R}_{>0}$-action on M. We will use the term *dilation* to refer to the $\mathbb{R}_{>0}$-action, and the term *conical* to refer to sets that are $\mathbb{R}_{>0}$-invariant.

Example 2.1.1. Here are some examples of the exact symplectic manifolds we have in mind (roughly speaking, the first is a mildly degenerate instance of the second):

(1) *Conical subsets of cotangent bundles*: fix a smooth (not necessarily compact) base manifold X, and let $M = T^*X$ be its cotangent bundle equipped with θ_M the canonical one-form. The Liouville vector field Z_M generates the fiberwise dilation. More generally, we could take a conical open subset $U \subset M = T^*X$.

(2) *Conical subsets of Weinstein manifolds*: suppose M admits a proper, bounded-below Morse function $h : M \to \mathbb{R}$ such that Z_M is gradient-like with respect to h. Such data naturally arises when $M \subset \mathbb{C}^n$ is a Stein submanifold or smooth affine complex variety: one can take h to be a perturbation of the restriction of the standard unitary norm on $\mathbb{C}^n$, and θ_M to correspond to the gradient of h via the symplectic form. More generally, we could consider a conical open subset $U \subset M$.

To control the noncompact nature of M, it is useful to assume it is the interior of a manifold with corners $\overline{M}$ such that the dilation $\mathbb{R}_{>0}$-action extends to $\overline{M}$. Furthermore, it is useful to assume that the closures in $\overline{M}$ of any two disjoint conical subsets of M continue to be disjoint. Some convenient notation: we will write $M^\infty = \overline{M} \setminus M$ for the boundary of $\overline{M}$, and given a subset $A \subset M$, we will write $\overline{A}$ for the closure of A inside of $\overline{M}$, and $A^\infty = \overline{A} \setminus A = \overline{A} \cap M^\infty$ for the part of $\overline{A}$ lying in the boundary M^∞.

Remark 2.1.2. *A technical comment*: it will be useful from a technical perspective to assume that $\overline{M}$ embeds as a subanalytic subset of some real analytic manifold N (which without loss of generality we could take to be $\mathbb{R}^n$ for some large n). We will then only consider subsets of M whose closures in N are themselves subanalytic. This obviates the possibility of any "wild" behavior and keeps us in the world of "tame" topology [BM88, VM96].

In order to work with Lagrangian branes inside of M, we will also consider the following standard background structures. Given a compatible almost complex structure $J \in \mathrm{End}(TM)$, we can speak about the complex canonical line bundle $\kappa = (\wedge^{\dim M/2} T^{hol} M)^{-1}$. A bicanonical trivialization η is an identification of the tensor-square $\kappa^{\otimes 2}$ with the trivial complex line bundle. The obstruction to a bicanonical trivialization is twice the first Chern class $2c_1(M) \in H^2(M, \mathbb{Z})$, and all bicanonical trivializations form a torsor over the group $\mathrm{Map}(M, S^1)$. Forgetting the specific compatible almost complex structure $J \in \mathrm{End}(TM)$, we will assume given a section of bicanonical trivializations over the space of all compatible almost complex structures.

We also fix a background class $[c] \in H^2(M, \mathbb{Z}/2\mathbb{Z})$ so as to be able to speak about pin structures relative to $[c]$.

2.2. **Support Lagrangian.**

Throughout this paper, $\Lambda \subset M$ will be a (not necessarily compact, possibly singular) closed Lagrangian subvariety. To be more precise, we suppose the closure $\overline{\Lambda} \subset \overline{M}$ is subanalytic, and hence admits a Whitney stratification into smooth submanifolds. Then we insist that Λ (though not necessarily irreducible) is pure of dimension $\dim M/2$, and each stratum of Λ is isotropic with respect to the symplectic form ω_M. (In fact, we could more generally allow Λ to be simply isotropic, but components of dimension less than $\dim M/2$ will not affect our story.)

Example 2.2.1. Continuing Example 2.1.1, here are some examples of the support Lagrangians we have in mind:

(1) *Conical Lagrangians in cotangent bundles*: take $\Lambda \subset M = T^*X$ to be any closed conical Lagrangian subvariety. In particular, we could take Λ to be the zero section alone. More generally, if $U \subset M = T^*X$ is a conical open subset, we can take the restriction $\Lambda \cap U \subset U$ as support Lagrangian inside of U.

(2) *Conical Lagrangians in Weinstein manifolds*: let $\Lambda^{sk} \subset M$ be the "Lagrangian skeleton" of stable manifolds associated to the exhausting Morse function $h : M \to \mathbb{R}$ (for details, see [Bi01]). We can then take Λ to be the union of Λ^{sk} together with the "cone" with respect to dilation over any Legendrian subvariety in M^∞. More generally, if $U \subset M$ is a conical open subset, we can take the restriction $\Lambda \cap U \subset U$ as support Lagrangian inside of U.

Although we have not discussed any non-conical examples, there is nothing to exclude such a choice.

2.3. **Lagrangian branes.**

A Lagrangian brane inside of M is an exact Lagrangian submanifold $L \subset M$ equipped with several additional structures. To control the possibly noncompact nature of $L \subset M$, we will always assume that it is tame, and its closure $\overline{L} \subset \overline{M}$ is a subanalytic subset. Furthermore, given a support Lagrangian $\Lambda \subset M$, we will only consider Lagrangian branes $L \subset M$ that *are disjoint from* Λ *at infinity* in the sense that $L^\infty = \overline{L} \cap M^\infty$ is disjoint from $\Lambda^\infty = \overline{\Lambda} \cap M^\infty$.

Now a brane structure on such an exact Lagrangian submanifold $L \subset M$ consists of a triple (f, α, q) of additional data:

1. $f : L \to \mathbb{R}$ is a function realizing the exactness of L with respect to the given primitive θ_M;
2. $\alpha : L \to \mathbb{R}$ is a grading with respect to the given trivialization of the complex bicanonical line bundle $\kappa^{\otimes 2}$;
3. q is a relative pin structure with respect to the given background class $[c] \in H^2(M, \mathbb{Z}/2\mathbb{Z})$.

Note that f is determined up to translation by an element of $H^0(L, \mathbb{R})$; α is determined up to translation by an element of $H^0(L, \mathbb{Z})$; and q is determined up to translation by an element of $H^1(L, \mathbb{Z}/2\mathbb{Z})$.

By a Lagrangian brane inside of M, we will mean the object $\mathsf{L} = (L, f, \alpha, q)$. Sometimes we will abuse notation and write $\mathsf{L} \subset M$, or simply L alone in place of L.

2.4. **Product structures.** All of the structures we have introduced in the preceding sections behave naturally with respect to Cartesian products. For concreteness, let us briefly spell this out.

For $i = 1, 2$, given exact symplectic manifolds M_i, ω_i, θ_i, we have the exact symplectic manifold $M_1 \times M_2$, $\omega_1 + \omega_2$, $\theta_1 + \theta_2$. Here and in what follows, we suppress from the notation the pullback of forms along the canonical projections.

Given almost complex structures J_i, bicanonical trivializations τ_i, and background classes $[c_i] \in H^2(M_i, \mathbb{Z}/2\mathbb{Z})$, we take the almost complex structure $J_1 \oplus J_2$, bicanonical trivialization $\tau_1 \wedge \tau_2$, and background class $[c_1] + [c_2] \in H^2(M_1 \times M^2, \mathbb{Z}/2\mathbb{Z})$.

Similarly, for $i = 1, 2$, given Lagrangian branes $L_i \subset M_i$ with brane structures (f_i, α_i, q_i), we have the Lagrangian brane $L_1 \times L_2 \subset M_1 \times M_2$ with brane structure $(f_1 + f_2, \alpha_1 + \alpha_2, q_1 + q_2)$.

2.5. **Euclidean space.** We will often want to consider the symplectic manifold $T^*\mathbb{R}^n$, and so spell out here what structures we equip it with to fit into our setup.

Let $\pi : T^*\mathbb{R}^n \to \mathbb{R}^n$ denote the canonical projection. We have a canonical identification $T^*\mathbb{R}^n \simeq \mathbb{R}^n \times (\mathbb{R}^n)^\vee$ where $(R^n)^\vee$ denotes the linear dual of $\mathbb{R}^n$. We write x_j for the standard coordinates on $\mathbb{R}^n$, and ξ_j for the dual coordinates on $(\mathbb{R}^n)^\vee$.

We work with the standard symplectic form on $T^*\mathbb{R}^n$ given in coordinates by $\omega = \sum_j d\xi_j dx_j$ with standard primitive $\theta = \sum_j \xi_i dx_j$. The Liouville vector field $Z = \sum_j \xi_j \partial_{\xi_j}$ generates the standard fiberwise dilation.

We take the standard complex structure $\mathbb{C}^n \simeq T^*\mathbb{R}^n$ with holomorphic coordinates $z_j = \xi_j + ix_j$. We trivialize the bicanonical bundle $\kappa^{\otimes 2}$ by taking the real line subbundle of the canonical bundle κ induced by the zero section $\mathbb{R}^n \subset T^*\mathbb{R}^n$. In particular, we can identify possible gradings on the zero section with the integers $\mathbb{Z}$ (rather than some arbitrary $\mathbb{Z}$-torsor). There is no choice of background class $[c] \in H^2(T^*\mathbb{R}^n, \mathbb{Z}/2\mathbb{Z})$ since $T^*\mathbb{R}^n$ is contractible. We will usually take the zero section $\mathbb{R}^n \subset T^*\mathbb{R}^n$ as our support Lagrangian Λ.

Here are some of our favorite branes inside of $T^*\mathbb{R}^n$.

Example 2.5.1 (Conormals)**.** The α-graded *conormal brane* $\mathsf{N}_x[\alpha]$ based at $x \in \mathbb{R}^n$ is the Lagrangian submanifold

$$T^*_{\{x\}}\mathbb{R}^n \subset T^*\mathbb{R}^n$$

for some $x \in \mathbb{R}^n$, equipped with the brane structure given by the primitive $f = 0$, grading $\alpha \in \mathbb{Z} + n/2$, and trivial relative pin structure.

More generally, the α-graded *conormal brane* $\mathsf{N}_X[\alpha]$ along a k-dimensional submanifold $X \subset \mathbb{R}^n$ is the Lagrangian submanifold

$$T^*_X\mathbb{R}^n \subset T^*\mathbb{R}^n$$

equipped with the brane structure given by the primitive $f = 0$, grading $\alpha \in \mathbb{Z} + (n - k)/2$, and trivial relative pin structure.

Example 2.5.2 (Graphs)**.** Given a function $h : \mathbb{R}^n \to \mathbb{R}$, the *graph* of its differential is the Lagrangian brane

$$\Gamma_h \subset T^*\mathbb{R}^n$$

with brane structure $(f_h, \alpha_h, [0])$, where f_h is the pullback of h, α_h is transported from the zero grading on the zero section via an isotopy through graphs, and $[0]$ is the trivial relative pin structure.

2.5.1. *Translation and carving.* The previous example leads to a natural construction which we will use throughout our arguments. Suppose $h : \mathbb{R}^n \to \mathbb{R}$ is a function with graph brane $\Gamma_h \subset T^*\mathbb{R}^n$. We can regard $\pi : T^*\mathbb{R}^n \to \mathbb{R}^n$ as a relative group, and consider the fiberwise translation given by adding Γ_h.

Given another Lagrangian brane $\mathsf{L} \subset T^*\mathbb{R}^n$, with brane structure $(f_\mathsf{L}, \alpha_\mathsf{L}, [c_\mathsf{L}])$, we can form the *translated* Lagrangian brane

$$\mathsf{L}_h = \mathsf{L} + \Gamma_h = \{(x, \xi) \in T^*\mathbb{R}^n \,|\, (x, \xi - dh_x) \in \mathsf{L}\}$$

with brane structure $(f_{\mathsf{L},h}, \alpha_{\mathsf{L},h}, [c_\mathsf{L}])$, where $f_{\mathsf{L},h}$ is the sum of f_L and the pullback of h, and $\alpha_{\mathsf{L},h}$ is transported from the grading α_L via an isotopy through graphs.

More generally, given an exact symplectic manifold M, and a Lagrangian brane $\mathsf{L} \subset M \times T^*\mathbb{R}^n$, with brane structure $(f_\mathsf{L}, \alpha_\mathsf{L}, [c_\mathsf{L}])$, we can similarly form the *translated* Lagrangian brane

$$\mathsf{L}_h = \mathsf{L} + \Gamma_h = \{(m, x, \xi) \in T^*\mathbb{R}^n \,|\, (m, x, \xi - dh_x) \in \mathsf{L}\}$$

with brane structure $(f_{\mathsf{L},h}, \alpha_{\mathsf{L},h}, [c_\mathsf{L}])$, where $f_{\mathsf{L},h}$ is the sum of f_L and the pullback of h, and $\alpha_{\mathsf{L},h}$ is transported from the grading α_L via an isotopy through graphs.

More generally still, we will often apply the above construction with a function h which is defined only on an open subset $U \subset \mathbb{R}^n$. In other words, suppose $h : \mathbb{R}^n \to \mathbb{R}$ is a partially defined function, with domain some open subset $U \subset \mathbb{R}^n$. Consider the associated graph brane $\Gamma_h \subset T^*U$.

Then given a Lagrangian brane $\mathsf{L} \subset M \times T^*\mathbb{R}^n$, with brane structure $(f_\mathsf{L}, \alpha_\mathsf{L}, [c_\mathsf{L}])$, we can form the *carved* Lagrangian brane

$$\mathsf{L}_h = \mathsf{L} + \Gamma_h = \{(m, x, \xi) \in M \times T^*U \,|\, (m, x, \xi - dh_x) \in \mathsf{L}|_U\} \subset M \times T^*U$$

with brane structure $(f_{\mathsf{L},f}, \alpha_{\mathsf{L},h}, [c_\mathsf{L}])$, where $f_{\mathsf{L},h}$ is the sum of f_L and the pullback of h, and $\alpha_{\mathsf{L},h}$ is transported from the grading α_L via an isotopy of Γ_h to the zero section through graphs.

We say that L_h is carved from L by the function h. We suppress mention of the domain $U \subset \mathbb{R}^n$ since it is often evident from the structure of h. In any event, we use the term "carved" since we envision that we are using h to remove any part of L that does not live above $U \subset \mathbb{R}^n$.

Of course, one needs to be careful and impose conditions to ensure the carved brane L_h is reasonable. In particular, one needs to be careful that h, L, and their interaction are reasonable at the boundary of $U \subset \mathbb{R}^n$. Rather than trying to systematize this, we will comment as necessary in particular cases.

2.5.2. *Pullbacks.* There are many general things to say about the functoriality of branes, but we will restrict our remarks to what we specifically need.

First, suppose $U \subset \mathbb{R}^m, V \subset \mathbb{R}^n$ are open domains, and $p : U \to V$ is a submersion. It provides a correspondence

$$\begin{tikzcd} T^*U & T^*V \times_V U \arrow[l, "i"'] \arrow[r, "q"] & T^*V \end{tikzcd}$$

in which i is an embedding.

Given a Lagrangian brane $\mathsf{L} \subset T^*V$, we can form the *pullback* Lagrangian brane

$$p^*\mathsf{L} = i(q(\mathsf{L})) \subset T^*U$$

with the evident brane structure pulled back along q.

More generally, given an exact symplectic manifold M, and a Lagrangian brane $\mathsf{L} \subset M \times T^*V$, we can similarly form the *pullback* Lagrangian brane

$$p^*\mathsf{L} = i(q(\mathsf{L})) \subset M \times T^*U$$

with the evident brane structure pulled back along s.

Suppose in addition there is a section $s : V \to U$ to the submersion p. Then we have the left-inverse s^* to the pullback p^*, and we refer to its result as the *restricted* Lagrangian brane

$$s^*(p^*(\mathsf{L})) = \mathsf{L} \subset M \times T^*V.$$

In this case, we will often say that $p^*\mathsf{L}$ is *collared* by L along the subspace $s(V) \subset U$ in the direction of the map p.

Example 2.5.3 (Orthogonal projection)**.** Suppose $p : \mathbb{R}^{m+k} \to \mathbb{R}^m$ is the orthogonal projection.

Given an exact symplectic manifold M, and a Lagrangian brane $\mathsf{L} \subset M \times T^*\mathbb{R}^m$, the pullback Lagrangian brane is simply the product with the zero section

$$p^*\mathsf{L} = \mathsf{L} \times T^*_{\mathbb{R}^k}\mathbb{R}^k \subset M \times T^*\mathbb{R}^{m+k}.$$

The restriction along the section $s : \mathbb{R}^m \to \mathbb{R}^{m+k}$ is simply the original brane

$$s^*(\mathsf{L} \times T^*_{\mathbb{R}^k}\mathbb{R}^k) = \mathsf{L} \subset M \times T^*\mathbb{R}^m.$$

Example 2.5.4 (Rotation via angular projection)**.** Let $\|\cdot\| : \mathbb{R}^n \to \mathbb{R}$ be the Euclidean length function. Fix $0 < a < b$, and consider the annulus and interval

$$U = \{v \in \mathbb{R}^n \mid a < \|v\| < b\} \qquad V = (a, b) \subset \mathbb{R}$$

Suppose $p : U \to V$ is the restriction of $\|\cdot\|$.

Given an exact symplectic manifold M, and a Lagrangian brane $\mathsf{L} \subset M \times T^*V$, we can form the *rotated* Lagrangian brane

$$p^*\mathsf{L} = \mathsf{L} \times T^*_{S^{n-1}}S^{n-1} \subset M \times T^*U.$$

Suppose in addition there is a small $\epsilon > 0$ such that over the open intervals

$$V_a = (a, a+\epsilon) \qquad V_b = (b-\epsilon, b)$$

we have identifications

$$\mathsf{L}|_{V_a} = \mathsf{L}_a \times T^*_{V_a}V_a \qquad \mathsf{L}|_{V_b} = \mathsf{L}_b \times T^*_{V_b}V_b$$

for some Lagrangian branes $\mathsf{L}_a, \mathsf{L}_b \subset M$.

Then we can form a single brane

$$\mathsf{R} \subset M \times T^*\mathbb{R}^n$$



Figure 2.5.5. Collared restriction of $\overline{p}^*\mathsf{P}$ to the first quadrant.

by gluing together $p^*\mathsf{L}$ over the annulus U with the product branes

$$\mathsf{L}_a \times T^*_{W_a} W_a \qquad \mathsf{L}_b \times T^*_{W_b} W_b$$

defined over the domains

$$W_a = \{v \in \mathbb{R}^n \,|\, \|v\| < a\} \qquad W_b = \{v \in \mathbb{R}^n \,|\, b < \|v\|\}$$

Finally, there are myriad variations on this theme. For instance, a useful further construction is to consider the restriction $\mathsf{R}|_Q$ of the rotated Lagrangian brane R to a quadrant $Q \subset \mathbb{R}^n$. With a slight tweak of the original function p, we can achieve that $\mathsf{R}|_Q$ is collared along the boundary of the quadrant in the normal directions.

See Figure 2.5.5 in the case $n = 2$ and $Q = \{(x, y) \in \mathbb{R}^2 \,|\, x, y > 0\}$. By a small perturbation, we have arranged so that there is $\epsilon > 0$ so that over the boxes

$$(a, b) \times (0, \epsilon) \qquad (0, \epsilon) \times (a, b)$$

the rotated brane $\mathsf{R}|_Q$ is the collared product

$$\mathsf{L} \times T^*_{(0,\epsilon)}(0, \epsilon) \qquad T^*_{(0,\epsilon)}(0, \epsilon) \times \mathsf{L}$$

This particular example will arise in our constructions of kernels in Section 5.3.

Remark 2.5.6 (Pictures of graphs)**.** Via the usual metric on $\mathbb{R}^n$, we can transform one-forms into vector fields, and exact one-forms into gradient vector fields. In our initial proofs, we will write fairly explicit formulas for one-forms, while in later proofs, we will often draw qualitatively meaningful vector fields and leave to the reader the choice of their precise realization.

Here are some sample functions $h(t,x)$ of two variables to give the reader a sense of how to interpret our pictures. We will draw large arrows to denote places where a vector field shoots off to infinity in the indicated direction, and (when necessary) small arrows to highlight where the vector field is non-zero in the indicated direction. Let us fix an auxiliary smooth, non-decreasing function $\tau : \mathbb{R} \to \mathbb{R}$ such that

$$\tau^{-1}(0) = (-\infty, 0] \qquad \tau^{-1}(1) = [1, \infty).$$

In the figures below we depict the 1-form dh for various functions h. The shaded regions indicate the domains on which dh is defined.



Figure 2.5.7. A drawing of dh, where $h(t,x) = -\log(1 - \tau(t))$.



Figure 2.5.8. A drawing of dh for $h(t, x) = \log(1 - \tau(t))$.



Figure 2.5.9. A drawing of dh for $h(t, x) = -\log(1 - \tau(t)\tau(x))$



Figure 2.5.10. A drawing of dh for $h(t, x) = \log(1 - \tau(t)\tau(x))$.

3. Lagrangian cobordisms

Throughout this section, we adopt the geometric setup of the previous section.

3.1. **Cubical collaring.** Fix n, a pair of vectors $\mathsf{a} = (a_1, \dots, a_n), \mathsf{b} = (b_1, \dots, b_n) \in \mathbb{R}^n$ with $a_i < b_i$ for all i. Consider the n-dimensional rectangular solid

$$R = [a_1, b_1] \times \cdots \times [a_n, b_n] \subset \mathbb{R}^n.$$

We will write $R^\circ \subset R$ for its interior, and T^*R° for the cotangent bundle of R°.

The facets $R_\beta \subset R$ correspond to maps

$$\beta : \{1, \dots, n\} \longrightarrow \{a, *, b\}$$

by the rule $x \in R$ lies in R_β if and only if $x_i = \beta(i)_i$ when $\beta(i)$ is equal to a or b, or $x_i \in (a_i, b_i)$ when $\beta(i) = *$. So in particular, the interior R° is simply R_β when β is constantly equal to $*$.

Given a facet $R_\beta \subset R$, by a *collaring neighborhood* $U_\beta \subset R$ we will mean an open subset containing R_β such that $\pi_\beta(U_\beta) = R_\beta$, where π_B is the orthogonal projection restricted to U_β.

Definition 3.1.1 (Cubical collaring)**.** Suppose given a Lagrangian brane

$$\mathsf{P} \subset M \times T^*R^\circ.$$

We say that P is *collared* if for each facet $R_\beta \subset R$, there is a Lagrangian brane

$$\mathsf{P}_\beta \subset M \times T^*R_\beta,$$

and collaring neighborhood $U_\beta \subset R$ such that we have an identity of branes

$$\mathsf{P}|_{R^\circ \cap U_\beta} = \pi_\beta^* \mathsf{P}_\beta = \mathsf{P}_\beta \times T^*_{N_\beta} N_\beta$$

where N_β is the affine space orthogonal to the facet F_β.

Observe that if a Lagrangian brane $\mathsf{P} \subset M \times T^*R^\circ$ is collared, then the collaring branes $\mathsf{P}_\beta \subset M \times T^*R_\beta$ are uniquely determined. When working with collared Lagrangian branes, we will often abuse notation and write $\mathsf{P} \subset T^*R$ rather than indicating the interior $R^\circ \subset R$.

3.2. **Convex preliminaries.** In order to refine the behavior of Lagrangian branes living over a rectangular solid, we will need to gather some preliminaries. The reader could skip to the next section and refer back to this one as needed.

Let $[n]$ denote the ordered set $\{0, 1, \dots, n\}$. We will think of elements of $[n]$ as the vertices of the n-simplex Δ^n.

Let $\mathcal{P}(n)$ denote the power set of subsets $J \subset [n]$. We will think of elements of $J \in \mathcal{P}(n)$ as the vertices of a facet $\Delta(J) \subset \Delta^n$. We will write J^{min} and J^{max} for the minimum and maximum elements of J respectively.

Let $\mathcal{Q}(n) \subset \mathcal{P}(n)$ denote those subsets $I \subset [n]$ such that $0, n \in I$. Here are two alternative ways to think of an element $I \in \mathcal{Q}(n)$. On the one hand, I encodes a path (directed sequence of vertices) in Δ^n from the initial vertex 0 to the terminal vertex n. On the other hand, I encodes a vertex $v(I)$ of the $(n-1)$-cube

$$c(n-1) = [0, 1]^{n-1} \subset \mathbb{R}^{n-1}$$

by setting $v(I)_j$ equal to 1 if $j \in I$ and 0 if $j \notin I$.

Consider the incidence set

$$\mathcal{Q}(n)_* = \{(I,k) \in \mathcal{Q}(n) \times [n] \,|\, k \in I\}.$$

On the one hand, an element of $\mathcal{Q}(n)_*$ encodes a path I in the n-simplex Δ^n together with a marked vertex k on the path. On the other hand, $\mathcal{Q}(n)_*$ encodes a point $v(I,k) = (v(I),k)$ of the n-dimensional rectangular solid

$$C(n) = c(n-1) \times [0,n] = [0,1]^{n-1} \times [0,n] \subset \mathbb{R}^n.$$

Let us next turn to the facets of the $(n-1)$-cube $c(n-1)$.

Recall that vertices $v(I) \in c(n-1)$ correspond to $I \in \mathcal{Q}(n)$ by setting $v(I)_j$ equal to 1 if $j \in I$ and 0 if $j \notin I$. Let us represent $I \in \mathcal{Q}(n)$ by a path of 1-subsimplices

$$\{0,i_1\},\{i_1,i_2\},\ldots,\{i_{\ell-1},n\} \in \mathcal{P}(n), \quad \text{where } I = \{0 < i_1 < i_2 < \cdots < i_{\ell-1} < n\}.$$

More generally, a chain β of subsimplices is a sequence of subsimplices

$$J_1, J_2, \ldots, J_\ell \in \mathcal{P}(n)$$

satisfying the following:

1. $|J_a| > 1$ for any $a = 1,\ldots,\ell$,
2. $J_1^{min} = 0$, $J_\ell^{max} = n$,
3. $J_a^{max} = J_{a+1}^{min}$, for any $a = 1,\ldots,\ell-1$,
4. if $a < b$, then $j_a \leq j_b$, for any $j_a \in J_a$, $j_b \in J_b$.

The facets of the $(n-1)$-cube $c(n-1)$ are in bijection with such chains: given a chain β, the corresponding facet $f(\beta) \subset c(n-1)$ is the convex hull of the vertices $v(I)$ corresponding to paths I through the subsimplices in β. More precisely, $v(I)$ is a vertex of $f(\beta)$ if for each $i_a \in I$, there is some subsimplex J_b in the chain β such that $i_a, i_{a+1} \in J_b$. The dimension of the facet $f(\beta)$ is the sum

$$\dim f(\beta) = \sum_{a=1}^{\ell} (|J_a| - 1)$$

By a vertical facet of the rectangular solid $C(n) = c(n-1) \times [0,n]$, we mean a facet of the form

$$F(\beta) = f(\beta) \times [0,n].$$

Given a subsimplex J appearing in a chain β, form the rectangular solid

$$F(\beta, J) = \{(x,t) \in F(\beta) \,|\, t \in [J^{min}, J^{max}]\}.$$

We will call $F(\beta,J)$ a refined facet of the rectangular solid $C(n)$. As we vary J, the collection of refined facets $F(\beta,J)$ form a cubical refinement of the vertical facet $F(\beta)$.

Finally, we will introduce the trivial directions within a refined facet $F(\beta,J)$. Let us write $C(J)$ for the $(|J|-1)$-dimensional rectangular solid

$$C(J) = [0,1]^{|J|-2} \times [J^{min}, J^{max}] \subset \mathbb{R}^{|J|-1}.$$

By construction, we have a natural orthogonal projection

$$p(\beta,J) : F(\beta,J) \longrightarrow C(J)$$

respecting projection onto the last coordinate direction. It forgets the variable directions x_i for those indices $i \in \{1, \ldots, n-1\}$ such that $i \notin J$.

3.3. **Factorization.** Now we are ready to refine the behavior of Lagrangian branes living over a rectangular solid. We adopt the notation of the previous section.

Recall that we work with the $(n-1)$-cube

$$c(n-1) = [0,1]^{n-1} \subset \mathbb{R}^{n-1}$$

and the n-dimensional rectangular solid

$$C(n) = c(n-1) \times [0,n] = [0,1]^{n-1} \times [0,n] \subset \mathbb{R}^n.$$

Fix Lagrangian branes $\mathsf{L}_0, \mathsf{L}_n \subset M$.

Definition 3.3.1 (Factorized Lagrangian n-cobordism)**.** A factorized Lagrangian n-cobordism from L_0 to L_n is a collared Lagrangian brane

$$\mathsf{P} \subset M \times T^*C(n)$$

satisfying the following.

(1) Along the face $c(n-1) \times \{0\} \subset C(n)$, P is collared by

$$\mathsf{L}_0 \times T^*_{c(n-1)} c(n-1),$$

and along the face $c(n-1) \times \{n\} \subset C(n)$, P is collared by

$$\mathsf{L}_n \times T^*_{c(n-1)} c(n-1).$$

(2) For all $J \in \mathcal{P}(n)$, there is a collared Lagrangian brane

$$\mathsf{P}_J \subset M \times T^*C(J)$$

such that for all vertical facets $F(\beta) \subset C(n)$, the restriction of the collaring brane P_β to the refined facet $F(\beta, J) \subset F(\beta)$ is equal to the pullback brane

$$\mathsf{P}_\beta|_{F(\beta,J)} = p(\beta, J)^* \mathsf{P}_J.$$

A factorized Lagrangian n-cobordism P from L_0 to L_n contains a lot of information that may not be apparent at first glance. For instance, it contains the information of intermediate Lagrangian branes

$$\mathsf{L}_1, \ldots, \mathsf{L}_{n-1} \subset M.$$

Namely, for $k \in \{1, \ldots, n-1\}$, consider the vertex $v(I) \in c(n-1)$ corresponding to $I = \{0, k, n\} \subset [n]$. Then the intermediate brane $\mathsf{L}_k \subset M$ appears as a collaring brane at the point $(v(I), k)$.

Example 3.3.2. For instance, when $n = 4$, the facet defined by the function

$$\beta(i) = \begin{cases} (0,1) & i = 1, 3 \\ \{1\} & i = 2 \end{cases}$$

can be split into two parts by $t \in [0,2]$ and $t \in [2,4]$. One sees that this facet is described completely by extending the Lagrangians associated to $J = [012] \subset \Delta^4$ and $J' = [234] \subset \Delta^4$, composing them appropriately.

Some low-dimensional examples are illustrated in Figures 3.3.3 and 3.3.4.



Figure 3.3.3. A factorized 2-cobordism P from L_0 to L_2, projected onto $C(2) \subset \mathbb{R}^2$. The indicated vertices are collared by the Lagrangians L_i for $i = 0, 1, 2$ and the indicated facets P_J are collared by $J = \{0,1\}, \{0,2\}, \{1,2\}$.



Figure 3.3.4. A factorized 3-cobordism P from L_0 to L_3, projected on to $C(3) \subset \mathbb{R}^3$. We have indicated how the various edges and vertices are collared. Note that grey shaded regions are idential to $P_{01} \times \mathbb{R}$ and $P_{23} \times \mathbb{R}$.

3.4. **Time symmetries.** We continue with the notation of the previous sections.

Set Diff(0) to be the trivial group, and let Diff(1) denote the group of orientation-preserving diffeomorphisms of the interval $[0,1]$ that are the identity in some neighborhood of the end points $\{0,1\} \subset [0,1]$.

Here is an inductive generalization for $n > 1$. Let Diff(n) denote the group of orientation-preserving diffeomorphisms of the n-dimensional rectangular solid

$$\varphi : C(n) \xrightarrow{\sim} C(n)$$

that satisfy the following:

(1) *time symmetry*: φ respects the orthogonal projection to the $(n-1)$-cube $c(n-1)$ in the sense that there is a map

$$\gamma : C(n) \longrightarrow [0,n]$$

such that we have

$$\varphi(x,r) = (x, \gamma(x,r)), \qquad (x,r) \in C(n).$$

In particular, φ restricts to a diffeomorphism of each vertical facet $F(\beta) \subset C(n)$.

(2) *preserves collaring*: (a) for each vertical facet $F(\beta) \subset C(n)$, there is a collaring neighborhood $U(\beta) \subset C(n)$ such that φ respects the orthogonal projection

$$\pi(\beta) : U(\beta) \longrightarrow F(\beta)$$

in the sense that

$$\pi(\beta) \circ \varphi = \varphi \circ \pi(\beta).$$

(b) there are open neighborhoods of the faces

$$c(n-1) \times \{0\}, c(n-1) \times \{n\} \subset C(n)$$

on which φ is the identity.

(3) *preserves refined facets*: φ restricts to a diffeomorphism of each refined facet

$$F(\beta, J) \subset C(n).$$

(4) *preserves trivial directions of refined facets*: for each refined strata

$$F(\beta, J) \subset C(n),$$

there is an element

$$\varphi(\beta, J) \in \mathrm{Diff}(|J| - 1)$$

such that we have

$$\varphi|_{F(\beta,J)} = p(\beta, J)^* \varphi(\beta, J)$$

under the projection

$$p(\beta, J) : F(\beta, J) \longrightarrow C(J).$$

We will refer to elements $\varphi \in$ Diff(n) as *time reparametrizations*. Any time reparametrization $\varphi \in$ Diff(n) induces a symplectomorphism

$$\varphi^* : M \times T^*C(n) \xrightarrow{\sim} M \times T^*C(n)$$

respecting all of the structures in play. Thus for $\mathsf{L}_0, \mathsf{L}_n \subset M$ fixed Lagrangian branes, φ^* induces a bijection on the set of factorized Lagrangian n-cobordisms from L_0 to L_n.

Definition 3.4.1 (Lagrangian n-cobordism)**.** A *Lagrangian n-cobordism* is an equivalence class of factorized Lagrangian n-cobordisms under the action of the group $\mathrm{Diff}(n)$.

It follows that the notion of Lagrangian n-cobordism is independent of the particular choice of timescale. More precisely, if we produce a factorized Lagrangian n-cobordism with some alternative ordered embedding of the set $[n] = \{0, 1, \ldots, n\}$ inside of the real line $\mathbb{R}$, we can unambiguously transport it to a Lagrangian n-cobordism living over the standard rectangular solid $C(n)$. As we will see in Section 4.1 below, one immediate consequence is that Lagrangian cobordisms naturally form simplicial sets.

Remark 3.4.2. It would have been equally reasonable to quotient by the natural action of the larger group of all diffeomorphisms of the n-dimensional rectangular solid $C(n)$ that preserve all of the additional structures in play. In other words, we could dispense with the first condition (called *time symmetry*) of the definition of $\mathrm{Diff}(n)$ and consider a larger class of so-called space-time symmetries.

There is the usual trade-off to such a choice: on the one hand, if we enlarge an equivalence class, we obtain more flexibility in describing a geometric representative; on the other hand, the equivalence class becomes that much further from the explicit geometric representative.

Philosophically speaking, it is more appealing to have the definitions be as concrete as possible and so not build unnecessary symmetries into them. Then any further symmetries should appear as properties of the resulting structure. Here we have quotiented by time reparametrizations to provide the quickest path to a well defined simplicial set.

3.5. **Non-characteristic propagation.** Now we introduce the Lagrangian variety $\Lambda \subset M$ into the story. Recall that a variety $\Lambda \subset M$ is said to be Lagrangian if it is purely half-dimensional and for any and hence all stratifications of Λ into submanifolds the symplectic form ω vanishes on each of the strata.

Recall the n-dimensional rectangular solid $C(n) = c(n-1) \times [0, n]$. We will write t for the standard coordinate on the factor $[0, n]$.

Let $\mathrm{Flow}(1)$ denote the set of closed (hence exact) one-forms on $[0, 1]$ that are equal to dt in some neighborhood of the end points $\{0, 1\} \subset [0, 1]$.

Here is an inductive generalization for $n > 1$. Let $\mathrm{Flow}(n)$ denote the set of closed (hence exact) one-forms $\eta \in \Omega^1(C(n))$ satisfying the following:

(1) *respects collaring*: for each vertical facet $F(\beta) \subset C(n)$, there is a collaring neighborhood $U(\beta) \subset C(n)$ such that

$$\eta|_{U(\beta)} = \pi(\beta)^*(\eta|_{F(\beta)})$$

under the orthogonal projection

$$\pi(\beta) : U(\beta) \longrightarrow F(\beta).$$

(2) *respects trivial directions of refined facets*: for each refined strata

$$F(\beta, J) \subset C(n),$$

there is an element

$$\eta(\beta, J) \in \mathrm{Flow}(|J| - 1)$$

such that we have

$$\eta = p(\beta, J)^*\eta(\beta, J)$$

under the projection

$$p(\beta, J) : F(\beta, J) \longrightarrow C(J).$$

Now given $\eta \in \mathrm{Flow}(n)$ and a Lagrangian brane

$$\mathsf{P} \subset M \times T^*C(n)$$

we can form the fiber-wise translation

$$\mathsf{P} + \eta = \{(m, x, \xi + \eta(x)) \in M \times T^*C(n) \,|\, (m, x, \xi) \in \mathsf{P}\}.$$

We do not discuss the brane structures because all we will care about is the underlying Lagrangian submanifold.

Definition 3.5.1 (Non-characteristic cobordisms)**.** A Λ-*non-characteristic* factorized Lagrangian n-cobordism is a factorized Lagrangian n-cobordism

$$\mathsf{P} \subset M \times T^*C(n)$$

for which there exists an element $\eta \in \mathrm{Flow}(n)$ such that

$$(\mathsf{P} + \eta) \cap (\Lambda \times T^*_{C(n)}C(n)) = \emptyset.$$

The notion is invariant under the action of $\mathrm{Diff}(n)$, and hence descends to provide the notion of a Λ-*non-characteristic Lagrangian n-cobordism.*

As defined above, the notion of Λ-non-characteristic is a property rather than a structure. There is the familiar trade-off: on the one hand, it can be convenient to have a specific $\eta \in \mathrm{Flow}(n)$ in hand to perform further constructions such as gluing together Λ-non-characteristic Lagrangian n-cobordisms; on the other hand, if we can verify enough such gluing to get off the ground, then our later arguments will be simpler since we will not need to carry around the extra structure of a specific $\eta \in \mathrm{Flow}(n)$.

As formalized in the above definition, we have opted for the latter approach of taking Λ-non-characteristic to be a property. It turns out that all of the gluings we will need can be recast to fit under the umbrella of the following extension lemma. Here is an explanation of the notation appearing in its statement: S^n denotes the n-sphere, $[0, h]_t$ denotes the interval for $h > 0$ with coordinate t, and $[a_0, a_1]_s$ denotes the interval for $a_0 < a_1$ with coordinate s; we also simplify the notation by writing a manifold Z in place of the zero section $T^*_Z Z \subset T^*Z$.

Lemma 3.5.2. *Suppose* P *is a Lagrangian brane inside of* $M \times T^*S^n \times T^*[0, h]_t$.

Suppose for $i = 0, 1$*, there are exact one forms* $\eta_i \in \Omega^1(S^n \times [0, h]_t)$ *equal to* dt *near the end points of the interval* $\{0, h\} \subset [0, h]_t$*, and such that*

$$(\mathsf{P} + \eta_i) \cap (\Lambda \times S^n \times [0, h]_t) = \emptyset.$$

Then for any $a_0 < a_1$*, there is an exact one-form* $\eta \in \Omega^1(S^n \times [0, h]_t \times [a_0, a_1]_s)$ *equal to* dt *near the end points of the interval* $\{0, h\} \subset [0, h]_t$*, equal to* η_i *near the boundary point* $a_i \subset [a_0, a_1]_s$ *for* $i = 0, 1$*, and such that*

$$((\mathsf{P} \times [a_0, a_1]_s) + \eta) \cap (\Lambda \times S^n \times [0, h]_t \times [a_0, a_1]_s) = \emptyset.$$

Proof. Let $f_0(x,t), f_1(x,t) : S^n \times [0,h]_t \to \mathbb{R}$ be primitives for η_0, η_1 respectively such that

$$f_0(x,t) \gg 0 \qquad f_1(x,t) \ll 0$$

Choose $0 < \epsilon < (a_1 - a_0)/2$, and a smooth, non-decreasing function $\alpha_0 : [a_0, a_1] \to \mathbb{R}$ such that

$$\alpha_0(x) = \begin{cases} 0, & s \leq a_0 + \epsilon \\ 1, & s \geq a_1 - \epsilon \end{cases}$$

Set $\alpha_1 = 1 - \alpha_0 : [a_0, a_1] \to \mathbb{R}$.

Take $\eta \in \Omega^1(S^n \times [0,h]_t \times [a_0, a_1]_s)$ to be the exact one-form

$$\eta = d(\alpha_0(s) f_0(x,t) + \alpha_1(s) f_1(x,t)) \in \Omega^1(S^n \times [0,h]_t \times [a_0, a_1]_s)$$

It is straightforward to check that η has the asserted properties, and in particular

$$((\mathsf{P} \times [a_0, a_1]_s) + \eta) \cap (\Lambda \times S^n \times [0,h]_t \times [a_0, a_1]_s) = \emptyset.$$

□

3.6. **Basic examples.** We record here some basic examples of Lagrangian 1-cobordisms.

Example 3.6.1 (The identity 1-cobordism)**.** For any Lagrangian brane $\mathsf{L} \subset M$, we have the Lagrangian 1-cobordism

$$\mathsf{L} \times T^*_{\mathbb{R}}\mathbb{R} \subset M \times T^*\mathbb{R}$$

obtained by taking the product of L with the zero section equipped with its canonical brane structure. We refer to $\mathsf{L} \times T^*_{\mathbb{R}}\mathbb{R}$ as the *identity cobordism* of the brane L.

Example 3.6.2 (The twist)**.** Let ν_l be a smooth, increasing function such that $\nu_l^{-1}(0) = (-\infty, -\epsilon]$ and $\nu_l^{-1}(1) = [0, \infty)$. Also let ν_r be a smooth, increasing function such that $\nu_r^{-1}(0) = (-\infty, 0]$ and $\nu_r^{-1}(1) = [\epsilon, \infty)$. Define the 1-form ν by $\nu = -d\log(\nu_l) - d\log(1 - \nu_r)$. Its graph Γ_ν is a Lagrangian in $T^*\mathbb{R}$ which approaches ∞ at $t = \epsilon$ and approaches $-\infty$ at $-\epsilon$. Fix a grading and primitive such that the two equal 0 where Γ_ν intersects the zero section.

The Lagrangian Γ_ν is clearly Hamiltonian-isotopic to the Lagrangian $T^*_{\{0\}}\mathbb{R}$, the vertical fiber over $0 \in \mathbb{R}$. The vertical fiber in turn is Hamiltonian isotopic to another Lagrangian, $\Gamma_{\nu'}$, obtained by graphing a 1-form $\nu'(t) = \nu(-t)$. The Hamiltonian isotopy taking Γ_ν to $T^*_{\{0\}}\mathbb{R}$ to $\Gamma_{\nu'}$ can be realized as a Lagrangian cobordism in $T^*\mathbb{R} \times T^*\mathbb{R}$.

The significance of this example is that the grading on $\Gamma_{\nu'}$ at the origin differs from the grading on Γ_ν at the origin. The former has changed by a full period of the circle. We will call this the *twist*, or the *ribbon morphism*, because it looks like a twisting ribbon when depicted as a vector field in $\mathbb{R}^2$. (See Figure 3.6.3.)



Figure 3.6.3. A projection onto $T^*\mathbb{R}_t \times T^*\mathbb{R}_s$ of the *ribbon morphism*, which we also call the *twist* from a rightward tilt of X to a leftward tilt of X. Time evolves from bottom to top, and the horizontal direction represents the spatial, or stabilizing, direction.

4. ∞-category of Lagrangian cobordisms

In this section, we build an ∞-category (synonymously, quasicategory or weak Kan complex) whose n-simplices label Lagrangian n-cobordisms. The patterns arising are inspired by the construction of simplicial nerves of simplicial categories. (We review some of the basic notions of ∞-categories and simplicial nerves in the Appendix.) The factorizations of the previous section will enable us to organize Lagrangian n-cobordisms into a simplicial set. The collarings of the previous section will enable us to show that the simplicial set is a weak Kan complex.

Roughly speaking, we will define an ∞-category $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$ whose objects are appropriate Lagrangian branes $\mathsf{L} \subset M$. Its 1-morphisms $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ are Lagrangian cobordisms $\mathsf{P} \subset M \times T^*[0,1]$ between these branes. In general for $n > 1$, its n-morphisms are cubical Lagrangian cobordisms parametrizing between $(n-1)$-morphisms. Since we work within the framework of an ∞-category (rather than an (∞, n)-category with $n > 1$), the morphisms between two objects $\mathsf{Lag}^{\diamond 0}(\mathsf{L}_0, \mathsf{L}_1)$ form a space of cobordisms (rather than an $(\infty, n-1)$-category with $n > 1$) – for instance, one can view a 2-morphism as a path between 1-morphisms.

4.1. **Weak Kan property.**

We continue with the geometric setup introduced in Section 2. We fix the symplectic manifold M and support Lagrangian Λ, setting $\mathsf{Lag}^{\diamond 0} = \mathsf{Lag}_\Lambda^{\diamond 0}(M)$.

Remark 4.1.1. The superscript "$\diamond 0$" reflects the fact that $\mathsf{Lag}^{\diamond 0} = \mathsf{Lag}_\Lambda^{\diamond 0}(M)$ is associated to $M = M \times T^*\mathbb{R}^0$ and $\Lambda = \Lambda \times \mathbb{R}^0$. Later, we will consider the sequence of ∞-categories $\mathsf{Lag}^{\diamond k} = \mathsf{Lag}_\Lambda^{\diamond k}(M)$ associated to $M^{\diamond k} = M \times T^*\mathbb{R}^k$ and $\Lambda^{\diamond k} = \Lambda \times T^*_{\mathbb{R}^k}\mathbb{R}^k$.

Definition 4.1.2 (Simplices)**.** We define the set $\mathsf{Lag}^{\diamond 0}(0)$ of 0-simplices to consist of Lagrangian branes $\mathsf{L} \subset M$.

For $n > 0$, we define the set $\mathsf{Lag}^{\diamond 0}(n)$ of n-simplices to consist of Λ-non-characteristic Lagrangian n-cobordisms.

We next construct the simplicial structure maps of $\mathsf{Lag}^{\diamond 0}$. Given $\sigma : [m] \to [n]$ a morphism (order-preserving map of finite sets) in the simplicial category, we will define a corresponding map of sets

$$\sigma^* : \mathsf{Lag}^{\diamond 0}(n) \longrightarrow \mathsf{Lag}^{\diamond 0}(m).$$

For concreteness, let us first describe the face and degeneracy maps. Fix n, and consider the standard order-preserving face inclusion

$$d_i : [n-1] \to [n], \qquad \text{for } i = 0, \dots, n,$$

for which $i \in [n]$ is not in the image, and the standard order-preserving degeneracy surjection

$$s_i : [n] \to [n-1], \qquad \text{for } i = 0, \dots, n-1,$$

for which $i \in [n-1]$ has two pre-image elements.

Recall that an n-simplex of $\mathsf{Lag}^{\diamond 0}$ is represented by a Λ-non-characteristic factorized Lagrangian n-cobordism $\mathsf{P} \subset M \times T^*C(n)$. By definition, P satisfies the following two boundary conditions.

(1) Along the face

$$c(n-1) \times \{0\} \subset C(n) = c(n-1) \times [0,n]$$

P is collared by a brane

$$\mathsf{L}_0 \times T^*_{c(n-1)} c(n-1) \subset M \times T^* c(n-1)$$

and along the face

$$c(n-1) \times \{n\} \subset C(n) = c(n-1) \times [0,n]$$

P is collared by a brane

$$\mathsf{L}_n \times T^*_{c(n-1)} c(n-1) \subset M \times T^* c(n-1)$$

(2) For all $J \subset [n]$, there is a brane

$$\mathsf{P}_J \subset M \times T^* C(J)$$

such that along all refined facets $F(\beta, J) \subset C(n)$, the restriction of P is equal to the pullback brane

$$\mathsf{P}|_{F(\beta,J)} = p(\beta, J)^* \mathsf{P}_J$$

along the natural projection

$$p(\beta, J) : F(\beta, J) \to C(J).$$

Definition 4.1.3 (Face maps)**.** For $n = 1$, we define the face maps

$$d_0^*, d_1^* : \mathsf{Lag}^{\diamond 0}(1) \to \mathsf{Lag}^{\diamond 0}(0) \qquad d_0^*(\mathsf{P}) = \mathsf{L}_0, d_1^*(\mathsf{P}) = \mathsf{L}_1.$$

where $\mathsf{L}_0, \mathsf{L}_1 \subset M$ are the collaring branes.

Fix $n > 1$, and any $i \in [n]$. Set $J = [n] \setminus i$. We define the face map

$$d_i^* : \mathsf{Lag}^{\diamond 0}(n) \to \mathsf{Lag}^{\diamond 0}(n-1) \qquad d_i^*(\mathsf{P}) = \mathsf{P}_J$$

where $\mathsf{P}_J \subset M \times T^* C(J)$ is the collaring brane. By applying a time reparametrization, we may identify $C(J)$ with the standard rectangular solid $C(|J|-1)$, and hence consider P_J as a Lagrangian $(|J|-1)$-cobordism.

Remark 4.1.4. In general, for an arbitrary inclusion $\sigma : J \hookrightarrow [n]$ in the simplicial category, we can take $\sigma^*(\mathsf{P})$ to be a time reparametrization of the collaring brane $\mathsf{P}_J \subset M \times T^* C(J)$.

To define degeneracy maps, we gather some preliminaries.

First, it is useful to explicitly describe the standard triangulation of the $(n-1)$-cube $c(n-1)$. Recall that vertices $v(I) \in c(n-1)$ correspond to subsets $I \subset [n]$ containing both $0, 1 \in [n]$. With this indexing, the k-simplices of the standard triangulation of $c(n-1)$ have vertices indexed by increasing sequences of subsets $I_1 \subset I_2 \subset \cdots I_k \subset [n]$.

Observe that a simplicial map $\sigma : [m] \to [n]$ induces a map from subsets of $[m]$ to subsets of $[n]$, and in turn a simplicial map

$$c(\sigma) : c(m-1) \longrightarrow c(n-1)$$

with respect to the standard triangulations. In general, the map $c(\sigma)$ is not a simple orthogonal projection (and not even smooth), but linear on each simplex in the domain.

Second, given a factorized Lagrangian $(n-1)$-cobordism $\mathsf{P} \subset M \times T^*C(n-1)$, and some $i = 1, \ldots, n-2$, we will choose a time reparametrization so as to stretch P to a brane in a longer time interval

$$\mathsf{P}'_i \subset M \times T^*(c(n-1) \times [0,n])$$

More precisely, we can choose a small $\epsilon > 0$, and a smooth embedding of intervals

$$p_i : [0,n] \hookrightarrow [0,n-1]$$

such that $p_i(t) = t$, for $t < i - \epsilon$, and $p_i(t) = t - 1$, for $t > i + 1 + \epsilon$. Then we will take the pullback $\mathsf{P}'_i = p_i^*(\mathsf{P})$ along the induced map

$$p_i : c(n-1) \times [0,n] \longrightarrow c(n-1) \times [0,n].$$

When $i = 0$, we can produce a similar brane

$$\mathsf{P}'_0 \subset M \times T^*(c(n-1) \times [0,n])$$

by translating P to the time interval $[1,n]$, and then gluing to it the constant brane

$$\mathsf{L}_0 \times T^*_{c(n-1)\times[0,1]}(c(n-1) \times [0,1]).$$

When $i = n-1$, we can produce a similar brane

$$\mathsf{P}'_{n-1} \subset M \times T^*(c(n-1) \times [0,n])$$

by gluing to P the constant brane

$$\mathsf{L}_{n-1} \times T^*_{c(n-1)\times[n-1,n]}(c(n-1) \times [n-1,n]).$$

Definition 4.1.5 (Degeneracy maps)**.** Fix any $n > 0$, and any $i \in [n-1]$.

We define the degeneracy map

$$s_i^* : \mathsf{Lag}^{\diamond 0}(n-1) \to \mathsf{Lag}^{\diamond 0}(n) \qquad s_i^*(\mathsf{P}) = c(s_i)^*(\mathsf{P}'_i)$$

where as introduced above the brane

$$\mathsf{P}'_i \subset M \times T^*(c(n-1) \times [0,n])$$

is the ith stretched time reparametrization of P for sufficiently small $\epsilon > 0$, and the simplicial map

$$c(s_i) : c(n) \times [0,n] \longrightarrow c(n-1) \times [0,n]$$

is that induced by s_i. By the pullback $c(s_i)^*(\mathsf{P}'_i)$, we mean the union of the pullbacks along each simplex on which $c(s_i)$ is linear. The collaring conditions on P, and hence on P'_i, ensure that the union glues together to a well-defined Lagrangian n-cobordism.

We leave as an exercise for the reader the following easy proposition.

Proposition 4.1.6. *With the face and degeneracy maps as defined above,* $\mathsf{Lag}^{\diamond 0}$ *is a simplicial set.*

Recall that for $k = 1, \dots, n-1$, the kth *inner horn* $\Lambda^n_k \subset \Delta^n$ is the subsimplicial set obtained by deleting the interior of Δ^n and the codimension one face opposite the kth vertex. A simplicial set X is called a *weak Kan complex* if any map from an inner horn $\Lambda^n_k \to X$ extends to a map $\Delta^n \to X$.

We leave the following elementary (but tedious) verification to the reader. The constructions of the preceding section – collarings, refined facet factorizations, and extension assertion of Lemma 3.5.2 – were designed to ensure this is true.

Proposition 4.1.7 (Weak Kan property)**.** *The simplicial set* $\mathsf{Lag}^{\diamond 0}$ *is a weak Kan complex.*

4.1.1. *Composition of edges via concatenation.* Recall that in an ∞-category, there is not an absolute notion of composition, but rather one defined up to an infinite sequence of contractible choices. Namely, given an ∞-category C, objects $x_0, x_1, x_2 \in \mathcal{C}$, and morphisms $f_{01} : x_0 \to x_1, f_{12} : x_1 \to x_2$, we are guaranteed (by the weak Kan property) to find a 2-simplex

$$\begin{tikzcd} x_0 \arrow[d, "f_{01}"'] \arrow[dr, "f_{02}"] & \\ x_1 \arrow[r, "f_{12}"'] & x_2 \end{tikzcd}$$

with the given boundary values. The "composition" $f_{02} : x_0 \to x_2$ and the 2-simplex are not unique, but the above 2-simplex and any other such 2-simplex will form the partial boundary of a 3-simplex which we again will be able to fill. And so on... Thus one can show that the "composition" $f_{02} : x_0 \to x_2$ while not unique is at least an element of a contractible space.

In the ∞-category $\mathsf{Lag}^{\diamond 0}$, the situation is slightly more concrete: if we are willing to dispense with strict associativity, there is a concrete notion of composition. Let $\mathsf{P}_{01} : \mathsf{L}_0 \to \mathsf{L}_1$ and $\mathsf{P}_{12} : \mathsf{L}_1 \to \mathsf{L}_2$ be morphisms in $\mathsf{Lag}^{\diamond 0}$. Up to time reparameterization, we can view them as Lagrangian 1-cobordisms inside the intervals

$$\mathsf{P}_{01} \subset M \times T^*C(1) = M \times T^*(0,1) \qquad \mathsf{P}_{12} \subset M \times T^*C(1) = M \times T^*(1,2)$$

Definition 4.1.8 (Composition via concatenation)**.** We define the *composition*

$$\mathsf{P}_{02} = \mathsf{P}_{12} \circ \mathsf{P}_{01} : \mathsf{L}_0 \to \mathsf{L}_2$$

to be the equivalence class under time reparametrization of the *concatenation*

$$\mathsf{P}_{01} \cup \mathsf{P}_{12} \subset M \times T^*(0,2).$$

Returning to the language of ∞-categories, we can think of the composition P_{02} as the third edge of the 2-simplex

$$\begin{tikzcd} \mathsf{L}_0 \arrow[d, "\mathsf{P}_{01}"'] \arrow[dr, "\mathsf{P}_{02}"] & \\ \mathsf{L}_1 \arrow[r, "\mathsf{P}_{12}"'] & \mathsf{L}_2 \end{tikzcd}$$

represented by the Lagrangian 2-cobordism

$$\mathsf{P} \subset M \times T^*C(2) = M \times T^*(0,2) \times T^*(0,1)$$

given simply by taking the product of the concatenation

$$\mathsf{P}_{01} \cup \mathsf{P}_{12} \subset M \times T^*(0,2)$$

with the zero section

$$T^*_{(0,1)}(0,1) \subset T^*(0,1).$$

4.1.2. *Composition of higher simplices via concatenation.* More generally, let Q' and Q'' be an n'-simplex and an n''-simplex respectively. We assume $n', n'' \geq 1$. Assume that the n'th vertex of Q' and the 0th vertex of Q'' are the same object L. We define the notion of their *composition* $\mathsf{Q}'' \circ \mathsf{Q}'$, which is an $(n'+n''-1)$-simplex.

Take the splitting

$$c(n'+n''-2) = c(n'-1) \times c(n''-1)$$

and consider the projections

$$\pi' : c(n'+n''-2) \to c(n'-1), \qquad \pi'' : c(n'+n''-2) \to c(n''-1).$$

For instance, π'' acts by forgetting the first $(n'-1)$ coordinates of a point in $c(n'+n''-2)$. We extend $\mathsf{Q}', \mathsf{Q}''$ by zero sections by defining

$$\bar{\mathsf{Q}}' := \pi'^* \mathsf{Q}' \subset M \times T^*(0,n') \times T^*c(n'-1) \times T^*c(n''-1)$$

and

$$\bar{\mathsf{Q}}'' := \pi''^* \mathsf{Q}'' \subset M \times T^*(0,n'') \times T^*c(n'-1) \times T^*c(n''-1).$$

By time reparametrization we can realize Q'' as a Lagrangian brane in the manifold

$$M \times T^*(n', n'+n'') \times T^*c(n''-1).$$

Since Q'' and Q' are both collared by L at time $t = n'$, we concatenate:

Definition 4.1.9 (Composition of higher simplices)**.** We define the composition

$$\mathsf{Q}'' \circ \mathsf{Q}'$$

of Q' with Q'' to be the equivalence class (under time reparametrization) of the Lagrangian brane whose underlying Lagrangian submanifold is the concatenation

$$\bar{\mathsf{Q}}' \cup \bar{\mathsf{Q}}'' \subset M \times T^*(0, n'+n'') \times c(n'+n''-2).$$

Remark 4.1.10. Just as there is a 2-simplex in $\mathsf{Lag}^{\diamond 0}$ whose boundary contains P_{12}, P_{01} and $\mathsf{P}_{12} \circ \mathsf{P}_{01}$, one can produce a $k+l$-simplex relating the composition $\mathsf{Q}'' \circ \mathsf{Q}'$ with the cobordisms Q'' and Q'. One simply extends Q by the zero section, for instance by taking the kth degenerate simplex of Q. We leave it as an exercise to the reader to verify that Q'' and Q' collar the obvious subfacets of this cube.

4.2. **Zero object.** Recall that for C an ∞-category, and two objects $x, x' \in \mathsf{C}(0)$, the *mapping space* $\mathsf{C}(x, x')$ is a simplicial set whose n-simplices are $(n+1)$-simplices in C whose 0th face is the degenerate face at x' and whose 0th vertex is x. (Up to weak equivalence, this is the same as the simplicial set of $(n+1)$-simplices in C whose $(n+1)$st vertex is x' and whose $(n+1)$st face is the degenerate face at x.)

Recall that a zero object $z \in \mathsf{C}(0)$ is an object such that $\mathsf{C}(x, z)$ and $\mathsf{C}(z, x)$ are contractible for all $x \in \mathsf{C}(0)$.

Definition 4.2.1 (Empty brane)**.** Let $\mathsf{L}_\emptyset \in \mathsf{Lag}^{\diamond 0}(0)$ denote the empty Lagrangian equipped with its unique brane structure.

We will show below that $\mathsf{L}_\emptyset$ is a zero object of $\mathsf{Lag}^{\diamond 0}$. Before giving the formal proof, let us construct particularly simple elements of the mapping spaces $\mathsf{Lag}^{\diamond 0}(\mathsf{L}, \mathsf{L}_\emptyset)$ and $\mathsf{Lag}^{\diamond 0}(\mathsf{L}_\emptyset, \mathsf{L})$, for any object $\mathsf{L} \in \mathsf{Lag}^{\diamond 0}(0)$.

Example 4.2.2 (Zero morphisms)**.** Choose $0 < \tau_0 < \tau_1 < 1$, and a function $\tau : \mathbb{R} \to \mathbb{R}$ that is smooth, non-decreasing, and satisfies

$$\tau(t) = \begin{cases} 0, & t \leq \tau_0 \\ 1, & t \geq \tau_1 \end{cases}$$

Consider the associated functions

$$\sigma_{\emptyset\to}(t) = \log \tau(t) \qquad \sigma_{\to\emptyset}(t) = -\log(1 - \tau(t)),$$

and the corresponding graph branes

$$\Gamma_{\sigma_{\emptyset\to}}, \Gamma_{\sigma_{\to\emptyset}} \subset T^*\mathbb{R}.$$

We define the *zero morphisms*

$$z_{\emptyset\to} : \mathsf{L}_\emptyset \to \mathsf{L} \qquad z_{\to\emptyset} : \mathsf{L} \to \mathsf{L}_\emptyset$$

to be the equivalence classes under time reparametrizations of the product branes

$$\mathsf{L} \times \Gamma_{\sigma_{\emptyset\to}}, \mathsf{L} \times \Gamma_{\sigma_{\to\emptyset}} \subset M \times T^*C(1).$$

Now the main result of this section is the following.

Theorem 4.2.3 (Zero object)**.** *The empty brane* $\mathsf{L}_\emptyset \in \mathsf{Lag}^{\diamond 0}(0)$ *is a zero object: for any object* $\mathsf{L} \in \mathsf{Lag}^{\diamond 0}(0)$*, the mapping spaces* $\mathsf{Lag}^{\diamond 0}(\mathsf{L}_\emptyset, \mathsf{L})$ *and* $\mathsf{Lag}^{\diamond 0}(\mathsf{L}, \mathsf{L}_\emptyset)$ *are contractible.*

Proof. The proof for $\mathsf{Lag}^{\diamond 0}(\mathsf{L}, \mathsf{L}_\emptyset)$ is parallel to that for $\mathsf{Lag}^{\diamond 0}(\mathsf{L}_\emptyset, \mathsf{L})$, and we will focus on the former. Since $\mathsf{Lag}^{\diamond 0}(\mathsf{L}, \mathsf{L}_\emptyset)$ is a Kan complex, it suffices to show that any map of simplicial sets

$$b : \partial\Delta^k \longrightarrow \mathsf{Lag}^{\diamond 0}(\mathsf{L}, \mathsf{L}_\emptyset),$$

extends to a map

$$\Delta^k \longrightarrow \mathsf{Lag}^{\diamond 0}(\mathsf{L}, \mathsf{L}_\emptyset).$$

In particular, the base case $k = 0$ will imply $\mathsf{Lag}^{\diamond 0}(\mathsf{L}, \mathsf{L}_\emptyset)$ is nonempty.

For convenience, set $n = k+1$. The data of the map b provides a compatible collection of Lagrangian branes P_b over the boundary $\partial C(n)$ of the n-dimensional rectangular solid

$$C(n) = [0,1]^{n-1} \times [0,n].$$

In particular, since $L_\emptyset$ is the collaring brane along the face

$$[0,1]^{n-1} \times \{n\} \subset C(n),$$

there exists $\epsilon > 0$ such that P_b is empty over the open subset

$$[0,1]^{n-1} \times (n-\epsilon, n] \subset C(n).$$

Using our collaring conventions, there exists a canonical extension of P_b to a Lagrangian branes P_B over an open neighborhood $B \subset C(n)$ of the boundary $\partial C(n)$.

We will construct an extension of P_B to a Lagrangian n-cobordism P over all of $C(n)$. To this end, it is convenient to fix a small $\epsilon > 0$, and choose once and for all an elementary function $\tau : \mathbb{R} \to \mathbb{R}$ that is smooth, non-decreasing, and satisfies

$$\tau(t) = \begin{cases} 0, & t \leq \epsilon/2 \\ 1, & t \geq \epsilon \end{cases}$$

Next define the function

$$\sigma : C(n) = [0,1]^{n-1} \times [0,n] \longrightarrow \mathbb{R} \qquad \sigma(x,t) = \tau(t) \textstyle\prod_{i=1}^n \tau(x_i)\tau(1-x_i)$$

Consider the partially defined one form

$$\kappa = -d\log(1-\sigma) = \frac{d\sigma}{1-\sigma}$$

Finally, form the fiberwise translation

$$\mathsf{P} = \mathsf{P}_B + \kappa \subset M \times T^*C(n)$$

It is straightforward to verify that P is a well-defined Lagrangian n-cobordism and provides the desired extension of b. In particular, the fact that P_b is Λ-non-characteristic implies the same for P. $\square$

4.3. **Non-characteristic objects.**

Definition 4.3.1. An object $\mathsf{L} \in \mathsf{Lag}^{\diamond 0}(0)$ is said to be *non-characteristic* if

$$\mathsf{L} \cap \Lambda = \emptyset.$$

Example 4.3.2 (Backwards zero morphisms)**.** Recall that for any object $\mathsf{L} \in \mathsf{Lag}^{\diamond 0}$, we have the zero morphisms

$$z_{\emptyset\to} : \mathsf{L} \to \mathsf{L}_\emptyset \qquad z_{\to\emptyset} : \mathsf{L} \to \mathsf{L}_\emptyset$$

represented by the product branes

$$\mathsf{L} \times \Gamma_{\sigma_{\emptyset\to}}, \mathsf{L} \times \Gamma_{\sigma_{\to\emptyset}} \subset M \times T^*C(1)$$

where the graph branes are associated to the functions

$$\sigma_{\emptyset\to}(t) = \log\tau(t) \qquad \sigma_{\to\emptyset}(t) = -\log(1-\tau(t)),$$

for a smooth, non-decreasing function $\tau : \mathbb{R} \to \mathbb{R}$ such that

$$\tau(t) = \begin{cases} 0, & t \leq \tau_0 \\ 1, & t \geq \tau_1 \end{cases}$$

with $0 < \tau_0 < \tau_1 < 1$.

If L is non-characteristic, then we also have the *backwards zero morphisms*

$$w_{\emptyset\to} : \mathsf{L}_\emptyset \to \mathsf{L} \qquad w_{\to\emptyset} : \mathsf{L} \to \mathsf{L}_\emptyset$$

represented by the product branes

$$\mathsf{L} \times \Gamma_{-\sigma_{\emptyset\to}}, \mathsf{L} \times \Gamma_{-\sigma_{\to\emptyset}} \subset M \times T^*C(1)$$

where the graph branes are associated to the negative functions

$$-\sigma_{\emptyset\to}(t) = -\log \tau(t) \qquad -\sigma_{\to\emptyset}(t) = \log(1-\tau(t)),$$

If L were not non-characteristic, the above cobordisms would not be Λ-non-characteristic.

The following proposition puts the above example in context.

Proposition 4.3.3. *If* $\mathsf{L} \in \mathsf{Lag}^{\diamond 0}(0)$ *is non-characteristic, then it is a zero object.*

Proof. We will show that the identity morphism id_{L} (see Example 3.6.1) factors through the zero object $\mathsf{L}_\emptyset$. More precisely, we will construct a 2-simplex in $\mathsf{Lag}^{\diamond 0}$ with boundary values

$$\begin{tikzcd}
\mathsf{L} \arrow[d] \arrow[dr, "\mathrm{id}_{\mathsf{L}}"] & \\
\mathsf{L}_\emptyset \arrow[r] & \mathsf{L}
\end{tikzcd}$$

Choose $0 < \tau_0 < \tau_1 < \frac{1}{2} < \tau_2 < \tau_3 < 1$, and a smooth bump function $\tau : \mathbb{R} \to \mathbb{R}$ such that

$$\tau(t) = \begin{cases} 0, & t \leq \tau_0 \\ 1, & \tau_1 \leq t \leq \tau_2 \\ 0, & t \geq \tau_3 \end{cases}$$

with τ non-decreasing over (τ_0, τ_1) and non-increasing over (τ_2, τ_3).

Choose $0 < \epsilon_0 < \epsilon_1 < 0$, and a smooth, non-increasing function $\sigma : \mathbb{R} \to \mathbb{R}$ such that

$$\sigma(s) = \begin{cases} 0, & s \leq \epsilon_0 \\ 1, & s \geq \epsilon_1 \end{cases}$$

Form the partially defined function

$$q : C(2) = [0,1] \times [0,2] \longrightarrow \mathbb{R} \qquad q(s,t) = -\log(1 - \sigma(s)\tau(t))$$

and consider the corresponding graph brane

$$\Gamma_q \subset T^*C(2) = T^*((0,1) \times (0,2))$$

Now we define the sought after 2-simplex to be represented by the Lagrangian 2-cobordism given by the translated brane

$$\mathsf{Q} = (\mathsf{L} \times T^*_{C(2)}C(2)) + \Gamma_q \subset M \times T^*C(2)$$

It is straightforward to verify that Q is a well-defined Lagrangian 2-cobordism and has the prescribed boundary behavior. In particular, by assumption L is non-characteristic, hence by construction Q is Λ-non-characteristic. $\square$

There is a simple but useful generalization of the above proposition. Fix a morphism $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ and a time $t_0 \in (0,1)$. Consider the natural correspondence

$$\begin{tikzcd} M \times T^*C(1) & M \times T^*_{\{t_0\}}C(1) \arrow[l, hook', "i"'] \arrow[r, two heads, "p"] & M \end{tikzcd}$$

and the resulting subset

$$\mathsf{P}_{t_0} = p(i^{-1}(\mathsf{P})) \subset M.$$

Note that $\mathsf{P}_{t_0} \subset M$ is not the naive restriction $\mathsf{P}|_{t_0} = i^{-1}(\mathsf{P}) \subset M \times T^*_{\{t_0\}}C(1)$ but rather the Hamiltonian reduction along the equation $t = t_0$.

Definition 4.3.4. A morphism $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ is said to admit a *non-characteristic cut* at time $t_0 \in (0,1)$ if

$$\mathsf{P}_{t_0} \cap \Lambda = \emptyset.$$

Example 4.3.5. If an object L is non-characteristic, then its identity morphism id_{L} admits a non-characteristic cut at any time $t_0 \in (0,1)$.

Proposition 4.3.6. *If a morphism $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ admits a non-characteristic cut at some time $t_0 \in (0,1)$, then it factors through the zero object $\mathsf{L}_\emptyset$: there is a 2-simplex in $\mathsf{Lag}^{\diamond 0}$ with boundary values*

$$\begin{tikzcd} \mathsf{L}_0 \arrow[d] \arrow[dr, "\mathsf{P}"] & \\ \mathsf{L}_\emptyset \arrow[r] & \mathsf{L}_1 \end{tikzcd}$$

Proof. We will write P' for the result of time reparametrizing P so that it lies inside of $M \times T^*(0,2)$. Without loss of generality, we may assume that P' admits a non-characterisric cut at time $t_0 = 1$.

Let us return to the proof of the preceding proposition, and in particular the graph brane

$$\Gamma_q \subset T^*C(2) = T^*((0,1) \times (0,2)).$$

Consider the Lagrangian 2-cobordism represented by the translated brane

$$\mathsf{Q} = (\mathsf{P}' \times T^*_{(0,1)}(0,1)) + \Gamma_q \subset M \times T^*C(2) = M \times T^*((0,1) \times (0,2))$$

Observe that admitting a non-characteristic cut is an open condition in the time variable t_0. Thus choosing all of the parameters $0 < \tau_0 < \tau_1 < \frac{1}{2} < \tau_2 < \tau_3 < 1$ in the construction of the graph brane Γ_q sufficiently close to $\frac{1}{2}$, the Lagrangian 2-cobordsm Q is non-characteristic. $\square$

Remark 4.3.8. We will eventually use not only the above proposition but also the specific 2-simplex constructed in its proof.

Thanks to the weak Kan property and the fact that $\mathsf{L}_\emptyset$ is a zero object, the above 2-simplex is equivalent up to a sequence of contractible choices with a 2-simplex of the



Figure 4.3.7. The graph brane Γ_q of the proposition.

more concrete form

$$\begin{tikzcd}
\mathsf{L}_0 \arrow[d, "z_{\to\emptyset}"'] \arrow[dr, "\mathsf{P}"] & \\
\mathsf{L}_\emptyset \arrow[r, "z_{\emptyset\to}"'] & \mathsf{L}_1
\end{tikzcd}$$

where P is factored into a composition of the zero morphisms of Example 4.2.2.

4.4. **Stabilization.** Though $\mathsf{Lag}^{\diamond 0} = \mathsf{Lag}^{\diamond 0}_\Lambda(M)$ has a zero object, one can check that in any generality it is not stable. The main result of this paper is a concrete geometric construction of a stabilization.

Definition 4.4.1 ([DAGI])**.** An ∞-category C is said to be *stable* if it satisfies the following:

(1) There exists a zero object $0 \in \mathsf{C}$.
(2) Every morphism in C admits a kernel and a cokernel.
(3) Any commutative diagram in C of the form

$$\begin{tikzcd}
a \arrow[r] \arrow[d] & b \arrow[d] \\
0 \arrow[r] & c
\end{tikzcd}$$

is Cartesian if and only if it is cocartesian.

The third condition states that the diagram presents a as a kernel of $b \to c$ if and only if it presents c as a cokernel of $a \to b$.

We have seen that the empty Lagrangian $\mathsf{L}_\emptyset$ is a zero object of $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$. To guarantee the existence of kernels and cokernels, we consider the following symplectic version of a stabilization procedure familiar from algebraic topology.

Consider the symplectic manifold $T^*\mathbb{R}^n$ with fixed support Lagrangian the zero section $\mathbb{R}^n \subset T^*\mathbb{R}^n$. We also equip $T^*\mathbb{R}^n$ with its canonical background structures (arising from the fact that it is a cotangent bundle). For notational simplicity, we set

$$\mathsf{Lag}_\Lambda^{\diamond n}(M) = \mathsf{Lag}_{\Lambda\times\mathbb{R}^n}^{\diamond 0}(M \times T^*\mathbb{R}^n),$$

which for $n = 0$ of course agrees with our previous notation.

Recall that for $x \in \mathbb{R}$, and $\alpha \in \mathbb{Z} + \frac{1}{2}$, we have the α-graded conormal brane

$$\mathsf{N}_x[\alpha] \subset T^*\mathbb{R}.$$

Let us focus on the $\frac{1}{2}$-graded conormal brane based at $x = 0$. Successively taking the product with it provides a tower of functors

$$\begin{tikzcd} \cdots \arrow[r] & \mathsf{Lag}_\Lambda^{\diamond n}(M) \arrow[r] & \mathsf{Lag}_\Lambda^{\diamond n+1}(M) \arrow[r] & \cdots & \mathsf{L} \arrow[r, mapsto] & \mathsf{L} \times \mathsf{N}_0[\tfrac{1}{2}]. \end{tikzcd}$$

Note that each functor is a level-wise injection.

Definition 4.4.2. Given $\Lambda \subset M$, we define the ∞-category $\mathsf{Lag}_\Lambda(M)$ to be the homotopy colimit

$$\mathsf{Lag}_\Lambda(M) = \mathrm{colim}_{n\to\infty}\, \mathsf{Lag}_\Lambda^{\diamond n}(M)$$

in the ∞-category of stable ∞-categories.

The advantage of the above definition is it provides access to the universal property of the colimit. But it would be difficult to work with if we did not have the following observation. Since the above tower consists of inclusions of simplicial sets, its colimit can be calculated by the naive increasing union of simplicial sets.

Lemma 4.4.3. *The colimit* $\mathsf{Lag}_\Lambda(M)$ *can be calculated by the naive increasing union of simplicial sets*

$$\mathsf{Lag}_\Lambda(M) \simeq \cup_{n\to\infty} \mathsf{Lag}_\Lambda^{\diamond n}(M).$$

Proof. The category of simplicial sets admits a model structure (the Joyal model structure) in which fibrant-cofibrant objects are weak Kan complexes and cofibrations are level-wise inclusions. Hence the homotopy colimit of a sequence of inclusions is precisely the union. ☐

Now the following theorem is an abstract form of our main result. The remaining sections of the paper are devoted to its proof, and in particular a construction of the required mapping cones.

Theorem 4.4.4. *The* ∞*-category* $\mathsf{Lag}_\Lambda(M)$ *is stable.*

Strictly speaking, we do not prove properties (2) and (3) of the above definition of stable ∞-category. Rather we verify the three equivalence properties given by the following theorem of Lurie.

Theorem 4.4.5 ([L11]). *An ∞-category C is a stable ∞-category if and only if the following three properties are satisfied:*

1. *There exists a zero object $0 \in \mathsf{C}$.*
2. *Every morphism in C admits a kernel.*
3. *Let $\Omega : \mathsf{C} \to \mathsf{C}$ be the functor induced by sending every object L to the kernel of the zero map $0 \to \mathsf{L}$. Then Ω is an equivalence.*

Remark 4.4.6. While we have used the term *stabilization* to refer to the construction of $\mathsf{Lag}_\Lambda(M)$, the same term is used in [L11] as a general procedure for producing stable ∞-categories from non-stable ones. We expect that $\mathsf{Lag}_\Lambda(M)$ is the universal stabilization of $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$ but tackling this question is beyond the scope of this paper.

4.5. **Space symmetries.** Before continuing on to the proof of theorem, we state here an easily checked invariance of our constructions under isotopies.

Let $\mathrm{Diff}_c(\mathbb{R}^k)$ denote the topological group of compactly supported diffeomorphisms of $\mathbb{R}^k$. It is useful to recognize that $\mathrm{Diff}_c(\mathbb{R}^k)$ deformation retracts onto the general linear group. In particular, $\mathrm{Diff}_c(\mathbb{R}^k)$ consists of two components, depending on whether an element is orientable.

Let $P_c(\mathbb{R}^k)$ denote the Poincare ∞-groupoid of $\mathrm{Diff}_c(\mathbb{R}^k)$. The group structure on $\mathrm{Diff}_c(\mathbb{R}^k)$ turns $P_c(\mathbb{R}^k)$ into a Picard ∞-groupoid. We will write $P_c(\mathbb{R}^k)(n)$ for its set of n-simplices, and in particular $P_c(\mathbb{R}^k)(0)$ for its discrete group of 0-simplices.

By construction, $P_c(\mathbb{R}^k)(0)$ naturally acts on $\mathsf{Lag}_\Lambda^{\diamond k}(M)$, or in other words, there is a morphism

$$P_c(\mathbb{R}^k)(0) \longrightarrow \mathrm{Aut}(\mathsf{Lag}_\Lambda^{\diamond k}(M))$$

where we write Aut to denote the Picard ∞-groupoid of ∞-category automorphisms.

We leave the following assertion to the interested reader.

Proposition 4.5.1. *The natural action of the discrete group $P_c(\mathbb{R}^k)(0)$ on the ∞-category $\mathsf{Lag}^{\diamond k}(M)$ lifts to an action of the full Picard ∞-groupoid $P_c(\mathbb{R}^k)$.*

Example 4.5.2 (Isotopy of Domain). Here is the simplest general import of the previous proposition.

Suppose we begin with an element $g \in P_c(\mathbb{R}^k)(0)$ which for simplicity we assume represents an orientation-preserving diffeomorphism. Let $p \in P_c(\mathbb{R}^k)(1)$ represent a path in $\mathrm{Diff}_c(\mathbb{R}^k)$ from the identity to the element g.

Suppose we take an object $\mathsf{L} \in \mathsf{Lag}^{\diamond k}(0)$. Then the proposition asserts that there is an invertible morphism $\mathsf{P} \in \mathsf{Lag}_\Lambda^{\diamond k}(M)(1)$ from L to $g(\mathsf{L})$.

Example 4.5.3. Here is a very special but useful application of the previous proposition (which could easily be deduced in an ad hoc manner).

Recall that for $x \in \mathbb{R}$, and $\alpha \in \mathbb{Z} + \frac{1}{2}$, we have the α-graded conormal brane

$$\mathsf{N}_x[\alpha] \subset T^*\mathbb{R}.$$

In particular, in our stabilization tower, we worked with the $\frac{1}{2}$-graded conormal brane based at $x = 0$.

The above proposition confirms that our constructions are independent of the choice of $x = 0$. The functor of taking the product with $\mathsf{N}_0[\frac{1}{2}]$ is equivalent to taking the product with $\mathsf{N}_x[\frac{1}{2}]$ for any other $x \in \mathbb{R}^k$.

We will not use the following assertion (and in fact it follows from our main theorem), but we state it here since it can be deduced rather formally from the above proposition.

Fix two objects $\mathsf{L}_0, \mathsf{L}_1 \in \mathsf{Lag}^{\diamond k}(M)(0)$. Using the above proposition, we can assume they are disjoint $\mathsf{L}_0 \cap \mathsf{L}_1 = \emptyset$, and hence their disjoint union provides a well defined object

$$\mathsf{L}_0 \coprod \mathsf{L}_1 \in \mathsf{Lag}_\Lambda^{\diamond k}(M)(0)$$

Corollary 4.5.4. *Disjoint union of branes provides a natural $\mathcal{E}_k$-structure on the ∞-category $\mathsf{Lag}^{\diamond k}(M)$. Taking $k \to \infty$, we obtain an $\mathcal{E}_\infty$-structure on the ∞-category $\mathsf{Lag}_\Lambda(M)$.*

Our proof that $\mathsf{Lag}_\Lambda(M)$ is stable shows in particular that disjoint union is the coproduct in $\mathsf{Lag}_\Lambda(M)$.

4.6. **Tilting.** We present here a simple but particularly useful variation of Proposition 4.5.1 which could be skipped until needed later. It can be thought of as the "Fourier transform" of the operation of translation.

Recall that for $x \in \mathbb{R}$, and $\alpha \in \mathbb{Z} + \frac{1}{2}$, we have the α-graded conormal brane

$$\mathsf{N}_x[\alpha] \subset T^*\mathbb{R}.$$

More generally, consider an n-dimensional submanifold $X \subset \mathbb{R}^k$, a contractible open neighborhood $U \subset X$, and a smooth function $b : X \to \mathbb{R}$ that is strictly positive on U and zero elsewhere. Consider the logarithm $\log b : U \to \mathbb{R}$, and for $\beta \in \mathbb{Z} + (k-n)/2$, the corresponding translated conormal brane

$$\mathsf{T}_U[\beta] = \mathsf{N}_X[\beta] + \Gamma_{\log b} \subset T^*\mathbb{R}^k$$

Definition 4.6.1. For $\alpha \in \mathbb{Z} + \frac{1}{2}$, a *tilt* of the conormal brane $\mathsf{N}_x[\alpha]$ is any such brane $\mathsf{T}_U[\beta] = \mathsf{N}_X[\beta] + \Gamma_{\log b}$ with $\beta = \alpha - (k-n)/2$.

The source of the name tilt is that one can obtain $\mathsf{T}_U[\beta]$ from the conormal brane $\mathsf{N}_x[\alpha]$ by a time-dependent Hamiltonian symmetry of $T^*\mathbb{R}^k$. We leave the following easy lemma to the reader.

Lemma 4.6.2. *Time-dependent Hamiltonian symmetries provide a contractible space of identifications of all tilts of the conormal brane $\mathsf{N}_x[\alpha]$.*

5. Construction of kernel

The remainder of the paper is devoted to the proof of Theorem 4.4.4. Fix once and for all a morphism $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ between objects $\mathsf{L}_0, \mathsf{L}_1 \in \mathsf{Lag}_\Lambda(M)$. We will construct a kernel object $\mathsf{K} \in \mathsf{Lag}_\Lambda(M)$ and a morphism $\mathsf{k} : \mathsf{K} \to \mathsf{L}_0$, then show that the composition $\mathsf{P} \circ \mathsf{k} : \mathsf{K} \to \mathsf{L}_1$ is homotopic to a zero map. We will refer to the 2-simplex of $\mathsf{Lag}_\Lambda(M)$ realizing this homotopy as the kernel homotopy. The construction of the kernel object, kernel morphism, and kernel homotopy are the subjects of Sections 5.1, 5.2, and 5.3, respectively. We verify the above data satisfies the universal property of the kernel in Section 6.

Recall that $\mathsf{Lag}_\Lambda(M)$ is the union of the ∞-subcategories

$$\mathsf{Lag}_\Lambda^{\diamond k}(M) = \mathsf{Lag}_{\Lambda\times\mathbb{R}^k}^{\diamond 0}(M \times T^*\mathbb{R}^k).$$

Hence the morphism $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ comes from $\mathsf{Lag}_\Lambda^{\diamond k}(M)$, for some k. It is convenient to reindex our objects once and for all, and write M in place of $M \times T^*\mathbb{R}^k$, and Λ in place of $\Lambda \times \mathbb{R}^k$. With this understanding, we view $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ as a morphism in $\mathsf{Lag}_\Lambda^{\diamond 0}(M)$. The kernel K will then be an object of $\mathsf{Lag}_\Lambda^{\diamond 1}(M)$.

In any stable ∞-category, the kernel and cokernel of a morphism differ by a shift (properly speaking, the shift functor is deduced from the axiom that squares are Cartesian if and only if cocartesian). Thus our construction of a candidate kernel K just as well provides a candidate cokernel $co\mathsf{K} = \mathsf{K}[1]$, where as usual $[1]$ denotes the shift of grading. We will refer to the underlying Lagrangian submanifold

$$C(\mathsf{P}) \subset M \times T^*\mathbb{R}$$

of each of these branes as the *cone* of P. Often in what follows we will focus on the kernel, though all of our arguments have precise analogues for the cokernel.

5.1. **Kernel object.** In this section, we give a specific model of K depending on the choice of realization of the cone $C(\mathsf{P})$. In particular, we will fix once and for all a concrete representative brane

$$\mathsf{P} \subset M \times T^*C(1)$$

for the morphism P (rather than an equivalence class under time reparametrization). We will make further choices to construct the model of the kernel—in verifying the universal property of the kernel, we will have shown that the space of such choices is contractible.

In what follows, the subscripts ℓ, r stand for left and right.

Construction 5.1.1 (Cone)**.** Fix once and for all a smooth non-decreasing function $\tau_\ell : \mathbb{R} \to \mathbb{R}$ and a smooth non-increasing function $\tau_r : \mathbb{R} \to \mathbb{R}$ such that

$$\tau_\ell(t) = \begin{cases} 0, & t \leq -1 \\ 1, & t \geq 0 \end{cases} \qquad \tau_r(t) = \begin{cases} 1, & t \leq 1 \\ 0, & t \geq 2 \end{cases}$$

Consider the corresponding exact one-forms

$$\kappa_\ell = d\log\tau_\ell(t) \in \Omega^1(-1,\infty) \qquad \kappa_r = d\log\tau_r(t) \in \Omega^1(-\infty, 2).$$

Finally, consider the exact one-form given by the linear combination

$$\kappa = -\kappa_\ell + \kappa_r \in \Omega^1(-1,2).$$

We will only appeal to the fact that κ has the qualitative behavior

1. κ is identically zero over $[0,1]$,
2. κ has no zeros outside of $[0,1]$,
3. $\kappa(\partial_t) \to -\infty$ as $t \to -1$,
4. $\kappa(\partial_t) \to -\infty$ as $t \to 2$.

Now let us return to the Lagrangian brane

$$\mathsf{P} \subset M \times T^*C(1).$$

Thanks to its collaring by $\mathsf{L}_0, \mathsf{L}_1 \subset M$ at the end points $\{0\}, \{1\}$ of the interval $C(1) = [0,1]$, we can extend P to a Lagrangian brane over a longer interval

$$\tilde{\mathsf{P}} = (\mathsf{L}_0 \times T^*_{(-1,0)}(-1,0)) \cup \mathsf{P} \cup (\mathsf{L}_1 \times T^*_{(1,2)}(1,2)) \subset M \times T^*(-1,2).$$

We define the *cone* of P to be the translated Lagrangian submanifold

$$C(\mathsf{P}) = \tilde{\mathsf{P}} + \Gamma_\kappa \subset M \times T^*(-1,2).$$

Alternatively, we could restrict κ to the intervals $(-1,0), (1,2)$, and then form the glued Lagrangian submanifold

$$C(\mathsf{P}) = (\mathsf{L}_0 \times \Gamma_\kappa|_{(-1,0)}) \cup \mathsf{P} \cup (\mathsf{L}_1 \times \Gamma_\kappa|_{(1,2)}) \subset M \times T^*(-1,2).$$

See Figure 5.1.2.

Observe that $C(\mathsf{P})$ deformation retracts onto the original exact brane

$$\mathsf{P} = C(\mathsf{P})|_{[0,1]}.$$

Thus any discrete aspects of the geometry of $C(\mathsf{P})$ coincide with those of P. In particular, it is evident that $C(\mathsf{P})$ is a closed exact Lagrangian submanifold of $M \times T^*\mathbb{R}$.

Definition 5.1.3 (Kernel and cokernel)**.** We define the *kernel* K of the morphism P to be the Lagrangian brane with underlying Lagrangian submanifold the cone

$$C(\mathsf{P}) \subset M \times T^*\mathbb{R},$$

and brane structure $(f_{\mathsf{K}}, \alpha_{\mathsf{K}}, [c_{\mathsf{K}}])$ uniquely determined by the fact that its restriction to $\mathsf{P} \subset C(\mathsf{P})$ coincides with the brane structure $(f_{\mathsf{P}}, \alpha_{\mathsf{P}}, [c_{\mathsf{P}}])$ of P.

The *cokernel* *co*K is the shift *co*$\mathsf{K} = \mathsf{K}[1]$. Explicitly, *co*$\mathsf{K}$ has the structure $(f_{\mathsf{K}}, \alpha_{\mathsf{K}} + 1, [c_{\mathsf{K}}])$.

5.2. **Kernel morphism.** Next we define the kernel morphism $\mathsf{k} : \mathsf{K} \to \mathsf{L}_0$.

Let us begin with the identity morphism id_{K} represented by the Lagrangian 1-cobordism

$$\mathrm{id}_{\mathsf{K}} = \mathsf{K} \times T^*_{C(1)}C(1) \subset M \times T^*\mathbb{R} \times T^*C(1).$$

To construct k, we will carve id_{K} in the sense of Section 2.5.1 with a function

$$h : \mathbb{R} \times C(1) \to \mathbb{R}.$$

Fix once and for all a small $\epsilon > 0$, and smooth non-decreasings functions $\tau_s : \mathbb{R} \to \mathbb{R}, \tau_t : C(1) \to \mathbb{R}$ such that

$$\tau_s(s) = \begin{cases} 0, & s \leq -1 + \epsilon \\ 1, & s \geq 0 \end{cases} \qquad \tau_t(t) = \begin{cases} 0, & t \leq \epsilon \\ 1, & t \geq \frac{1}{2} \end{cases}$$


$\mathbb{R}^\diamond$
$x = -2$
$x = 1$
P
$\mathbb{R}_x$
$\mathsf{L}_0 \times (-\kappa_\ell)$
$\mathsf{L}_1 \times \kappa_r$

Figure 5.1.2. The projection of the cone $C(\mathsf{P})$ onto $T^*\mathbb{R}$.

Form the product $\tau(s,t) = \tau_s(s)\tau_t(t) : \mathbb{R} \times C(1) \to \mathbb{R}$, and finally consider the function

$$h(s,t) = -\log(1 - \tau(s,t))$$

over its natural domain of definition

$$D = ((-1,2) \times (0,1)) \setminus ([0,2) \times [\frac{1}{2}, 1)) \subset \mathbb{R} \times C(1).$$

Definition 5.2.1 (Kernel morphism)**.** We define the *kernel morphism* $\mathsf{k} : \mathsf{K} \to \mathsf{L}_0$ to be the carved Lagrangian brane

$$\mathsf{k} = \mathrm{id}_{\mathsf{K}} + \Gamma_h \subset M \times T^*\mathbb{R} \times T^*C(1).$$

Some immediate discussion is required to explain why the kernel morphism k is indeed a morphism to the object L_0. In fact, it is a morphism to a tilt (in the sense of Section 4.6) of the product brane

$$\mathsf{L}_0 \times \mathsf{N}_0[\frac{1}{2}] \subset M \times T^*\mathbb{R}.$$

On the one hand, $\mathsf{L}_0 \times \mathsf{N}_0[\frac{1}{2}]$ is simply the image of L_0 under the map

$$\mathsf{Lag}_\Lambda^{\diamond 0}(M) \to \mathsf{Lag}_\Lambda^{\diamond 1}(M),$$

and so equivalent to L_0 inside of $\mathsf{Lag}_\Lambda(M)$. On the other hand, thanks to Lemma 4.6.2, there is a contractible space of such tilts, and they are all equivalent to $\mathsf{L}_0 \times \mathsf{N}_0[\frac{1}{2}]$ inside of $\mathsf{Lag}_\Lambda^{\diamond 1}(M)$. Thus we can unambiguously interpret k as a morphism to L_0.



(a) (b)

Figure 5.2.2. (a) The projection of id_{K} onto $\mathbb{R} \times C(1)$. (b) shows the effect of carving by dh; the resulting cobordism $\mathsf{k} = id_{\mathsf{K}} + \Gamma_{dh}$ is a morphism from K to (a tilt of) L_0.

5.3. **Kernel homotopy.** Now that we have the kernel object K and the kernel map $\mathsf{k} : \mathsf{K} \to \mathsf{L}_0$, we will construct a homotopy from the composition

$$\begin{tikzcd} \mathsf{K} \arrow[r, "\mathsf{k}"] & \mathsf{L}_0 \arrow[r, "\mathsf{P}"] & \mathsf{L}_1 \end{tikzcd}$$

to a zero map.

Recall that the empty brane $\mathsf{L}_\emptyset \subset M$ is a zero object in $\mathsf{Lag}_\Lambda(M)$: For any object L, the spaces of morphisms $\mathsf{L}_\emptyset \to \mathsf{L}$ and $\mathsf{L} \to \mathsf{L}_\emptyset$ are contractible. For concreteness, recall the representative zero morphisms $z_{\to\emptyset}, z_{\emptyset\to}$ constructed in Example 4.2.2.

We will construct a diagram of 2-simplices

$$\begin{tikzcd} \mathsf{K} \arrow[r, "\mathsf{k}"] \arrow[d, "z_{\to\emptyset}"'] \arrow[dr] & \mathsf{L}_0 \arrow[d, "\mathsf{P}"] \\ \mathsf{L}_\emptyset \arrow[r, "z_{\emptyset\to}"'] & \mathsf{L}_1 \end{tikzcd}$$

extending our previous constructions. Thanks to Proposition 4.3.6 (see also Remark 4.3.8), it suffices to find a 2-simplex

$$\begin{tikzcd} \mathsf{K} \arrow[r, "\mathsf{k}"] \arrow[dr, "\mathsf{h}"'] & \mathsf{L}_0 \arrow[d, "\mathsf{P}"] \\ & \mathsf{L}_1 \end{tikzcd}$$

such that the boundary edge h admits a non-characteristic cut. But our construction of k is a map to a tilt of L_0, rather than to $\mathsf{L}_0^\diamond$. As such we will instead construct a 2-simplex with boundary edges

$$\begin{tikzcd}
\mathsf{K} \arrow[r, "\mathsf{k}"] \arrow[dr, "\mathsf{h}"'] & \mathsf{L}_0 \times \Gamma_g \arrow[d, "\mathsf{P}\times\Gamma_g"] \\
& \mathsf{L}_1 \times \Gamma_g .
\end{tikzcd}$$

(Here, $\Gamma_g \subset T^*\mathbb{R}$ is the graph brane associated to the tilting function

$$g : (-1,0) \to \mathbb{R} \qquad g(s) = -\log(\tau_\ell(s)(1-\tau_s(s))).$$

Note that by Lemma 4.6.2, we lose no generality in replacing $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ by a tilt.)

To yield this 2-simplex we construct a Lagrangian 2-cobordism

$$\mathsf{H} \subset M \times T^*\mathbb{R} \times T^*C(2) = M \times T^*\mathbb{R} \times T^*((0,2)\times(0,1))$$

whose facets are collared as follows:

$$\mathsf{H}|_{(0,1)\times\{0\}} = \mathsf{k} \qquad \mathsf{H}|_{(1,2)\times\{0\}} = (\mathsf{P}\times\Gamma_g) \qquad \mathsf{H}|_{(0,2)\times\{1\}} = \mathsf{h}.$$

We will also construct the Lagrangian 1-cobordism h so that it admits a non-characteristic cut.

Moreover, it will be important that we understand the precise shape of H to later verify that the resulting kernel diagram is universal. Therefore, while we formulate the following as a proposition, we will eventually refer to properties established during its proof.

Proposition 5.3.1 (Kernel homotopy)**.** *There is a Lagrangian 2-cobordism*

$$\mathsf{H} \subset M \times T^*\mathbb{R} \times T^*C(2) = M \times T^*\mathbb{R} \times T^*((0,2)\times(0,1))$$

with collared boundaries over the facets

$$\mathsf{H}|_{(0,1)\times\{0\}} = k \qquad \mathsf{H}|_{(1,2)\times\{0\}} = (\mathsf{P}\times\Gamma_g) \qquad \mathsf{H}|_{(0,2)\times\{1\}} = \mathsf{h}$$

such that the Lagrangian 1-cobordism h *admits a non-characteristic cut.*

Proof. We break up the proof into first the construction of h then that of H.

Construction 5.3.2 (of the morphism h)**.** The construction of h is summarized in Figure 5.3.3. It proceeds in four steps.

Step (a). Recall the rotation construction from Example 2.5.4. We perform this on the cobordism $\tilde{\mathsf{P}}$ to obtain a Lagrangian in $M \times T^*\mathbb{R} \times T^*\mathbb{R}$. The result is depicted in Figure5.3.3(a), and inherits a canonical brane structure from that of P.

Step (b). In defining the cone $C(\mathsf{P})$, we utilized a 1-form $\kappa \in \Omega^1(\mathbb{R})$ in Construction 5.1.1. Let us consider $\kappa = \kappa(s,t) \in \Omega^1(\mathbb{R}\times\mathbb{R})$ as a 1-form with no dependence on t, and carve the brane from (a) by the 1-form $\kappa = \kappa(s,t)$. The result is a brane in $M \times T^*(-2,1) \times T^*\mathbb{R}$.

Step (c). Now we carve by the 1-form dh utilized in Section 5.2. Again we remember the resulting brane structure.



(a) (b) (c) (d)

Figure 5.3.3. A summary of the construction of h. (a) results from the rotation construction applied to P. (b) results from carving by the one-form $\kappa(s,t)$. (c) results from carving by the one-form dh. (d) is a drawing of h, where the addition of dg ensures that h admits a non-characteristic cut.



Figure 5.3.5. A summary of the construction of H. (a) is the Lagrangian $p^*(\mathsf{h})$. (b) is obtained by carving by the 1-form $d(\tau f)$. Note that the rightmost face of (b) is equal to the composition $\mathsf{P} \circ \mathsf{K}$, where P has been tilted. The drawing is not to scale, and we have not drawn any vector fields to indicate the behavior of H near infinity.

Step (d). Finally, to ensure that h admits a non-characteristic cut, we translate by a 1-form dg which we now define. Fix $\epsilon > 0$, and define a function $g_1 : \mathbb{R} \to \mathbb{R}$ such that

$$g_1(s) = \begin{cases} 1, & s \leq -2 + \epsilon \\ 0, & s \geq 1 - \epsilon \end{cases}$$

with g_1 strictly decreasing on $(-2+\epsilon, 1-\epsilon)$. Define a bump function $g_2 : C(1) \to \mathbb{R}$ such that

$$supp(g_2) \subset [\tfrac{1}{2} - \epsilon, \tfrac{1}{2} - 3\epsilon] \qquad\qquad g_2 > 0 \text{ on } (\tfrac{1}{2} - \epsilon, \tfrac{1}{2} - 3\epsilon).$$

Now define $g : \mathbb{R} \times C(1) \to \mathbb{R}$ by

$$g(s,t) = g_1(s) g_2(t)$$

and translate the brane from (c) by dg.

In principle we are done. But we will need some concrete notation for later on. Define the linear diffeomorphism

$$\psi : (-2, 3) \to (0, 1)$$

and transport the brane from (d) to a brane in $M \times T^*\mathbb{R} \times C(1)$ via the diffeomorphism

$$M \times T^*\mathbb{R} \times (-2,3) \longrightarrow M \times T^*\mathbb{R} \times C(1) \qquad (p,s,t) \longmapsto (p,s,\psi(t)).$$

We call this Lagrangian brane h, with all the brane structure induced from the previous steps. It clearly admits a non-characteristic cut at $\psi(\frac{1}{2} - 2\epsilon)$.

Construction 5.3.4 (of kernel homotopy H)**.** It is clear that $\mathsf{K} \circ \mathsf{P}$ can be obtained by carving a portion of h. The 2-cube

$$\mathsf{H} \subset M \times T^*\mathbb{R} \times C(2)$$

will be a cobordism realizing this carving. We depict the carving in Figure 5.3.5.

Explicitly, the linear diffeomorphism

$$\phi : (0,2) \to (0,1) \subset \mathbb{R}.$$

induces a map

$$\begin{array}{rcl} p : M \times T^*\mathbb{R} \times C(2) & \to & M \times T^*\mathbb{R} \times C(1) \\ (p, s, (x, t)) & \mapsto & (p, s, \phi(t)) \end{array}$$

by which we can pull back h to obtain

$$p^*(\mathsf{h}) \subset M \times T^*\mathbb{R} \times C(2).$$

This Lagrangian is the identity 2-morphism of h—up to scaling in the time coordinate, one can think of it simply as

$$\mathsf{h} \times T^*_{(0,1)}(0, 1).$$

Recall the function

$$h(s, t) = -\log(1 - \tau(s, t))$$

used in Section 5.2. Note that if we define the x-independent function

$$f = h - \phi^*\psi_* h$$

then the Lagrangian

$$p^*(\mathsf{h}) + \Gamma_{df}$$

is the identity 2-morphism of $\mathsf{K} \circ \mathsf{P}$. The goal is thus to parametrize between f and the function 0—we do this by introducing a function τ.

Choose a smooth, non-decreasing function $\tau : (0, 1) \to \mathbb{R}$ with boundary conditions

$$\tau(x) = \begin{cases} 0, & x \leq \epsilon \\ 1, & x \geq \frac{1}{2} \end{cases}$$

and define the product

$$\tau f(x, s, t) = \tau(x) f(s, t).$$

We define

$$\mathsf{H} = p^*(\mathsf{h}) + \Gamma_{d(\tau f)}.$$

As usual, the brane structure on H is induced by the process of carving and by pullbacks. From the comments above it is clear that H satisfies the boundary conditions of Proposition 5.3.1.

The above constructions complete the proof of Proposition 5.3.1. □

Remark 5.3.6 (Stabilizing and kernels)**.** Given a morphism $\mathsf{P} \in \mathsf{Lag}^{\diamond 0}(\mathsf{L}_0, \mathsf{L}_1)$, we have defined the kernel to be an object $\mathsf{K}(\mathsf{P}) \in \mathsf{Lag}^{\diamond 1}$. As constructed, $\mathsf{K}(\mathsf{P})^\diamond, \mathsf{K}(\mathsf{P}^\diamond) \in \mathsf{Lag}^{\diamond 2}$ are not identical objects. For example, setting

$$\mathsf{Lag}^{\diamond 2}(M) = \mathsf{Lag}^{\diamond 0}(M \times T^*\mathbb{R}^2) = \mathsf{Lag}^{\diamond 0}(M \times T^*\mathbb{R}_{s_1} \times T^*\mathbb{R}_{s_2}),$$

we see that $\mathsf{K}(\mathsf{P}^\diamond)$ is a product with $T^*_{\{0\}}\mathbb{R}_{s_1}$ while $\mathsf{K}(\mathsf{P})^\diamond$ is a product with $T^*_{\{0\}}\mathbb{R}_{s_2}$.

However, there is a Hamiltonian isotopy of $\mathbb{R}^2$ which rotates $(-2, 1) \subset \mathbb{R}_{s_1}$ into $(-2, 1) \subset \mathbb{R}_{s_2}$, showing that $\mathsf{K}(\mathsf{P})^\diamond$ and $\mathsf{K}(\mathsf{P}^\diamond)$ are indeed equivalent. In fact, this rotation produces a prism in $\mathsf{Lag}^{\diamond 1}$ realizing a homotopy between the two diagrams

$$\begin{tikzcd} \mathsf{K}(\mathsf{P})^\diamond \arrow[r, "\mathsf{k}(\mathsf{P})^\diamond"] \arrow[dr, swap, "\mathsf{h}(\mathsf{P})^\diamond"] & \mathsf{L}_0^{\diamond 2} \arrow[d, "\mathsf{P}^{\diamond 2}"] \\ & \mathsf{L}_1^{\diamond 2} \end{tikzcd} \qquad \begin{tikzcd} \mathsf{K}(\mathsf{P}^\diamond) \arrow[r, "\mathsf{k}(\mathsf{P}^\diamond)"] \arrow[dr, swap, "\mathsf{h}(\mathsf{P}^\diamond)"] & \mathsf{L}_0^{\diamond 2} \arrow[d, "\mathsf{P}^{\diamond 2}"] \\ & \mathsf{L}_1^{\diamond 2}. \end{tikzcd}$$

Here the rightmost edge $\mathsf{P}^{\diamond 2}$ is fixed, since we can choose a rotation which fixes the origin of $\mathbb{R}^2$, and $\mathsf{P}^{\diamond 2}$ lives over the origin.

6. Proof of universal property

In this section, we prove that the kernel diagram (object, morphism, and homotopy) from the preceding section satisfies the ∞-categorical universal property of a kernel. In Section 6.1, we describe the outline of the proof, reducing it to three key constructions given in Sections 6.3, 6.4, and 6.5. In Section 6.2, we introduce a useful figure for reference throughout the constructions. Throughout what follows, we continue with the setup of the preceding section. In particular, we assume P is a morphism in $\mathsf{Lag}^{\diamond 0}$ without loss of generality.

6.1. **Formal reductions.**

Definition 6.1.1. Fix an ∞-category C and a simplicial set D. A *diagram in* C *indexed by* D is a map of simplicial sets $\mathsf{D} \to \mathsf{C}$. Given a diagram $\mathsf{D} \to \mathsf{C}$, the *overcategory* C_{D} is the unique simplicial set such that

$$sSet(\Delta^n, \mathsf{C}_{\mathsf{D}}) = sSet_{\mathsf{D}}(\Delta^n \star \mathsf{D}, \mathsf{C})$$

where $\Delta^n \star \mathsf{D}$ denotes the join of Δ^n and D, and $sSet_{\mathsf{D}}$ denotes maps of simplicial sets $\Delta^n \star \mathsf{D} \to \mathsf{C}$ that restrict to the diagram $\mathsf{D} \to \mathsf{C}$.

Example 6.1.2. Let $\mathsf{D} = \Delta^0$ be a point and let the diagram $\mathsf{D} \to \mathsf{C}$ specify an object L of C. Then an n-simplex in C_{D} is an $(n+1)$-simplex in C whose final vertex is the object L.

For details on the join of two simplicial sets and diagram categories, we refer the reader to the Appendix.

Notation 6.1.3. We denote simplices of C_{D} with a subscript D. The map

$$\mathsf{C}_{\mathsf{D}} \longrightarrow \mathsf{C} \qquad \mathsf{X}_{\mathsf{D}} \longmapsto \mathsf{X}$$

denotes the forgetful map.

Given the morphism $\mathsf{P} : \mathsf{L}_0 \to \mathsf{L}_1$ let D be the diagram in Lag given by

$$\begin{tikzcd} & \mathsf{L}_0 \arrow[d, "\mathsf{P}"] \\ 0 \arrow[r, "z_{\emptyset\to}"'] & \mathsf{L}_1 \end{tikzcd}$$

We have the overcategory $\mathsf{Lag}_{\mathsf{D}}$, and also for $i = 0, 1, 2, \ldots$, the overcategory $\mathsf{Lag}_{\mathsf{D}}^{\diamond i}$ where we regard D as a diagram in $\mathsf{Lag}^{\diamond i}$.

Remark 6.1.4. An object $\mathsf{X}_{\mathsf{D}} \in \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$ represents a diagram in $\mathsf{Lag}^{\diamond i}$ of the form

$$\begin{tikzcd} \mathsf{X} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond i} \arrow[d, "\mathsf{P}^{\diamond i}"] \\ 0 \arrow[r] & \mathsf{L}_1^{\diamond i}. \end{tikzcd}$$

A higher simplex $\mathsf{X}_{\mathsf{D}} : \Delta^m \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$ also represents a diagram in $\mathsf{Lag}^{\diamond i}$ of a similar form. For example, an edge $\mathsf{X}_{\mathsf{D}} : \Delta^1 \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$ with underlying vertices $\mathsf{X}_0, \mathsf{X}_1 \in \mathsf{Lag}^{\diamond i}$ represents the union of two tetrahedra built upon compositions

$$\mathsf{X}_0 \to \mathsf{X}_1 \to 0 \to \mathsf{L}_1 \qquad \mathsf{X}_0 \to \mathsf{X}_1 \to \mathsf{L}_0 \to \mathsf{L}_1$$

glued along their common triangle. In general, an m-simplex $\mathsf{X}_{\mathsf{D}} : \Delta^m \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$ with underlying vertices $\mathsf{X}_0, \dots, \mathsf{X}_m \in \mathsf{Lag}^{\diamond i}$ represents a diagram in $\mathsf{Lag}^{\diamond i}$ obtained by gluing two $(m+2)$-simplices along a common $(m+1)$-simplex. The two $(m+2)$-simplices are built upon compositions

$$\mathsf{X}_0 \to \cdots \to \mathsf{X}_m \to 0 \to \mathsf{L}_1 \qquad \mathsf{X}_0 \to \cdots \to \mathsf{X}_m \to \mathsf{L}_0 \to \mathsf{L}_1.$$

In the preceding section, we constructed an object $\mathsf{K}_{\mathsf{D}} = \mathsf{K}_{\mathsf{D}}(\mathsf{P}) \in \mathsf{Lag}_{\mathsf{D}}^{\diamond 1}$ given by the commutative square

$$\begin{tikzcd}
\mathsf{K} \arrow[r, "\mathsf{k}"] \arrow[d, "z_{\to\emptyset}"'] \arrow[dr, "\mathsf{h}"'] & \mathsf{L}_0^{\diamond 1} \arrow[d, "\mathsf{P}^{\diamond 1}"] \\
0 \arrow[r, "z_{\emptyset\to}"'] & \mathsf{L}_1^{\diamond 1}.
\end{tikzcd}$$

Note that for $i = 0, 1, 2, \dots,$ the objects

$$\mathsf{K}_{\mathsf{D}}(\mathsf{P}^{\diamond i}), \mathsf{K}_{\mathsf{D}}^{\diamond i} = \mathsf{K}_{\mathsf{D}}(\mathsf{P})^{\diamond i} \in \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}.$$

are naturally equivalent by Remark 5.3.6, so there is no ambiguity in defining the object $\mathsf{K}_{\mathsf{D}} \in \mathsf{Lag}_{\mathsf{D}}$.

Our ultimate aim is to establish the following:

Theorem 6.1.5. K_{D} *is a terminal object of the overcategory* $\mathsf{Lag}_{\mathsf{D}}$*. That is,* K_{D} *is a kernel of the map* P*.*

The theorem is a simple corollary of the following lemma:

Lemma 6.1.6. *For every object* $\mathsf{X}_{\mathsf{D}} \in \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$*, the stabilization map*

$$\diamond : \mathsf{Lag}_{\mathsf{D}}^{\diamond i}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}^{\diamond i}) \longrightarrow \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}^{\diamond i+1})$$

induces the zero map on homotopy groups.

Proof of Theorem 6.1.5. To show the object K_{D} in the ∞-category $\mathsf{Lag}_{\mathsf{D}}$ is terminal is equivalent to showing that the space of morphisms $\mathsf{Lag}_{\mathsf{D}}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}})$ is contractible, for any object $\mathsf{X}_{\mathsf{D}} \in \mathsf{Lag}_{\mathsf{D}}$. By definition of Lag, we have $\mathsf{Lag}_{\mathsf{D}}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}) = \operatorname{colim}_j \mathsf{Lag}_{\mathsf{D}}^{\diamond i+j}(\mathsf{X}_{\mathsf{D}}^{\diamond j}, \mathsf{K}_{\mathsf{D}}^{\diamond i+j})$ as Kan complexes. (We have fixed i such that X_{D} originates in $\mathsf{Lag}_{\mathsf{D}}^{\diamond i}$.)

Consider $f : \partial\Delta^m \to \mathsf{Lag}_{\mathsf{D}}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}})$. Since $\partial\Delta^m$ is a finite simplicial set, f factors through $\mathsf{Lag}_{\mathsf{D}}^{\diamond i+j}$, for some j. Lemma 6.1.6 shows f can be filled by a map $\tilde{f} : \Delta^m \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i+j+1}$. □

We will prove the lemma based on two propositions. To state the propositions, it is convenient to recall the following:

Definition 6.1.7. Given an ∞-category C, we denote by $\mathsf{C}^{\triangleright} = \mathcal{C} \star *$ the *terminal cone category* given by attaching a terminal vertex $*$ to C. We have the natural inclusion $\iota : \mathsf{C} \to \mathsf{C}^{\triangleright}$ of the *base category* into the terminal cone category.

Given X a diagram in C, we denote by $\mathsf{X}^{\triangleright}$ the *terminal cone diagram* in $\mathsf{C}^{\triangleright}$ obtained by taking the join of X and $*$.

Proposition 6.1.8. *For each $i = 0, 1, 2, \ldots$, there exists a functor*

$$F^i : (\mathsf{Lag}_{\mathsf{D}}^{\diamond i})^{\triangleright} \longrightarrow \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}$$

such that the composition

$$\mathsf{Lag}_{\mathsf{D}}^{\diamond i} \xrightarrow{\iota} (\mathsf{Lag}_{\mathsf{D}}^{\diamond i})^{\triangleright} \xrightarrow{F^i} \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}$$

is the stabilization functor

$$\mathsf{X}_{\mathsf{D}} \longmapsto \mathsf{X}_{\mathsf{D}}^{\diamond}.$$

Proposition 6.1.9. *For each $i = 0, 1, 2, \ldots$, the functor F^i of Proposition 6.1.8 evaluated on the terminal cone point $* \in (\mathsf{Lag}_{\mathsf{D}}^{\diamond i})^{\triangleright}$ satisfies*

$$F^i(*) = \mathsf{K}_{\mathsf{D}}(\mathsf{P}^{\diamond i}) \in \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1},$$

and for each $i = 1, 2, 3, \ldots$, the following morphism is invertible

$$F^i(\mathsf{K}_{\mathsf{D}}(\mathsf{P})^{\diamond i-1} \to *) \in \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}(F^i(\mathsf{K}_{\mathsf{D}}(\mathsf{P})^{\diamond i-1}), \mathsf{K}_{\mathsf{D}}(\mathsf{P}^{\diamond i}))$$

where $\mathsf{K}_{\mathsf{D}}(\mathsf{P})^{\diamond i-1} \to *$ is the unique morphism.

The proofs of these propositions will occupy Sections 6.3, 6.4, and 6.5. For now we prove the lemma assuming the propositions.

Proof of Lemma 6.1.6. Recall that in Section 4.2 we defined the mapping space $\mathsf{C}(x, x')$ for any ∞-category C. In the present proof, for convenience we will take a different (but weakly equivalent) model of the mapping space: Namely, we take the m-simplices of $\mathsf{C}(x, x')$ to be the $(m+1)$-simplices of C whose face opposite the $(m+1)$st vertex is a degenerate face at x, and whose $(m+1)$st vertex is x'.

Since $\mathsf{Lag}_{\mathsf{D}}^{\diamond i}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}^{\diamond i})$ and $\mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}^{\diamond i+1})$ are Kan complexes, we merely need to solve the lifting problem

$$\begin{tikzcd}
\partial\Delta^m \arrow[r, "f"] \arrow[d] & \mathsf{Lag}_{\mathsf{D}}^{\diamond i}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}^{\diamond i}) \arrow[d, "\diamond"] \\
\Delta^m \arrow[r, dashed, "\tilde{f}"] & \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}^{\diamond i+1}).
\end{tikzcd}$$

By definition, f yields a map $\partial\Delta^{m+1} \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$, which in turn induces a canonical map $f^{\triangleright} : (\partial\Delta^{m+1})^{\triangleright} \to (\mathsf{Lag}_{\mathsf{D}}^{\diamond i})^{\triangleright}$. Applying the functor F^i of Proposition 6.1.8, we observe that $F^i(f^{\triangleright})$ is an *outer* horn in $\mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}$, with the face opposite the $(m+2)$nd vertex deleted.

By Proposition 6.1.9, the edge between the $(m+1)$st and $(m+2)$nd vertices is invertible. Hence we can exchange the ordering of the two vertices, obtaining an *inner* horn corresponding to a $(m+2)$-simplex with the $(m+1)$st face deleted. (Strictly speaking, we must post-compose with the inverse of the edge to obtain an inner horn whose boundary agrees with the outer horn.)

By the weak Kan property of $\mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}$, this inner horn can be filled. The resulting $(m+1)$st face is a map $\tilde{f} : \Delta^m \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}(\mathsf{X}_{\mathsf{D}}, \mathsf{K}_{\mathsf{D}}^{\diamond i+1})$ whose boundary is f. □

Remark 6.1.10 (The need for Proposition 6.1.9)**.** Let $\mathsf{X}_{\mathsf{D}} : \Delta^m \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$ be an m-simplex. Then the functor F^i will map the $(m+1)$-simplex given by the join $\mathsf{X}_{\mathsf{D}}^{\triangleright} = \mathsf{X}_{\mathsf{D}} \star *$ to an $(m+1)$-simplex $F^i(\mathsf{X}_{\mathsf{D}}^{\triangleright})$ with terminal vertex $F^i(*) = \mathsf{K}_{\mathsf{D}}(\mathsf{P})^{\diamond i+1}$ and initial opposite face $\mathsf{X}_{\mathsf{D}}^{\diamond 1}$.

In other words, to each m-simplex in $\mathsf{Lag}_{\mathsf{D}}^{\diamond i}$, the functor F^i compatibly produces an m-simplex in $(\mathsf{Lag}_{\mathsf{D}}^{\diamond i+1})_{\mathsf{K}}$ solving the lifting problem

$$\begin{tikzcd}
\Delta^m \arrow[r, dashed] \arrow[d, "\mathsf{X}_{\mathsf{D}}"'] & (\mathsf{Lag}_{\mathsf{D}}^{\diamond i+1})_{\mathsf{K}} \arrow[d] \\
\mathsf{Lag}_{\mathsf{D}}^{\diamond i} \arrow[r, "\diamond"'] & \mathsf{Lag}_{\mathsf{D}}^{\diamond i+1}.
\end{tikzcd}$$

If $\mathsf{Lag}_{\mathsf{D}}$ and $(\mathsf{Lag}_{\mathsf{D}})_{\mathsf{K}}$ were Kan complexes (rather than weak Kan complexes), such a lift would suffice to show that K is a terminal object of $\mathsf{Lag}_{\mathsf{D}}$ by standard topological arguments. However, since we are dealing with ∞-categories (rather than groupoids), we need Proposition 6.1.9 regarding the invertibility of $F^i(\mathsf{K}_{\mathsf{D}}(\mathsf{P})^{\diamond i} \to *)$. This makes the proof of Lemma 6.1.6 possible.

Remark 6.1.11. To unpack the lifting problem in terms of diagrams in $\mathsf{Lag}^{\diamond i}$, recall that an m-simplex $\mathsf{X}_{\mathsf{D}} : \Delta^m \to \mathsf{Lag}_{\mathsf{D}}^{\diamond i}$ represents a diagram in $\mathsf{Lag}^{\diamond i}$ of the form

$$\begin{tikzcd}
\mathsf{X} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond i} \arrow[d, "\mathsf{P}^{\diamond i}"] \\
0 \arrow[r] & \mathsf{L}_1^{\diamond i}.
\end{tikzcd}$$

After stabilizing once, we can regard this as the diagram in $\mathsf{Lag}^{\diamond i+1}$ of the form

$$\begin{tikzcd}
\mathsf{X} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond i+1} \arrow[d, "\mathsf{P}^{\diamond i+1}"] \\
0 \arrow[r] & \mathsf{L}_1^{\diamond i+1}.
\end{tikzcd}$$

To construct the functor F^i, we must compatibly construct a diagram of the form

$$\begin{tikzcd}
\mathsf{X} \arrow[dr] \arrow[drr] \arrow[ddr] & & \\
& \mathsf{K} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond i+1} \arrow[d, "\mathsf{P}^{\diamond i+1}"] \\
& 0 \arrow[r] & \mathsf{L}_1^{\diamond i+1}.
\end{tikzcd}$$

Note this is analogous to proving the "existence" part of the universal property of the kernel. The "uniqueness" part is taken care of by the fact that F^i is defined compatibly for all simplices.

6.2. **Anatomy of lift.** In this interlude between arguments, we introduce some notation and conventions for what follows. Since many of our constructions will take place in $\mathbb{R}^4$, we hope these will ease the presentation of our proofs. In particular, we introduce Figure 6.2.1 which will be frequently referenced during our constructions. We will proceed assuming we have constructed F^i and develop some pictures of its structure. These will guide us in its construction.

Throughout what follows, we will adopt a notational shorthand: We will represent a simplex $\mathsf{X} : \Delta^m \to \mathsf{Lag}$ by concatenation of its vertices, $\mathsf{X}_0\mathsf{X}_1 \cdots \mathsf{X}_m$. The higher morphisms represented by X are to be understood.

As discussed in Remark 6.1.4, an m-simplex $\mathsf{X}_\mathsf{D} : \Delta^m \to \mathsf{Lag}_\mathsf{D}^{\diamond i}$ represents a diagram in $\mathsf{Lag}^{\diamond i}$ of the form

$$\begin{tikzcd}
\mathsf{X} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond i} \arrow[d, "\mathsf{P}^{\diamond i}"] \\
0 \arrow[r] & \mathsf{L}_1^{\diamond i}.
\end{tikzcd}$$

This commutative diagram should not be taken too literally: There are more vertices, edges, and higher simplices than naively drawn. In this pictorial shorthand, any edge drawn from X to another vertex should be interpreted as a terminal cone from X to that vertex.

To construct the functor F^i, we must compatibly construct a diagram of the form

$$\begin{tikzcd}
\mathsf{X} \arrow[dr] \arrow[drr] \arrow[ddr] & & \\
& \mathsf{K} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond i+1} \arrow[d, "\mathsf{P}^{\diamond i+1}"] \\
& 0 \arrow[r] & \mathsf{L}_1^{\diamond i+1}.
\end{tikzcd}$$

This diagram comprises a pair of $(m+3)$-simplices in $\mathsf{Lag}^{\diamond i+1}$ glued along a common $(m+2)$-simplex. If $\mathsf{X}_0, \ldots, \mathsf{X}_m \in \mathsf{Lag}^{\diamond i}$ denote the underlying vertices of X_D, then the two $(m+3)$-simplices are built upon compositions

$$\mathsf{X}_0 \cdots \mathsf{X}_m\mathsf{K}0\mathsf{L}_1 \qquad \mathsf{X}_0 \cdots \mathsf{X}_m\mathsf{K}\mathsf{L}_0\mathsf{L}_1.$$

The common $(m+2)$-simplex is built upon a composition

$$\mathsf{X}_0 \cdots \mathsf{X}_m\mathsf{K}\mathsf{L}_1.$$

As with our pictures, we will denote such compositions by the respective expressions

$$\mathsf{XK0L}_1 \qquad \mathsf{XKL}_0\mathsf{L}_1 \qquad \mathsf{XKL}_1$$

with the understanding that X is a general m-simplex.

Let us now return to the geometry of Lag and examine what such simplices encode. Recall that an $(m+3)$-simplex of $\mathsf{Lag}^{\diamond i+1}$ represents a cobordism in

$$M \times T^*\mathbb{R}^{i+1}_s \times T^*\mathbb{R}_t \times T^*\mathbb{R}^{m+2}_x$$

where $\mathbb{R}^{i+1}_s$, $\mathbb{R}_t$, and $\mathbb{R}^{m+2}_x$ denote the stabilizing, time, and space directions.

In order to draw pictures, let us project onto the final two space coordinates

$$M \times T^*\mathbb{R}^{i+1}_s \times T^*\mathbb{R}_t \times T^*\mathbb{R}^{m+2}_x \longrightarrow \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}.$$

Then we can depict the cobordisms represented by the $(m+3)$-simplices $\mathsf{XK0L}_1$ and $\mathsf{XKL}_0\mathsf{L}_1$ as living over squares, and that represented by the common $(m+2)$-simplex XKL_1 as living over a common edge. This is depicted in Figure 6.2.1.



Figure 6.2.1. A schematic picture of the cobordims comprising $F^i(\mathsf{X}^{\triangleright}_{\mathsf{D}})$ projected onto the final two space coordinates $\mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$. The horizontal direction is the x_{m+1}-direction and the vertical is the x_{m+2}-direction; the lower left vertex $\mathsf{XL}_0\mathsf{L}_1$ is placed at $(0,0)$, and the other vertices are at integral points.

Looking at Figure 6.2.1, along the lefthand edge $x_{m+1} = 0$, we see that $F^i(\mathsf{X}_D^{\triangleright})$ is collared by the original diagram X_D.

Along the righthand edge $x_{m+1} = 1$, we see that $F^i(\mathsf{X}_D^{\triangleright})$ is collared by a composition: it represents a map from X to the kernel diagram K_D. To produce $F^i(\mathsf{X}_\mathsf{D}^{\triangleright})$, a cobordism living over this rectangle, is to produce a homotopy parametrizing between the two edges.

Throughout what follows, we will refer to Figure 6.2.1 as a guide. Our first step, taken in Section 6.3, will be to construct the map from X to the kernel diagram K_D, producing the righthand edge $x_{m+1} = 1$.

6.3. **Map to kernel.** In what follows, we assume without loss of generality that $i = 0$. Accordingly we will simply denote the functor F^i by F.

Recall that an m-simplex $\mathsf{X}_\mathsf{D} : \Delta^m \to \mathsf{Lag}_\mathsf{D}^{\diamond 0}$ with underlying m-simplex $\mathsf{X} : \Delta^m \to \mathsf{Lag}^{\diamond 0}$ represents a diagram

$$\begin{tikzcd}
\mathsf{X} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond 0} \arrow[d, "\mathsf{P}^{\diamond 0}"] \\
0 \arrow[r] & \mathsf{L}_1^{\diamond 0}.
\end{tikzcd}$$

Given the above data, we will construct here a natural map

$$\begin{tikzcd}
\mathsf{X} \arrow[r] & \mathsf{K}
\end{tikzcd}$$

or more precisely, a functor

$$\begin{tikzcd}
F_1 : \mathsf{Lag}_\mathsf{D}^{\diamond 0} \arrow[r] & \mathsf{Lag}_\mathsf{K}^{\diamond 1}.
\end{tikzcd}$$

The notation F_1 reflects the fact that this will yield the boundary value of the functor F along the edge

$$\begin{tikzcd}
\mathsf{XK0L}_1 \arrow[d, dash] \\
\mathsf{XKL}_1 \arrow[d, dash] \\
\mathsf{XKL}_0\mathsf{L}_1
\end{tikzcd}$$

given by $x_{m+1} = 1$ in Figure 6.2.1. This is because, taking the composition of $\mathsf{X} \to \mathsf{K}$ with the kernel diagram

$$\begin{tikzcd}
\mathsf{X} \arrow[dr] & & \\
& \mathsf{K} \arrow[r] \arrow[d] \arrow[dr] & \mathsf{L}_0^{\diamond 1} \arrow[d, "\mathsf{P}^{\diamond 1}"] \\
& 0 \arrow[r] & \mathsf{L}_1^{\diamond 1},
\end{tikzcd}$$

we can regard F_1 as a functor

$$F_1 : \mathsf{Lag}_{\mathsf{D}}^{\diamond 0} \longrightarrow \mathsf{Lag}_{\mathsf{K}}^{\diamond 1} \longrightarrow \mathsf{Lag}_{\mathsf{D}}^{\diamond 1}$$

which will be the boundary value of F along the edge given by $x_{m+1} = 1$ in Figure 6.2.1.

In alternative but equivalent terms, to construct the functor F_1, we must functorically solve the lifting problem

$$\begin{tikzcd}
\Delta^m \arrow[r, dashed] \arrow[d, "\mathsf{X}_{\mathsf{D}}"'] & \mathsf{Lag}_{\mathsf{K}}^{\diamond 1} \arrow[d] \\
\mathsf{Lag}_{\mathsf{D}}^{\diamond 0} \arrow[r, "\diamond"] & \mathsf{Lag}_{\mathsf{D}}^{\diamond 1}.
\end{tikzcd}$$

We will solve this for a single simplex, then check afterwards that it is compatible with face and degeneracy maps.

Construction 6.3.1 (of the functor F_1 on an m-simplex X_{D})**.** The construction is summarized in Figure 6.3.2. We follow the figure's steps (a) through (d).

(a) Let X_{D} be a m-simplex in $\mathsf{Lag}_{\mathsf{D}}^{\diamond 0}$, and let the vertices of $f(\mathsf{X})$ be $\mathsf{X}_0, \ldots, \mathsf{X}_m \in \mathsf{Lag}^{\diamond 0}$. As noted in Remark 6.1.4, X_{D} corresponds to a diagram in $\mathsf{Lag}^{\diamond 0}$ obtained by gluing two $(m+2)$-simplices along a common face. (One of these simplices contains the vertex L_0, while the other contains the vertex 0.) Hence X_{D} yields the data of two cubical Lagrangians living inside $M \times T^*\mathbb{R}_t \times T^*\mathbb{R}^{m+1}$. We depict these two cubical cobordisms in Figure 6.3.2(a). The cubes have been projected onto the plane spanned by the coordinates t and x_{m+1}.

(b) The simplex of X_{D} containing the vertex L_0 is collared along one facet by the cobordism P. The other cube has a face collared by a cobordism factoring through the empty Lagrangian $\mathsf{L}_{\emptyset}$. The two cubes share a common face—the collaring condition says we can smoothly glue the two cubes along this common face. This yields the cube depicted in (b), which we have re-scaled to make the cube narrower. We now think of this as a Lagrangian living in

$$M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*\mathbb{R}^m_x,$$

treating the x_{m+1} direction as the stabilizing s direction.

(c) To make the construction explicit, assume we have chosen a model so that the cobordism depicted in (b) lives above the open rectangle

$$(0,1) \times (-4,0) \subset \mathbb{R}_s \times \mathbb{R}_t.$$

Further assume that this model is collared by the object L_0 along the open edge

$$\{0\} \times (-2,-1)$$

and by the morphism P along the open edge

$$\{0\} \times (-1,0).$$

The cube is labeled accordingly in Figure 6.3.2(b).

To obtain the cube in (c), we perform the rotation construction taking the edge

$$\{0\} \times (-2,0)$$



Figure 6.3.2. A depiction of the steps in the construction of $F_1(\mathsf{X}_\mathsf{D})$. We begin in (a) with the two cobordisms given by the diagram X_D. After gluing and rescaling (a), we obtain the cobordism in (b). We then obtain (c) by rotating the portion of (b) collared by L_0 and P. Finally, to obtain (d), we carve (c) by a one-form $d\eta$.

to the edge

$$(-2,0)\times\{0\}$$

by rotating clockwise about the origin.

(d) To obtain the cube in (d), we translate by a 1-form $d\eta = d\eta_0 + d\eta_1$. To define η_0, let E be the union of three edges

$$(\{-2\}\times(-2,\infty))\cup((-2,0)\times\{-2\})\cup(\{0\}\times(-2,-\infty))\subset\mathbb{R}^2=\mathbb{R}_s\times\mathbb{R}_t.$$

Let $\epsilon>0$ and define N_+ to be the closed set

$$N_+ := \{(e_s+s, e_t+t)\mid (e_s,e_t)\in E \text{ and } s,t\in[0,\epsilon].\}$$

Choose a smooth function $f : \mathbb{R}_s \times \mathbb{R}_t \to \mathbb{R}$ such that

1. $f|_E = 1, \qquad f|_{\partial N_+ \backslash E} = 0,$
2. f is locally constant on $\mathbb{R}^2 \backslash N_+$,
3. f has no critical points on $N_+ \backslash \partial N_+$, and
4. $\frac{\partial f}{\partial s} < 0$ on $N_+ \backslash \partial N_+$.

Treating f as a function on $\mathbb{R}_s \times \mathbb{R}_t \times \mathbb{R}^m_x$ with dependence only on t and s, We define

$$\eta_0 = -\log(1-f)$$

Now we define η_1. Let $u(t) : \mathbb{R} \to \mathbb{R}$ be a C^∞ function such that

$$u|_{(-\infty, 1-\epsilon]} = 0, \qquad u|_{[1,\infty)} = 1$$

and

$$\mathrm{Crit}(u) \cap (1-\epsilon, 1) = \emptyset.$$

Then we define $\eta_1 : \mathbb{R}_s \times \mathbb{R}_t \times \mathbb{R}^m_x \to \mathbb{R}$ to be the function

$$\eta_1 = \log \frac{1 - u(s)u(t+2-\epsilon)}{1-u(s)u(-t-\epsilon)}.$$

with dependence only on t and s. Defining $\eta := \eta_0 + \eta_1$, we obtain the cobordism in step (d) by translating the cobordism in (c) by Γ_η.

We have chosen a model in which the edge $s = 1$ is collared by the empty Lagrangian $L_\emptyset$ at $t = -1$, so that this translation does not yield a singular Lagrangian. The resulting brane structure of (d) is the obvious induced brane structure.

The careful reader will notice that for $i > 0$, the same construction yields a map to $\mathsf{K}(\mathsf{P}^{\diamond i})$, not to $\mathsf{K}(\mathsf{P})^{\diamond i}$. But the observation from Remark 5.3.6 tells us we can always post-compose with a rotation taking the s_{i+1}-axis to the s_1-axis, and this is how we define F^i for $i > 0$.

This ends the construction.

Finally, as we have not affected the directions $x_1, \ldots, x_m$ in the simplex X, the cobordism $F(\mathsf{X}^{\triangleright}_{\mathsf{D}})$ is collared in the $x_1, \ldots, x_m$ coordinates by the appropriate facets. So we have

Lemma 6.3.3. *The construction above is compatible with face and degeneracy maps.*

6.4. **Proof of Proposition 6.1.8.** Let us return to the organizational framework of Figure 6.2.1. It depicts that we must construct a cobordism

$$F^i(\mathsf{X}^{\triangleright}_{\mathsf{D}}) \subset M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*\mathbb{R}^{m+2}_x$$

living over the open rectangle

$$R = (0,1) \times (0,2) \subset \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}.$$

Furthermore, we have the following prescribed boundary values. First, along the labelled edge

$$\begin{tikzcd}
\mathsf{X0L_1} \arrow[d, dash] \\
\mathsf{XL_1} \arrow[d, dash] \\
\mathsf{XL_0L_1}
\end{tikzcd}$$

given by $x_{m+1} = 0$, we have the cobordism given by the initial data $\mathsf{X_D}$ itself.

Along the labelled edge

$$\begin{tikzcd}
\mathsf{XK0L_1} \arrow[d, dash] \\
\mathsf{XKL_1} \arrow[d, dash] \\
\mathsf{XKL_0L_1}
\end{tikzcd}$$

given by $x_{m+1} = 1$, we have the cobordism $F_1(\mathsf{X_D})$ constructed in the previous section.

Here is a rough summary of our approach to the above challenge. First, we construct a cobordism living over the triangle

(T)

$$\begin{tikzcd}
\mathsf{X0L_1} \arrow[d, dash] \arrow[dr, dash] & \\
\mathsf{XL_1} \arrow[d, dash] & \mathsf{XKL_1} \arrow[dl, dash] \\
\mathsf{XL_0L_1} &
\end{tikzcd}$$

with vertices given by the coordinates $(0,0), (0,2), (1,1)$. Then we extend it over the two missing triangles

(T_1)

$$\begin{tikzcd}
\mathsf{X0L_1} \arrow[r, dash] \arrow[dr, dash] & \mathsf{XK0L_1} \arrow[d, dash] \\
& \mathsf{XKL_1}
\end{tikzcd}$$

(T_2)

$$\begin{tikzcd}
& \mathsf{XKL_1} \arrow[dl, dash] \arrow[d, dash] \\
\mathsf{XL_0L_1} \arrow[r, dash] & \mathsf{XKL_0L_1}
\end{tikzcd}$$

with vertices given by the coordinates $(0,2), (1,2), (1,1)$ and $(0,0), (1,0), (1,1)$ respectively.

Finally, it will be straightforward to see that the above constructions yield the desired boundary values and are compatible with face and degeneracy maps.

6.4.1. *Cobordism over triangle T.* Recall the rectangle $R = (0,1) \times (0,2)$, and the triangle $T \subset R$ with vertices given by the coordinates $(0,0),(0,2),(1,1)$.

We will construct a cobodism

$$\mathsf{W} \subset M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*(\mathbb{R}^m_x \times R)$$

living over the rectangle R, and then pull back W to a cobordism

$$\mathsf{W}' = \phi^*(\mathsf{W}) \subset M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*(\mathbb{R}^m_x \times T)$$

living over the triangle T by the diffeomorphism

$$\phi : T \longrightarrow R \qquad \phi(x_{m+1}, x_{m+2}) = (x_{m+1}, \tfrac{x_{m+2}-1}{1-x_{m+1}} + 1).$$

One might be concerned about the complicated behavior of ϕ near the boundary, but this will be of no consequence: W will be collared by the zero section near the boundary.

Construction 6.4.1 (of cobordism W)**.** We will construct W as the union of three Lagrangians

$$\mathsf{W} = \mathsf{W}_{[0,\frac{1}{3}]} \cup \mathsf{W}_{[\frac{1}{3},\frac{2}{3}]} \cup \mathsf{W}_{[\frac{2}{3},1]}.$$

The subscripts $[a,b]$ refer to the fact that we will construct W over the intervals $[a,b] \subset \mathbb{R}_{x_{m+1}}$ piece by piece. We will glue the pieces together to obtain one cobordism W living over $[0,1] \subset \mathbb{R}_{x_{m+1}}$.

We describe the construction of each of these pieces, stating lemmas along the way and leaving the proof of these lemmas til afterward.

6.4.2. *Set-up for construction of* W. *The cobordism* $\mathsf{S}(\mathsf{X_D})$. Let $\mathsf{X} \to \mathsf{K}$ be the map given in construction 6.3.1, and let $\mathsf{h} : \mathsf{K} \to \mathsf{L}_1$ be the simplex constructed in Construction 5.3.2. Consider the composition

$$\begin{tikzcd} \mathsf{X} \arrow[r] & \mathsf{K} \arrow[r, "\mathsf{h}"] & \mathsf{L}_1 \end{tikzcd}$$

as given in Definition 4.1.9. For example if X_D is an m-simplex in $\mathsf{Lag}^{\diamond 0}_D$ (so it yields a pair of $(m+2)$-simplices in $\mathsf{Lag}^{\diamond 0}$), we extend h by the zero section

$$T^*_{\mathbb{R}^{m+1}_x}\mathbb{R}^{m+1}_x$$

before concatenating with the cobordism $\mathsf{X} \to \mathsf{K}$.

For concreteness we fix a model of $\mathsf{X} \to \mathsf{K} \to \mathsf{L}_1$ as follows. We assume that the cobordism $\mathsf{X} \to \mathsf{K}$ lives above the time interval $(-4,0) \subset \mathbb{R}_t$ as in Construction 6.3.1, and that h lives above the interval $(0,5)$. (That is, we choose a model such that h has been translated by two units in the time direction. For instance it allows a non-characteristic cut at $t = 2.5 - \epsilon$.) This composition is depicted in Figure 6.4.3(a).

Construction 6.4.2 (of $\mathsf{S}(\mathsf{X_D})$)**.** Now we note that there is an isotopy of domain, depicted in Figure 6.4.3, which takes $(\mathsf{X} \to \mathsf{K}) \circ \mathsf{h}$ and produces a morphism $\mathsf{X} \to \mathsf{L}_1$ living over a rectangular domain in $\mathbb{R}_s \times \mathbb{R}_t$. (Compare to Figure 6.3.2(b).) We denote the resulting morphism $\mathsf{X} \to \mathsf{L}_1$ by $\mathsf{S}(\mathsf{X_D})$.



(*a*) (*b*)

Figure 6.4.3. An isotopy taking (a) the cobordism $(\mathsf{X} \to \mathsf{K}) \circ \mathsf{H}$ to (b) the cobordism $\mathsf{S}(\mathsf{X_D})$. The horizontal coordinate is the s direction, and the vertical coordinate is the t direction.

Remark 6.4.4. Note that a copy of X_D is contained in the Lagrangian $\mathsf{S}(\mathsf{X}_D)$ by construction: As we travel in the s direction of $\mathsf{S}(\mathsf{X}_D)$, we witness exactly the evolution of X_D. The issue is that s is a *stabilizing* direction; hence we want W to be a cobordism which takes this stabilizing direction and 'turns' it into a direction in which morphisms are allowed to evolve, namely the direction x_{m+2}. If there were no inherent difference between a stabilizing s direction and a morphism x direction in our set-up, the construction of W would be trivial.

6.4.3. *Construction of* $\mathsf{W}_{[\frac{2}{3},1]}$. We parametrize the isotopy from Figure 6.4.3 by the interval

$$[\frac{2}{3},1] \subset \mathbb{R}_{x_{m+1}}.$$

By Example 4.5.2, we can realize the isotopy by a cobordism

$$\underline{\mathsf{W}}_{[\frac{2}{3},1]} \subset (M \times T^*\mathbb{R}_s) \times T^*\mathbb{R}_t \times T^*\mathbb{R}^{m+1}_x.$$

Setting

$$\pi_{m+2} : \mathbb{R}_s \times \mathbb{R}_t \times \mathbb{R}^{m+2}_x \to \mathbb{R}_{x_{m+2}}$$

to be projection onto the last coordinate, we define $\mathsf{W}_{[\frac{2}{3},1]}$ by the pullback

$$\mathsf{W}_{[\frac{2}{3},1]} := \pi^*_{m+2}\underline{\mathsf{W}}_{[\frac{2}{3},1]} = \underline{\mathsf{W}}_{[\frac{2}{3},1]} \times T^*_{\mathbb{R}_{x_{m+2}}}\mathbb{R}_{x_{m+2}}.$$

We direct the isotopy so that $\mathsf{W}_{[\frac{2}{3},1]}$ is collared by

$$\mathsf{XKL}_1 \times T^*_{\mathbb{R}_{x_{m+2}}}\mathbb{R}_{x_{m+2}}$$

along $x_{m+1} = 1$, and by

$$\mathsf{W}_{\frac{2}{3}} := \mathsf{S}(\mathsf{X}_D) \times T^*_{\mathbb{R}_{x_{m+2}}}\mathbb{R}_{x_{m+2}}$$

along $x_{m+1} = \frac{2}{3}$.

6.4.4. *Construction of* $\mathsf{W}_{[\frac{1}{3},\frac{2}{3}]}$. This is done by carving $\mathsf{W}_{[2/3,1]}$. First we define a subset

$$A \subset \mathbb{R}_t \times \mathbb{R}_s \times \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$$

by $A = A' \coprod A''$, where

$$A := [-4+\epsilon, 5-\epsilon]_t \times (-\infty, 1-\epsilon)_s \times (-\infty, 1/3+\epsilon]_{x_{m+1}} \times [2-\epsilon, \infty)_{x_{m+2}}$$

and

$$A'' := [-4+\epsilon, 5-\epsilon]_t \times [\epsilon, \infty)_s \times (-\infty, 1/3+\epsilon]_{x_{m+1}} \times (-\infty, \epsilon]_{x_{m+2}}.$$

We let $N_{\epsilon/2}(A)$ be its open $\epsilon/2$-neighborhood.

Then we let

$$f : \mathbb{R}^4 = \mathbb{R}_t \times \mathbb{R}_s \times \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}} \to \mathbb{R}$$

be a function such that

$$f^{-1}(1) = A, \qquad f^{-1}(0) = \mathbb{R}^4 \backslash N_{\epsilon/2}(A), \qquad \mathrm{Crit}(f) = f^{-1}(1) \cup f^{-1}(0).$$

We then declare

$$\mathsf{W}_{[1/3,2/3]} \subset (\mathsf{W}_{2/3} \times T^*_{\mathbb{R}_{x_{m+1}}}\mathbb{R}_{x_{m+1}}) + \Gamma_{-\log(1-f)}$$

to be the portion living above $[1/3, 2/3] \subset \mathbb{R}_{x_{m+1}}$. It is easily seen that this cobordism is collared at $x_{m+1} = 1/3$; we denote by $\mathsf{W}_{1/3}$ the brane which collars $\mathsf{W}_{[1/3,2/3]}$ there.

Remark 6.4.5 (An explanation of A)**.** The interval $[4+\epsilon, 5-\epsilon]_t$ is chosen in the definition of A so that the resulting carving by f is still collared by L after time $t = 5$, and by X before time $t = -4$.

The interval $(-\infty, 1/3+\epsilon]_s$ is chosen so that $\mathsf{W}_{[1/3,2/3]}$ is indeed collared by $\mathsf{W}_{2/3}$ for $s >> 1/3$, and by the Lagrangian $\mathsf{W}_{1/3}$ along $s \leq 1/3$.

Finally, depicted in Figure 6.4.6 is the portion of $\mathsf{W}_{1/3}$ living over the time interval

$$(-4+\epsilon, 5-\epsilon) \subset \mathbb{R}_t.$$

Note that for $x_{m+2} < \epsilon$, $\mathsf{W}_{1/3}$ is collared by (a tilt of) the morphism $\mathsf{XL}_0\mathsf{L}_1$, and for $x_{m+2} > 2-\epsilon$, $\mathsf{W}_{1/3}$ is collared by (a tilt of) $\mathsf{XL}_\emptyset\mathsf{L}_1$.



Figure 6.4.6. The portion of $\mathsf{W}_{1/3}$ living over the the time interval $(-4+\epsilon, 5-\epsilon) \subset \mathbb{R}_t$. Depicted is the projection onto $\mathbb{R}_s \times \mathbb{R}_{x_{m+2}}$. The horizontal direction is the s direction, and the vertical direction is the x_{m+2} direction.

6.4.5. *Construction of* $\mathsf{W}_{[0,\frac{1}{3}]}$. Assume the following Lemma:

Lemma 6.4.7. *There is a lagrangian cobordism from* $\mathsf{W}_{1/3}$ *to (a tilt of)* X_D.

We let this cobordism be $\mathsf{W}_{[0,1/3]}$, living over the interval

$$[0,1/3] \subset \mathbb{R}_{x_{m+1}}$$

and directed in such a way that X_D collars $\mathsf{W}_{[0,1/3]}$ at $x_{m+1} = 0$. We are finished by declaring

$$\mathsf{W} := \mathsf{W}_{[0,\frac{1}{3}]} \cup \mathsf{W}_{[\frac{1}{3},\frac{2}{3}]} \cup \mathsf{W}_{[\frac{2}{3},1]}.$$

Proof of Lemma 6.4.7. Let $U \subset \mathbb{R}_s \times \mathbb{R}_{x_{m+2}}$ be the region depicted in Figure 6.4.6. Explicitly, U is the union of three rectangles:

$$U = (1-\epsilon, 1)_s \times [2-\epsilon, \infty)_{x_{m+2}} \coprod (0,1)_s \times (\epsilon, 2-\epsilon) x_{m+2} \coprod (0,\epsilon)_s \times (-\infty, \epsilon]_{x_{m+2}}.$$

Fix an orientation-preserving diffeomorphism

$$\psi : (0,1)_s \to (0,\epsilon)_s$$

and choose a smooth isotopy

$$\mathscr{S}_r : [0,1/3]_r \times (0,1)_s \times \mathbb{R}_{x_{m+2}} \to (0,1)_s \times \mathbb{R}_{x_{m+2}}$$

satisfying the following properties:

(1) $\mathscr{S}_0 = id_{(0,1)\times\mathbb{R}}$

(2) $\mathscr{S}_{1/3}((0,1)\times\mathbb{R}) = U$

(3) For all $s \in (0,1)$, $\mathscr{S}_{1/3}(s,x) =: \gamma_s(x)$ is a smooth curve such that
   (a) $\gamma_s(x) = (\psi(s), x)$ for $x \notin [\epsilon, 2-\epsilon]$, and
   (b) writing the tangent vector to $\gamma_s(x)$ as

$$\frac{\partial}{\partial x}\gamma_s(x) = a\partial_s + b\partial_{x_{m+2}} \in T_{\gamma_s(x))}((0,1)\times\mathbb{R}),$$

   we require that one has $a, b \geq 0$ and $a+b > 0$ for all x.

The point of the isotopy is that as r moves from 0 to 1/3, a vertical line in the x_{m+2} direction is isotoped into a curve which points primarily in the s direction. This is the essence of the W as explained in Remark 6.4.4.

One can clearly choose such an isotopy $\mathscr{S}_r$ such that the isotopy takes the tilt

$$(\mathsf{X}_D \times \Gamma_{\log b}) \cap \pi_t^{-1}(-4,5)$$

at $r = 0$ to the Lagrangian

$$\mathsf{W}_{1/3} \cap \pi_t^{-1}(-4,5)$$

at $r = 1/3$. Here, $b : \mathbb{R}_s \to \mathbb{R}$ is a tilting function, and π_t is the projection to the zero section in the time direction:

$$\pi_t : M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*\mathbb{R}^m_x \times T^*\mathbb{R}_{x_{m+2}} \to \mathbb{R}_t.$$

We are also imagining that X_D, as it moves from 0 to 2 in the x_{m+2} direction, is evolving from the cobordism $\mathsf{XL}_0\mathsf{L}_1$ to the cobordism $\mathsf{XL}_\emptyset\mathsf{L}_1$.

By Example 4.5.2 one can realize the isotopy $\mathscr{S}$ as a cobordism evolving in the x_{m+1} direction—we have replaced by x_{m+1} the coordinate r. All that remains, then, is to extend the cobordism associated to $\mathscr{S}_{x_{m+1}}$, which lives above the time interval $(-4,5) \subset \mathbb{R}_t$, to a cobordism living over the whole of $\mathbb{R}_t$. This is done by first constructing a non-smooth Lagrangian V, then creating a smooth Lagrangian $\mathsf{W}_{[0,1/3]}$ by pushing the non-smooth portions to infinity via carving. That is, we will define

$$\mathsf{W}_{[0,1/3]} := \mathsf{V} + \Gamma_{f_S}$$

for a suitable function f_S and some singular Lagrangian V.

The non-smooth Lagrangian V is defined as follows. Let

$$\mathsf{V}_{(-\infty,-4]} := \pi_t^{-1}(-\infty,4] \bigcap (\mathsf{S}(\mathsf{X}_D) \times T^*_{(0,1/3)}(0,1/3)_{x_{m+1}} \times T^*_{\mathbb{R}_{x_{m+2}}}\mathbb{R}_{x_{m+2}})$$

$$\mathsf{V}_{[5,\infty)} := \pi_t^{-1}[5,\infty) \bigcap (\mathsf{S}(\mathsf{X}_D) \times T^*_{(0,1/3)}(0,1/3)_{x_{m+1}} \times T^*_{\mathbb{R}_{x_{m+2}}}\mathbb{R}_{x_{m+2}})$$

and let $\mathsf{V}_{[-4,5]}$ be the cobordism associated to $\mathscr{S}_{x_{m+1}}$. Clearly

$$\mathsf{V} := \mathsf{V}_{(-\infty,-4]} \cup \mathsf{V}_{[-4,-5]} \cup \mathsf{V}_{[5,\infty)}$$

is singular above the times $t = -4$ and $t = 5$. However, note that at $x_{m+1} = 0$, V is collared by the tilt

$$\mathsf{X}_D \times \Gamma_{\log b}$$

as desired.

We fix the non-smoothness of V via carving by a function f_S, constructed as follows.

Consider the set

$$\begin{aligned} S' &= \bigcup_{x_{m+1}} \{x_{m+1}\} \times \mathscr{S}_{x_{m+1}}((0,1)\times\mathbb{R}) \\ &\subset \mathbb{R}_{x_{m+1}} \times \mathbb{R}_s \times \mathbb{R}_{x_{m+2}}. \end{aligned}$$

S' is the projection of the graph of an isotopy. Setting

$$S = S' \times [-4,5]_t \subset \mathbb{R}^4$$

we can choose a function

$$f_S : \mathbb{R}^4 \to [0,1]$$

such that

$$f_S^{-1}(1) = \overline{\mathbb{R}^4 \backslash S}, \qquad f_S^{-1}(0,1) = S \cap N_\epsilon(\partial S), \qquad \mathrm{Crit}(f_S) = f_S^{-1}(1) \cup f_S^{-1}(0).$$

Here, $\overline{\mathbb{R}^4 \backslash S}$ is the closure of $\mathbb{R}^4 \backslash S$, and $N_\epsilon(\partial S)$ denotes the ϵ-neighborhood of ∂S. The resulting Lagrangian

$$\mathsf{W}_{[0,1/3]} := \mathsf{V} + \Gamma_{f_S}$$

is the cobordism we seek. □

This concludes the construction of W.

Remark 6.4.8 (Description of W.)**.** By construction, $\phi^*\mathsf{W}$ is indeed collared along $x_{m+1} = 0$ by a tilt of the diagram X_D, and is collared at the vertex

$$(0,1) \in \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$$

by the cobordism XKL_1.

Remark 6.4.9. Each part of the decomposition

$$\mathsf{W} = \mathsf{W}_{[0,\frac{1}{3}]} \cup \mathsf{W}_{[\frac{1}{3},\frac{2}{3}]} \cup \mathsf{W}_{[\frac{2}{3},1]}.$$

can be described as follows. We began by isotoping XKL_1 to $\mathsf{S}(\mathsf{X}_D)$ along the interval $[2/3,1] \subset \mathbb{R}_{x_{m+1}}$. Along the interval $[1/3,2/3]$ we turned $\mathsf{S}(\mathsf{X}_D)$ into a form where we could begin to change the s-evolution of $\mathsf{S}(\mathsf{X}_D)$ into an evolution along the x_{m+2} direction. We then 'turned' the s evolution into an x_{m+2} evolution via an isotopy along the interval $[0,1/3]$.

6.4.6. *Cobordisms over triangles T_1, T_2.* In Construction 6.4.1 we constructed a cobordism

$$\mathsf{W}' = \phi^*(\mathsf{W}) \subset M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*(\mathbb{R}^m_x \times T)$$

living over the triangle T. We will now construct cobordisms

$$\mathsf{W}_1 \subset M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*(\mathbb{R}^m_x \times T_1)$$

$$\mathsf{W}_2 \subset M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*(\mathbb{R}^m_x \times T_2)$$

living over the triangles T_1 and T_2, respectively, extending the cobordism W'. The two are similar in nature, and we will focus on the latter and leave the former to the reader.

Construction 6.4.10. Let $C \subset \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$ be the interior of the triangle with vertices

$$v_0 = (0,0), v_1 = (1,0), v_2 = (1,1) \in \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$$

and let $d_i C$ be the edge in $\partial C = \overline{C} \backslash C$ opposite the vertex v_i. We choose an orientation-perserving diffeomorphism

$$\phi : C \to (0,1)_{y_1} \times (0,1)_{y_2} \subset \mathbb{R}_{y_1} \times \mathbb{R}_{y_2} =: \mathbb{R}^2_y$$

satisfying the following:

(1) There is some open neighborhood $U \subset \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$ of the edge $d_2 C$ such that

$$\phi(C \cap U) = (0, \epsilon)_{y_1} \times (0,1)_{y_2}$$

for some ϵ, and

$$\lim_{x \to (1/3,1/3)} \phi(x) = (0, \frac{1}{2}) \in \mathbb{R}^2_y.$$

(2) There is some open neighborhood $V \subset \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$ of the union $d_0 C \cup d_1 C$ such that

$$\phi(C \cap V) = (1-\epsilon, 1)_{y_1} \times (0,1)_{y_2}$$

and

$$\lim_{x \to (1,0)} \phi(x) = (1, \frac{1}{2}) \in \mathbb{R}^2_y.$$

We will construct a Lagrangian cobordism

$$\mathsf{Y} \subset M \times T^*(\mathbb{R}_s \times \mathbb{R}_t \times \mathbb{R}^m_x \times \mathbb{R}^2_y)$$

and define

$$\phi^* \mathsf{Y} \subset M \times T^*(\mathbb{R}_s \times \mathbb{R}_t \times \mathbb{R}^{m+2}_x)$$

to be the portion of $F(\mathsf{X}^{\triangleright}_{\mathsf{D}})$ living above C.

First, note that Y must be collared by certain cobordisms Y_i along the edges $y_1 = i$ for $i = 0, 1$:

Along $y_1 = 0$, Y_0 begins as the cobordism $\mathsf{XL}_0\mathsf{L}_1$, and (a) as we move from $y_2 = 0$ toward $y_2 = \frac{1}{2}$, it is isotoped to the portion of $\mathsf{W}_{1/3}$ living over the vertex $(1/3, 1/3) \in \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}}$. (b) At $y_2 = \frac{1}{2}$, Y is carved into $\mathsf{W}_{2/3}$, and (c) is isotoped thereafter to the cobordism XKL_1, which collars $(0,1) \in \mathbb{R}^2_y$.

The description along $y_1 = 1$ is analogous: (a) At $(1,0)$, Y_1 begins as $\mathsf{XL}_0\mathsf{L}_1$, then (b) at $y_2 = \frac{1}{2}$, Y is carved into the Lagrangian $\mathsf{XKL}_0\mathsf{L}_1 = \mathsf{P} \circ \mathsf{K} \circ \mathsf{X}$ from Construction 5.3.4 and (c) it is then isotoped until Y equals XKL_1 at $(1,1) \in \mathbb{R}^2_y$.

We have described the cobordisms Y_i which collar the edges $y_1 = i$. The key observation is

Lemma 6.4.11. *There exists an isotopy of domain in* $\mathbb{R}_s \times \mathbb{R}_t$ *taking* Y_0 *to* Y_1.

We parametrize this isotopy by the interval $[0,1] \subset \mathbb{R}_{y+1}$, and we let Y be the Lagrangian cobordism corresponding to this isotopy. This concludes the construction of $F(\mathsf{X}^{\triangleright}_{\mathsf{D}})$.

Proof of Lemma 6.4.11. Let $A_i \subset \mathbb{R}_s \times \mathbb{R}_t$ be the domain of the Lagrangian collaring Y_i at $y_2 = \frac{1}{2} + \epsilon$, and let A_i' be the domain of the Lagrangian collaring Y_i at $y_2 = \frac{1}{2} - \epsilon$. Then $A_i' \backslash A_i \subset \mathbb{R}_s \times \mathbb{R}_t$ is the region carved out of Y_i at $y_2 = \frac{1}{2}$.

There is an obvious isotopy taking A_0' to A_1' which restricts to an isotopy from A_0 to A_1; this induces the isotopy of domain taking Y_0 to Y_1. □

6.4.7. *Compatibillity with simplicial maps.* Given an m-simplex $\mathsf{X}_\mathsf{D} : \Delta^m \to \mathsf{Lag}_\mathsf{D}$, we have constructed $F(\mathsf{X}_\mathsf{D}^\triangleright)$. Note that all the constructions depended only on the coordinates s, t, x_{m+1}, and x_{m+2}, and did not depend on any spatial coordinate x_j for $j \leq m$. In other words, the constructions restrict to the faces of $\mathsf{X}_\mathsf{D}^\triangleright$—note that the dependence on the time coordinate is remedied by the fact that all morphisms are identified up to time reparametrization. This completes the proof of Proposition 6.1.8.

6.5. **Proof of Proposition 6.1.9.** Now that we have constructed the functor F as described in Proposition 6.1.8, we turn to the proof of Proposition 6.1.9.

Without loss of generality, we may assume that $i = 1$ and study the functor F^1. To reduce clutter, let us introduce the notation

$$\mathsf{X}_\mathsf{D} = F^1(*) \in \mathsf{Lag}_\mathsf{D}^{\diamond 2}.$$

Then we seek to show the natural morphism

$$F^1(\mathsf{K}_\mathsf{D}(\mathsf{P}) \to *) \in \mathsf{Lag}_\mathsf{D}^{\diamond 2}(F^i(\mathsf{K}_\mathsf{D}(\mathsf{P})), \mathsf{X}_\mathsf{D})$$

is invertible. Here $\mathsf{K}_\mathsf{D}(\mathsf{P}) \to *$ is the unique simplex from K_D to $*$ in the cone category.

Our proof once again will be constructive: we will find a cobordism

$$\mathsf{I} \subset M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*\mathbb{R}_x^{m+3}$$

with prescribed boundary values. To approach this, following the pattern of Figure 6.2.1, let us project onto the final three space coordinates

$$M \times T^*\mathbb{R}_s \times T^*\mathbb{R}_t \times T^*\mathbb{R}_x^{m+2} \longrightarrow \mathbb{R}_{x_{m+1}} \times \mathbb{R}_{x_{m+2}} \times \mathbb{R}_{x_{m+3}}.$$

Then the cobordism I will live over the following labelled cube

$$\begin{tikzcd}
& \mathsf{XX0L}_1 \arrow[rr, dash] \arrow[dl, dash] \arrow[dd, dash] & & \mathsf{XKX0L}_1 \arrow[dl, dash] \arrow[dd, dash] \\
\mathsf{X0L}_1 \arrow[rr, dash] \arrow[dd, dash] & & \mathsf{XK0L}_1 \arrow[dd, dash] & \\
& \mathsf{XXL}_1 \arrow[rr, dash] \arrow[dl, dash] \arrow[dd, dash] & & \mathsf{XKXL}_1 \arrow[dl, dash] \arrow[dd, dash] \\
\mathsf{XL}_1 \arrow[rr, dash] \arrow[dd, dash] & & \mathsf{XKL}_1 \arrow[dd, dash] & \\
& \mathsf{XXL}_0\mathsf{L}_1 \arrow[rr, dash] \arrow[dl, dash] & & \mathsf{XKXL}_0\mathsf{L}_1 \arrow[dl, dash] \\
\mathsf{XL}_0\mathsf{L}_1 \arrow[rr, dash] & & \mathsf{XKL}_0\mathsf{L}_1 &
\end{tikzcd}$$

We view this cube as a parameterized version of the rectangle of Figure 6.2.1. Namely, the new x_{m+3}-direction points into the paper so that along the face $x_3 = 0$ we recover precisely Figure 6.2.1. The face is labelled to indicate that the cobordism I will be collared by $\mathsf{X}_\mathsf{D} = F^1(*)$ along it. Along the lefthand face given by $x_{m+1} = 0$, the cobordism I will be collared by the degenerate cobordism obtained by setting the morphism $\mathsf{X} \to \mathsf{X}$ to be the identity of X.

6.5.1. *Construction of* $\mathsf{I}|_{x_3=1}$. The point is to construct a diagram

$$\begin{tikzcd}
\mathsf{X} \arrow[r, "F_1^1"] \arrow[dr, "id_\mathsf{X}"'] & \mathsf{K} \arrow[d, "\mathrm{Rot}"] \\
& \mathsf{X}
\end{tikzcd}$$

at the level of objects in Lag (not at the level of objects in the over-category Lag_D.) The map Rot indicates the isotopy of domain described in Remark 5.3.6, rotating the s_2 axis into the s_1 axis. We follow the construction as depicted in Figure 6.5.1.

(a) Examine the morphism $\mathsf{X} \to \mathsf{K}$ given by F_1^1; this is given by a Lagrangian cobordism living in $M \times T^*\mathbb{R}_t \times T^*\mathbb{R}^2_s$. Its projection onto $T^*_{\mathbb{R}^2_s}\mathbb{R}^2_s$ is the union of two rectangles:

$$\pi(F_1^1) = R_1 \cup R_2, \qquad R_1 = (-2,-1)_{s_1} \times (-2,0]_{s_2}, \qquad R_2 = (-2,1)_{s_1} \times (0,1)_{s_2}.$$

The part of F_1^1 living over R_2 encodes the data of the map $\mathsf{X} \to \mathsf{D}$, and the portion over R_1 is contained in Figure 6.3.2—it is the difference between part (b) and part (c) of the figure. It is also the shaded region in Figure6.5.1(a).

(b) The main observation is that, since F_1^1 is collared along the interval $s_1 = -2$ by the morphism P, we can perform an isotopy of domain ϕ moving $R_1 \cup R_2$ to a new



Figure 6.5.1. A depiction of the face $\mathsf{I}|_{x_3=1}$. (a) is the morphism $\mathsf{X} \to \mathsf{K}$ given by F^1. (b) is obtained by an isotopy of domain in the s_1-s_2-plane. The shaded portion indicates the part of the cobordism affected by the isotopy. Note the isotopy is possible because along $s_1 = -1$ the morphism $\mathsf{X} \to \mathsf{K}$ is collared by P. We parametrize this isotopy by the coordinate x_2, though this is not indicated in the figure. We carve the cobordism from (b) to obtain the cobordism in (c). Clearly the morphism in (c) is isotopic to the identity morphism of X. Note that this figure is not to scale.

domain

$$R_1' \cup R_2$$

where the set R_1' is given by isotoping R_1 to the domain

$$R_1' = (-4,-2)_{s_1} \times (\frac{1}{2} - \epsilon, \frac{1}{2} + \epsilon)_{s_2}.$$

We correspondingly induce an isotopy on the rotation morphism $\mathsf{K} \to \mathsf{X}$ (this is not depicted in the figure).

(c) We now carve (b) to obtain yield the cobordism described in Figure 6.5.1(c). Note that the carving yields a cobordism which, along the region of h allowing a non-characteristic cut, approaches $-\infty$ in the dt direction. Moreover, straightening the snake-like path that the morphism P takes within the cobordism of (c), it is clear that we can isotope (c) into the identity morphism from X to itself. This completes the construction of $\mathsf{I}_{x_3=1}$.

6.5.2. *Construction of* I. The key observation is that the cobordism from $\mathsf{X} \to \mathsf{K}$ to D has two geometric copies of the diagram X_{D} inside it; the construction of I is simply an interpolation between the two. Specifically, there is a copy of X_{D} in the x_2 direction, given by D itself, and there is a second copy in the s_2 direction, as depicted in Figure 6.3.2(b). This was part of the definition of the morphism $F_1^1 : \mathsf{X} \to \mathsf{K}$.

The only difference between the faces we have constructed at $x_3 = 0$ and $x_3 = 1$ is that different copies of D are isotoped from the $x_1 = 1$ face to the $x_1 = 0$ face. More explicitly, along the face $x_3 = 0$, the cobordism from Construction 6.5.1 isotopes the copy of D in the s_2 direction to re-orient D into the x_2 direction, and carves out the copy of D originally living in the x_2 direction. Along the face $x_3 = 1$, we have done just the opposite: We carved out the copy of D living in the s_2 direction, keeping only the copy living in the x_2 direction.

(1) We first fill in the portion of I along the interval $[2/3, 1]_{x_2}$. The simple observation is that $\mathsf{W}_{2/3}$ and the cobordism from Figure 6.5.1(b) are both obtained by performing an isotopy on the basic morphism XKL_1. Further we can demand that the face $\mathsf{I}_{x_2=1}$ be collared by the isotopy which isotopes X into K by performing a rotation on the coordinates s_1 and s_2. So we have three isotopies collaring three edges—$[2/3, 1]_{x_2} \times \{0\}_{x_3}$, $[2/3, 1]_{x_2} \times \{1\}_{x_3}$, and $\{1\}_{x_2} \times [0, 1]_{x_3}$. Clearly we can find a 2-simplex in the space of all isotopies of domain, parametrizing between these three isotopies. Realizing this 2-simplex as a cobordism, we have filled in the portion of I living above the rectangle

$$[2/3, 1]_{x_2} \times [0, 1]_{x_3} \subset \mathbb{R}_{x_2} \times \mathbb{R}_{x_3}.$$

(2) Next we observe that there is an isotopy ψ of $\mathbb{R}_{s_2} \times \mathbb{R}_{x_2}$ which we depict in Figure 6.5.2. The salient feature is that it takes the domain of $\mathsf{W}_{1/3}$ as described in Figure 6.4.6 and transports it to the rectangle in $\mathbb{R}_{s_2} \times \mathbb{R}_{x_2}$ given by

$$(\frac{1}{2} - \epsilon, \frac{1}{2} + \epsilon) \times \mathbb{R}_{x_2}.$$

We parametrize this isotopy ψ by the coordinate x_3. Note that the function f (which we used to carve out $\mathsf{W}_{1/3}$ in Section 6.4.4) can be isotoped along ψ. Let us call this new function $\tilde{f}$ and carve the coboridsm from (1) by f, realizing this carving as taking place along the interval $[1/3, 2/3]_{x_2}$. Then at $x_2 = 1/3$, we have a cobordism such that at $x_3 = 1$ we have the cobordism from Figure 6.5.1(c), and at $x_3 = 0$ we have carved out the cobordism $\mathsf{W}_{1/3}$ from Section 6.4.4.

(3) Now we can use the same trick we used in step (1). Note that the cobordisms given by $\mathsf{I}|_{x_3=1}, \mathsf{I}|_{x_3=0}$ are merely isotopies of domain along the interval $[0, 1/3]_{x_2}$. We can again find a 2-simplex in the space of isotopies to fill in the three isotopies at play. (Namely, these are the isotopies realized along the edges $[0, 1/3]_{x_2} \times \{1\}_{x_3}, [0, 1/3]_{x_2} \times \{0\}_{x_2}$, and $\{1/3\}_{x_2} \times [0, 1]_{x_3}$.) Realizing this 2-simplex as an actual cobordism living



Figure 6.5.2. The isotopy ψ described in the construction of I. The horizontal coordinate is s_2 and the vertical coordinate is x_2. The indicated asymptotics are a result of the carving function $\tilde{f}$ which we induce using ψ.

above the rectangle $[0,1/3]_{x_2} \times [0,1]_{x_3}$ and demanding that along $\{0\}_{x_2} \times [0,1]_{x_3}$ it be the identity, we have our desired I.

7. The loop functor

Finally, with the preceding construction of kernels in hand, and with Theorem 4.4.5 in mind, we discuss properties of the loop functor of Lag.

7.1. **Definition of loop functor.** Let C be an ∞-category with a zero object $0 \in \mathsf{C}$.

Define the simplicial set C^Ω to consist of all maps

$$\Delta^1 \times \Delta^1 \longrightarrow \mathsf{C}$$

whose image is a limit diagram (Cartesian square) of the form

$$\begin{tikzcd} y \arrow[r] \arrow[d] & 0 \arrow[d] \\ 0 \arrow[r] & x \end{tikzcd}$$

The obvious evaluations give a pair of maps $y, x : \mathsf{C}^\Omega \to \mathsf{C}$, and if such Cartesian squares always exist, then $x : \mathsf{C}^\Omega \to \mathsf{C}$ is a trivial fibration, and hence there is a contractible space of sections $s : \mathsf{C} \to \mathsf{C}^\Omega$. In this case, the *loop functor* $\Omega : \mathsf{C} \to \mathsf{C}$ is



Figure 7.2.1. A comparison of $\Omega\mathsf{L}$ and L. At the origin, both $\Omega\mathsf{L}$ and the tilt of L have grading equal to α. Isotoping both $\Omega\mathsf{L}$ and the tilt of L to the product of L with the conormal to a point, we see that the two objects are isomorphic up to a grading shift of one.

defined to be the composition

$$\Omega : \mathsf{C} \xrightarrow{s} \mathsf{C}^{\Omega} \xrightarrow{y} \mathsf{C}.$$

Similarly, if colimit diagrams (cocartesian squares) of the form

$$\begin{tikzcd} x \arrow[r] \arrow[d] & 0 \arrow[d] \\ 0 \arrow[r] & y \end{tikzcd}$$

always exist, then one can define the *suspension functor* $\Sigma : \mathsf{C} \to \mathsf{C}$.

7.2. **Loop functor for Lag.** Let us begin by describing the action of the loop functor of Lag on objects. Then we will formally calculate its action on all simplices.

Fix an object $\mathsf{L} \in \mathsf{Lag}$. By definition, the object $\Omega\mathsf{L} \in \mathsf{Lag}$ is the kernel of the zero map $0 : \mathsf{L}_{\emptyset} \to \mathsf{L}$. By construction, this is a cobordism $\Omega\mathsf{L} \subset M \times T^*\mathbb{R}$ given by the product of L with a graph. The graph is Hamiltonian isotopic to the conormal to a point, and hence $\Omega\mathsf{L}$ is equivalent *up to a shift of grading* with the stabilization $\mathsf{L}^{\diamond 1}$. Deciding what the grading is comes down to comparing the gradings on the graph and the conormal to a point. We refer to Figure 7.2 to see that they will differ by one.

Proposition 7.2.2. *Fix an object* $\mathsf{L} \in \mathsf{Lag}$ *thought of as a brane. The kernel of the zero morphism* $0 : \mathsf{L}_\emptyset \to \mathsf{L}$*, or in other words, the limit to the diagram*

$$\begin{tikzcd} & 0 \arrow[d] \\ 0 \arrow[r] & \mathsf{L} \end{tikzcd}$$

is the brane L *with grading shifted downward by one.*

More generally, given a k-simplex $\mathsf{P} : \Delta^k \to \mathsf{Lag}$ *thought of as a brane, its looping* $\Omega\mathsf{P} : \Delta^k \to \mathsf{Lag}$ *is again the brane* P *with grading shifted downward by one.*

Proof. Set $M' = \Lambda' = \mathsf{L}' = pt$, and consider the zero map $0 : \mathsf{L}_\emptyset \to \mathsf{L}'$. Recall the corresponding cobordism $\mathsf{h}' \subset T^*\mathbb{R}^2$ constructed as part of the kernel diagram.

Returning to the given M and Λ, consider a k-simplex $\mathsf{P} : \Delta^k \to \mathsf{Lag}_\Lambda(M)$ representing a cobordism $\mathsf{Q} \subset M \times T^*\mathbb{R} \times T^*\mathbb{R}^k$. Then the product $\mathsf{Q} \times \mathsf{h}' \subset M \times T^*\mathbb{R} \times T^*\mathbb{R}^k \times T^*\mathbb{R}^2$ is again a cobordism giving a $(k+2)$-simplex of Lag.

It is easily seen that $\mathsf{Q} \times \mathsf{h}'$ gives a simplicial section $\mathsf{Lag} \to \mathsf{Lag}^\Omega$.

Finally, observe that the product with h' gives a cobordism from the original k-simplex P to a new k-simplex $\Omega\mathsf{P}$ whose underlying brane has grading shifted downward by one. □

Remark 7.2.3. One can similarly prove that the suspension functor is given by a shift of grading upward by one.

Remark 7.2.4. The proof of the proposition exploits a more general structure: one can show that $\mathsf{Lag}_{pt}(pt)$ is a symmetric monoidal ∞-category and $\mathsf{Lag}_\Lambda(M)$ is naturally a module category.

Remark 7.2.5. The reader may wonder if the grading shift arose simply from grading conventions. But the grading conventions are necessary: for the cobordism H from the composition $\mathsf{P} \circ \mathsf{k}$ to the zero map to restrict to the appropriate gradings on its boundaries, a grading shift of one needed to appear.

Note that shifting grading is clearly an autoequivalence. Hence we can now conclude with our main result: combining Theorem 4.2.3 (Lag has a zero object), Theorem 6.1.5 (Lag admits kernels), and Proposition 7.2.2 (the loop functor of Lag is invertible), Theorem 1.1.14 immediately follows from Lurie's theorem (Theorem 4.4.5).

8. Appendix: ∞-categories

Here we review ∞-categories, in particular collecting the results we need for our present work. In this appendix only, we will use the term *category* to mean a strict category – that is, a category in the sense of Mac Lane [M] for example. Outside the appendix, by a *category*, we mean an *∞-category*.

8.0.1. *Background.* The theory of ∞-categories was first developed by Joyal (a recent reference is [J02]), who coined them *quasi-categories*. Quasi-categories are direct generalizations of ordinary categories, allowing spaces of morphisms between objects. Moreover, the notion of a functor between quasi-categories, in which homotopies between morphisms must be preserved, is easily defined.

There are many extant models for capturing the idea of an $(\infty, 1)$-category, including complete Segal spaces and simplicial categories, all of which are equivalent. (See [B06].) We choose to use the language of quasi-categories since a formidable toolkit based on quasi-categories has been developed, as most notably evidenced in Lurie's [LTop06] and [L11]. Moreover, since every aspect of the theory is based on the well-studied theory of simplicial sets, deep homotopical statements can be reduced to proofs requiring concrete objectives. The model is formal enough to capture the structures we take interest in, and down-to-earth enough that we can prove concrete, applicable results.

As the main references for quasi-categories are quite large, we hope that this appendix will save the reader some effort in digging through the archives. Nothing collected in the appendix is original, and we learned most of this material from [LTop06]. (This is also our source for the term *∞-category*, which is synonymous with quasi-category.)

8.1. Simplicial sets, horns, quasi-categories.

Let Δ be the category whose objects are finite, ordered, non-empty sets, and whose morphisms are order-preserving maps. Every object in Δ is isomorphic to the object $[n] = \{0, 1, \ldots, n\}$ with numerical ordering.

As usual the injective morphism $d_i : [n] \hookrightarrow [n+1]$ skipping the ith element of $[n+1]$ is called the *ith face map*, and the surjective morphism $s_i : [n+1] \to [n]$ whose fiber above $[i] \in [n]$ is the set $\{i, i+1\} \subset [n+1]$ is called the *ith degeneracy map.* Every morphism in Δ is a composition of face and degeneracy maps.

Definition 8.1.1. A *simplicial set* is a functor $X : \Delta^{op} \to \text{Sets}$. A morphism between simplicial sets is a natural transformation. The set $X([i])$ is called the *set of i-simplices of X*.

Example 8.1.2. The *n-simplex*, written Δ^n, is the representable functor given by $\Delta^n([i]) = \text{Hom}_\Delta([i], [n])$. Given an n-simplex $\Delta^n \to X$, the *jth face* is the $(n-1)$-simplex opposite the jth vertex.

Example 8.1.3 (The nerve of a category)**.** Given any small category Z, one can define a simplicial set called the *nerve of Z*. The 0-simplices are the objects of Z, the 1-simplices are the morphism of Z, and the k-simplices are diagrams of the form

$$\begin{tikzcd} Z_0 \arrow[r, "f_0"] & Z_1 \arrow[r] & \cdots \arrow[r, "f_{k-1}"] & Z_k. \end{tikzcd}$$

For $0 < i < k$, the ith face map is given by composing f_i and f_{i-1}. The other face maps 'forget' the 0th or $(k-1)$st morphism. For all $0 \leq i \leq k$, the ith degeneracy map is given by introducing the morphism $id_{Z_i} : Z_i \to Z_i$.

Example 8.1.4. For $0 \leq i \leq n$ we let Λ^n_i be the simplicial set obtained by deleting the face opposite the ith vertex of the n-simplex. We call Λ^n_i the *ith horn of* Δ^n. When $0 < i < n$, we call Λ^n_i an *inner horn*.

Definition 8.1.5. Let $\Lambda^n_i \to \mathsf{C}$ be a map of simplicial sets. If there exists a map $\Delta^n \to \mathsf{C}$ making the following diagram commute

$$\begin{tikzcd}
\Lambda^n_i \arrow[r] \arrow[d] & \mathsf{C} \\
\Delta^n \arrow[ur] &
\end{tikzcd}$$

we say that the horn $\Lambda^n_i \to \mathsf{C}$ can be *filled.*

Definition 8.1.6. If for all $n \geq 0$, any horn $\Lambda^n_i \to \mathsf{C}$ can be filled, we say that C is a *Kan complex.* If any horn can be filled for $0 < i < n$, we say that C is a *weak Kan complex*, an ∞-*category*, and a *quasi-category.* (The three terms are synonymous, and all in common usage.)

Example 8.1.7. If C is the nerve of a small category, we can fill Λ^2_1 because we can compose any two functions. To be able to fill Λ^2_0 or Λ^2_2 means we can find inverses to any function. Intuitively, the difference between a Kan complex and a weak Kan complex is that the former is a groupoid, while the latter is one in which composition is defined (up to homotopy).

Example 8.1.8. Given any topological space X, one can define the simplicial set of *singular chains on* X, $\mathrm{Sing}(X)_\bullet$, whose n-simplices are continuous maps of the standard n-simplex into X. This is a Kan complex.

Example 8.1.9. One can show that, if the horn-fillings in Definition 8.1.6 are unique for every inner horn, then C is the nerve of a category. Hence one already sees that a weak Kan complex (where horn-fillings are not necessarily unique) describes a flimsier, more general notion of "category," in which compositions are not unique.

Definition 8.1.10. Let C be an ∞-category. Then we call the 0-simplices of C the *vertices*, or *objects*, of C. We also call the 1-simplices the *edges*, or the *morphisms*, of C. We call k-simplices k*-morphisms.*

A *functor*, or ∞-*functor*, between two quasi-categories is simply a map of simplicial sets.

Example 8.1.11. Let C be the nerve of an ordinary category, and let Spaces be the ∞-category of topological spaces. Then a functor from C to Spaces takes commutative diagrams in C to *homotopy commutative* diagrams in Spaces.

8.2. **Mapping spaces.**

For a quasi-category C, there are several equivalent models for the space $\mathrm{Hom}_{\mathsf{C}}(X, Y)$, and we use the following.

Definition 8.2.1. Given two objects X, Y in C, let $\mathrm{Hom}_{\mathsf{C}}(X,Y)$ be the simplicial set whose k-simplices are maps $\Delta^{k+1} \to \mathsf{C}$ such that $(k+1)$st face of Δ^{k+1} is sent to the object X, and such that the $(k+1)$st vertex is sent to the object Y. (The face and degeneracy maps are defined in the natural way.) We call this the *mapping space from X to Y.*

It is not hard to justify the terminology mapping *space*:

Proposition 8.2.2. *If C is a quasi-category, then for all objects $X, Y \in \mathsf{C}$, $\mathrm{Hom}_{\mathsf{C}}(X,Y)$ is a Kan complex.*

Proof. See Proposition 1.2.2.3 of [LTop06]. $\square$

There is another model for the mapping space, given by labeling vertices dually. That is, we can define a Kan complex $\mathrm{Hom}^L_{\mathsf{C}}(X,Y)$ to be simplicial set whose k-simplices are maps $\Delta^{k+1} \to \mathsf{C}$ where the 0th vertex is X, but whose 0th face is the degenerate n-simplex at Y. The choice of models is inconsequential:

Proposition 8.2.3. $\mathrm{Hom}_{\mathsf{C}}(X,Y)$ *is homotopy equivalent to* $\mathrm{Hom}^L_{\mathsf{C}}(X,Y)$.

Proof. See Remark 1.2.2.5 and Corollary 4.2.1.8 in [LTop06]. $\square$

8.3. **Limits and terminal objects.** Now we discuss the notion of (homotopy) limits and colimits in the language of ∞-categories. The homotopical flexibility is built into the ∞-category framework.

Definition 8.3.1. Let A and B be two simplicial sets. The *join from A to B*, denoted $A \star B$, is the simplicial set defined as follows. The set of n-simplices is given by

$$(A \star B)[n] = A[n] \bigcup B[n] \bigcup_{i+j=n-1} A[i] \times B[j].$$

The kth boundary map for an n-simplex $(a,b) \in A[i] \times B[j]$ is given by taking $(d_k a, b)$ if $k \leq i$, and by taking $(a, d_{k-i-1} b)$ for $k > i$. When a (or b) is a zero-simplex, the corresponding boundary map merely forgets a (or b).

Note that if A is a point, then $A \star B$ is the cone over B. So if $D : B \to \mathsf{C}$ is a diagram in C, a map $A \star B \to \mathsf{C}$ restricting to D along B yields an object living over the diagram D. Simliarly, a map $\Delta^1 \star B \to \mathsf{C}$ restricing to D over B would be a map between two objects living over D. This prompts us to define

Definition 8.3.2. Let $D : B \to \mathsf{C}$ be a diagram in C, and let $sSet_D(A \star B, \mathsf{C})$ be the simplicial set of all maps $\phi : A \star B \to \mathsf{C}$ such that $\phi|_B = D$. We define a simplicial set C_D by the identity

$$sSet(\Delta^n, \mathsf{C}_D) = sSet_D(\Delta^n \star B, \mathsf{C})$$

with the obvious face and degeneracy maps. We call C_D the *category of objects living over D*, or the *over-category* when the context is clear.

Definition 8.3.3. A *terminal object* X in a quasi-category C is a vertex $X \in \mathsf{C}$ such that the forgetful map $\mathsf{C}_X \to \mathsf{C}$ from the overcategory to C is a trivial Kan fibration. That is, if the right lifting problem

$$\begin{tikzcd}
\partial\Delta^k \arrow[r] \arrow[d] & \mathsf{C}_X \arrow[d] \\
\Delta^k \arrow[r] \arrow[ur, dashed] & \mathsf{C}
\end{tikzcd}$$

can always be solved.

Remark 8.3.4. Let us restrict our attention to maps $\partial\Delta^k \to \mathsf{C}_X$ such that the composition $\partial\Delta^k \to \mathsf{C}_X \to \mathsf{C}$ is constant, with image X'. Then the condition of being a trivial Kan fibration guarantees that the mapping space $\mathrm{Hom}_{\mathsf{C}}(X', X)$ is contractible. The following assures the converse:

Proposition 8.3.5. *If* C *is a quasi-category,* $X \in \mathsf{C}$ *is a terminal object if and only if* $\mathrm{Hom}_{\mathsf{C}}(X', X)$ *is contractible for all objects* $X' \in \mathsf{C}$*.*

Proof. See Proposition 1.2.12.4 of [LTop06]. □

Definition 8.3.6. Fix a diagram $D : B \to \mathsf{C}$. We say that $X \in \mathsf{Lag}_D$ is a *limit* for D if it is a terminal object in Lag_D.

Remark 8.3.7. In ordinary category theory, terminal objects are unique up to unique isomorphism. In a quasi-category, any two terminal objects are unique up to a contractible choice of isomorphisms.

Example 8.3.8 (Kernels)**.** We define a *zero object* of C is an object 0 which is both initial and terminal. Then a *kernel* to a map $P : L_0 \to L_1$ is a limit to the diagram D, which we depict as

$$\begin{tikzcd}
 & L_0 \arrow[d, "P"] \\
0 \arrow[r] & L_1.
\end{tikzcd}$$

8.4. **Dual notions.** To speak of initial objects, and colimits, all we need is to define the opposite of a quasi-category. In general, we can define the opposite of a simplicial set.

Definition 8.4.1. Let C be a simplicial set. Then the *opposite* of C, written C^{op}, is given on objects by $\mathsf{C}^{op}([n]) = \mathsf{C}([n])$. On morphisms,

$$d_i : \mathsf{C}^{op}([n]) \to \mathsf{C}^{op}([n-1])$$

is given by

$$d_{n-i} : \mathsf{C}([n]) \to \mathsf{C}([n-1])$$

and likewise for the degeneracy maps s_i.

Example 8.4.2. When $\mathsf{C} = \Delta^1$, with non degenerate edge X and vertices $d_0(X) = X_0$, $d_1(X) = X_1$, C^{op} has the same simplices, but $d_0(X) = X_1$, and $d_1(X) = X_0$. This shows that, in general (as one would expect) the directions of the morphisms are reversed.

Example 8.4.3. Given a 2-simplex

$$\begin{tikzcd} B \arrow[r] & C \\ A \arrow[u] \arrow[ur] & \end{tikzcd}$$

in C, the corresponding 2-simplex in C^{op} can be drawn as

$$\begin{tikzcd} B \arrow[d] & C \arrow[l] \arrow[dl] \\ A & \end{tikzcd}$$

which simply asserts the existence of a homotopy from the composite $C \to B \to A$ to $C \to A$.

Definition 8.4.4. Given an ∞-category C, an *initial object* X is a terminal object of C^{op}. Similarly, given a diagram D, a *colimit* to D is a limit to D^{op} in C^{op}.

8.5. **The simplicial nerve.** This section is not necessary for reading the present work. However, the idea of the simplicial nerve inspired the definition of our quasi-category, so we include it here.

Given any fibrant simplicial category $\mathcal{C}$ (a category enriched over Kan complexes) one can form a quasi-category C. This is done by taking the *simplicial nerve.* This in fact gives an equivalence between the model category of quasi-categories and simplicial categories. (See [B06].) One should consider the simplicial nerve and the original simplicial category equivalent. For instance, one can prove:

Proposition 8.5.1. *Let* C *be the simplicial nerve of* $\mathcal{C}$*. Then for all objects* X, Y*, the space* $\mathrm{Hom}_{\mathsf{C}}(X,Y)$ *is homotopy equivalent to* $\mathcal{C}(X,Y)$*.*

In this section we discuss the simplicial nerve construction in some detail. We hope this may motivate the factorization conditions placed on Lagrangian cobordisms, which were inspired by this construction.

Remark 8.5.2. This section closely follows Lurie [LTop06]. In other literature, what we call the simplicial nerve is also called the *homotopy coherent nerve.* It is also a special case of Boardman and Vogt's W construction for simplicial operads.

Let *sSet* denote the category of simplicial sets and *sCat* that of simplicial categories (an object of *sCat* is a category enriched over simplicial sets). There is an adjunction

$$\mathfrak{C} : sSet \rightleftarrows sCat : N$$

where $\mathfrak{C}$ is the rigidification functor and N is the simplicial nerve or coherent nerve (see also [DS09]).

If $\mathcal{C}$ is a fibrant simplicial category (a simplicial category whose morphism simplicial sets are Kan complexes), then the simplicial nerve $N(\mathcal{C})$ is an ∞-category.

We will not describe the rigidifcation $\mathfrak{C}$ in general, but just enough to recall the construction of the simplicial nerve N.

Definition 8.5.3. Given integers $0 \leq i \leq j$, let P_{ij} be the partially ordered set whose elements are subsets of $[i, j] \subset \mathbb{N}$ containing i and j and whose ordering is given by inclusion. Viewing this partially ordered set as a category, we let $N(P_{ij})$ denote the nerve of P_{ij}.

Example 8.5.4. Here are some small examples of P_{ij}.

1. If $i = j$ or $i+1 = j$, then P_{ij} is a category with the single object $\{i\}$ or $\{i, i+1\}$, and no non-identity morphisms.
2. If $i + 2 = j$, then P_{ij} is a category with two objects $\{i, i + 2\}$, $\{i, i + 1, i + 2\}$ and a single non-identity morphism
$$\begin{tikzcd}\{i, i+2\} \arrow[r] & \{i, i+1, i+2\}.\end{tikzcd}$$
3. If $i + 3 = j$, then P_{ij} can be depicted as two glued triangles
$$\begin{tikzcd}\{i, i+3\} \arrow[r] \arrow[d] \arrow[dr] & \{i, i+1, i+3\} \arrow[d] \\ \{i, i+2, i+3\} \arrow[r] & \{i, i+1, i+2, i+3\}.\end{tikzcd}$$

Remark 8.5.5. In general for $i < j$, the category P_{ij} can be depicted as a simplicial decomposition of a k-cube where $k = i - j - 1$. The 2^k vertices of the cube are in bijection with the ways to choose a subset of $[i, j] \subset \mathbb{Z}$ containing i and j.

Let Δ^n denote the n-simplex as a representable simplical set. One defines the simplicial category $\mathfrak{C}[\Delta^n]$ to consist of $n + 1$ objects labeled $0, 1, \ldots, n$, with morphisms

$$\mathfrak{C}[\Delta^n](i, j) = P_{ij}, \quad \text{for } i \leq j,$$

and no morphisms from i to j, for $i > j$. Composition is induced by unions of sets where we regard an element of P_{ij} as a subset of $\mathbb{Z}$.

Remark 8.5.6. Here we are thinking of the category P_{ij} as a simplicial set by taking its nerve.

Definition 8.5.7 (Simplicial Nerve)**.** Given a simplicial category $\mathcal{C}$, its *simplicial nerve* $\mathsf{C} = N(\mathcal{C})$ is the simplicial set defined by the property

$$\mathrm{Hom}_{sSet}(\Delta^n, \mathsf{C}) = \mathrm{Hom}_{sCat}(\mathfrak{C}[\Delta^n], \mathcal{C}).$$

In other words, an n-simplex in C is a functor of simplicial categories $\mathfrak{C}[\Delta^n] \to \mathcal{C}$.

For any arbitrary simplicial category this gives an arbitrary simplicial set. It is not hard to verify

Proposition 8.5.8. *When $\mathcal{C}$ is a fibrant simplicial category, C is a quasi-category.*

Here are some examples of low-dimensional simplices in the simplcial nerve $\mathsf{C} = N(\mathcal{C})$.

Example 8.5.9 (0-simplices and 1-simplices)**.** The 0-simplices (or vertices) of C are the objects of $\mathcal{C}$. The 1-simplices in C are the 1-morphisms in $\mathcal{C}$.

Example 8.5.10 (2-simplices)**.** A 2-simplex in C is the following data: three objects x_0, x_1, x_2, three 0-morphisms $f_{01} : x_0 \to x_1$, $f_{12} : x_1 \to x_2$, and $f_{02} : x_0 \to x_2$, and a 1-morphism $f_{02} \implies f_{12} \circ f_{01}$. We will alternatively depict this either as the segment

$$\begin{tikzcd}
\{0,2\} \arrow[r] & \{0,1,2\}
\end{tikzcd}$$

inside of $\mathcal{C}(x_0, x_2)$ given by the above data, or as the solid rectangle of compositions and homotopies the segment parameterizes:

$$\begin{tikzcd}
x_2 \arrow[r, dash] & x_2 \\
& x_1 \arrow[u, "f_{12}"'] \\
x_0 \arrow[uu, "f_{02}"] \arrow[r, dash] & x_0 \arrow[u, "f_{01}"']
\end{tikzcd}$$

Example 8.5.11 (3-simplices)**.** Similarly, a 3-simplex is a choice of objects x_i, for $0 \leq i \leq 3$, along with morphisms f_{ij}, for $0 \leq i < j \leq 3$, and coherent homotopies among their compositions. Again, we will depict this in two alternative fashions. First, we can draw the triangulated square inside of $\mathcal{C}(x_0, x_3)$ given by the above data

$$\begin{tikzcd}
\{0,3\} \arrow[r] \arrow[d] \arrow[dr] & \{0,2,3\} \arrow[d] \\
\{0,1,3\} \arrow[r] & \{0,1,2,3\}
\end{tikzcd}$$

Here each vertex represents a composition of morphisms (for instance, the vertex $\{0,2,3\}$ represents the composition $f_{23} \circ f_{02}$), and the higher simplices represent homotopies between the compositions. Alternatively, we can extend this diagram vertically and draw the compositions it parameterizes



For clarity, we have drawn the above picture as two disjoint prisms, but one should glue them together above the common rectangle living over the edge $\{0,3\} \to \{0,1,2,3\}$.

One should note that there are some rectangles in the picture whose horizontal edges are drawn without arrowheads; these correspond to the trivial homotopy between the morphisms along their vertical edges.

9. Appendix: Hamiltonian isotopies as cobordisms

9.1. **Deformations of Lagrangians.** Let (M, ω) be a symplectic manifold. Write $\mathcal{C}^\infty(M)$ for its smooth functions, and $\mathcal{C}^{lc}(M)$ for its locally constant functions.

Recall that the first-order symmetries of (M, ω) in the form of vector fields $\mathrm{Vect}(M, \omega) \subset \mathrm{Vect}(M)$ preserving the symplectic form fit into the exact sequence

$$0 \longrightarrow \mathcal{C}^\infty(M)/\mathcal{C}^{lc}(M) \xrightarrow{\delta} \mathrm{Vect}(M, \omega) \xrightarrow{q} H^1(M, \mathbb{R}) \longrightarrow 0$$

where $\omega(\delta(f), -) = df$, and $q(v) = [\omega(v, -)]$. In other words, under the isomorphism

$$\mathrm{Vect}(M) \xrightarrow{\sim} \Omega^1(M) \qquad v \longmapsto \omega(v, -)$$

given by the symplectic form, the above sequence is nothing more than the standard sequence

$$0 \longrightarrow \Omega^1_{ex}(M) \longrightarrow \Omega^1_{cl}(M) \longrightarrow H^1(M, \mathbb{R}) \longrightarrow 0$$

Next, fix a Lagrangian submanifold $L \subset M$. Recall that first-order deformations of L as a Lagrangian submanifold are given by closed one-forms which fit into the exact sequence

$$0 \longrightarrow \mathcal{C}^\infty(L)/\mathcal{C}^{lc}(L) \xrightarrow{d} \Omega^1_{cl}(L) \xrightarrow{[-]} H^1(L, \mathbb{R}) \longrightarrow 0$$

Implicit in this is the identification, via the symplectic form, of the cotangent bundle T^*L with the normal bundle $\mathcal{N}_L M = TM|_L/TL$.

If M is exact with primitive one-form α so that $d\alpha = \omega$, and L is exact so that $[\alpha|_L] = 0 \in H^1(L, \mathbb{R})$, then exact one-forms

$$\Omega^1_{ex}(L) \simeq \mathcal{C}^\infty(L)/\mathcal{C}^{lc}(L)$$

give the first-order deformations of L as an exact Lagrangian submanifold.

9.2. Hamiltonian isotopies.

We begin by reviewing the ways to describe an isotopy of exact Lagrangian submanifolds.

Definition 9.2.1. An *isotopy of exact Lagrangians* of M is a submanifold $\mathcal{L} \subset M \times \mathbb{R}$ such that the projection $p : \mathcal{L} \to \mathbb{R}$ is a stratified submersion and each fiber $\mathcal{L}_t = p^{-1}(t)$ is an exact Lagrangian.

Remark 9.2.2. By Thom's Isotopy Lemma, we can lift the vector field ∂_t to show that all of the fibers of an isotopy of exact Lagrangians are equivalent to each other.

Given an isotopy of exact Lagrangians $\mathcal{L} \subset M \times \mathbb{R}$, we can encode its first-order behavior at a point $(\ell, t) \in \mathcal{L}$ as follows

$$T_{(\ell,t)}\mathcal{L}/T_\ell\mathcal{L}_t \in \mathrm{Hom}(\mathbb{R}, \mathcal{N}_{\mathcal{L}_t}M) \simeq \mathcal{N}_{\mathcal{L}_t}M \otimes \mathbb{R}^\vee$$

Here we write $\mathbb{R}^\vee$ for the dual of $\mathbb{R}$, which we keep around in order for the formulation to be transparently canonical.

We conclude that an isotopy of exact Lagrangians $\mathcal{L} \subset M \times \mathbb{R}$ canonically defines a section

$$\beta_{\mathcal{L}} \in \Gamma(\mathcal{L}, \mathcal{N}_{\mathcal{L}_t}M \otimes \mathbb{R}^\vee)$$

Now using the symplectic form to identify $\mathcal{N}_{\mathcal{L}_t}M \simeq T^*\mathcal{L}_t$, we can regard $\beta_{\mathcal{L}}$ as a section of $T^*\mathcal{L}_t \otimes \mathbb{R}^\vee$ over $\mathcal{L}$.

Definition 9.2.3. An isotopy $\mathcal{L} \subset M \times \mathbb{R}$ of exact Lagrangians is *Hamiltonian* if there is an energy function $E : \mathcal{L} \to \mathbb{R}^\vee$ such that the differential dE restricted to the foliation $T\mathcal{L}_t \subset T\mathcal{L}$ is equal to $\beta_{\mathcal{L}}$.

Lemma 9.2.4. *All isotopies of exact Lagrangians are Hamiltonian. The energy function is unique (locally) up to the addition of the pullback of a function* $\mathbb{R} \to \mathbb{R}^\vee$.

Proof. Follows from basic deformation facts recalled above. ☐

Suppose $\mathcal{L} \subset M \times \mathbb{R}$ is a Hamiltonian isotopy of exact Lagrangians with energy function $E : \mathcal{L} \to \mathbb{R}^\vee$. Then we obtain a natural embedding

$$\mathcal{L} \longrightarrow M \times \mathbb{R} \times \mathbb{R}^\vee \simeq M \times T^*\mathbb{R}$$

and can view $\mathcal{L}$ as a submanifold of $M \times T^*\mathbb{R}$.

To reflect the dependence of the above embedding on E, we will write $\mathcal{L}_E$ for its image. From this perspective, E is nothing more than the integral of the projection

$$\mathcal{L}_E \longrightarrow M \times T^*\mathbb{R} \longrightarrow \mathbb{R}^\vee.$$

Lemma 9.2.5. *$\mathcal{L}_E$ is an exact Lagrangian submanifold of $M \times T^*\mathbb{R}$.*

Proof. The fact that $\mathcal{L}_E$ is Lagrangian is a local exercise. Since $\mathcal{L}_E$ is diffeomorphic to $\mathcal{L} \times \mathbb{R}$, its exactness follows from that of $\mathcal{L}_0$. ☐

9.3. **Hamiltonian cobordisms.** Fix $t_0 < t_1 \in \mathbb{R}$, and for $i = 1, 2$, consider an exact Lagrangian $L_i \subset M$ with function $f_i : L_i \to \mathbb{R}$ such that $\alpha|_{L_i} = df_i$.

We will regard $M \times T^*\mathbb{R}$ as an exact symplectic manifold with respect to the one-form $\beta = \alpha + \xi dt$. In what follows, given subsets $L \subset M$, $S \subset \mathbb{R}$, we will write $L \times S$ to denote the corresponding subset of $M \times T^*\mathbb{R}$ where we regard $\mathbb{R}$ as the zero section of $T^*\mathbb{R}$.

Definition 9.3.1. A Hamiltonian isotopy $\mathcal{L} \subset M \times \mathbb{R}$ of exact Lagrangians with energy function $E : \mathcal{L} \to \mathbb{R}^\vee$ defines a *Hamiltonian cobordism* from (L_0, f_0, t_0) to (L_1, f_1, t_1) if for some small $\epsilon \in \mathbb{R}$, we have

$$\mathcal{L}_E|_{(-\infty, t_0+\epsilon)} = L_0 \times (-\infty, t_0 + \epsilon)$$
$$\mathcal{L}_E|_{(t_1-\epsilon, \infty)} = L_1 \times (t_1 - \epsilon, \infty)$$

and there is a function $f_{\mathcal{L}_E} : \mathcal{L}_E \to \mathbb{R}$ such that $\beta|_{\mathcal{L}_E} = df_{\mathcal{L}_E}$, $f_{\mathcal{L}_E}|\mathcal{L}_{t_0} = f_0$, and $f_{\mathcal{L}_E}|\mathcal{L}_{t_1} = f_1$.

Remark 9.3.2. Note that if the function $f_{\mathcal{L}_E}$ exists then it is unique.

Remark 9.3.3. Observe that for any $b \in \mathbb{R}$, by taking the function $f_{\mathcal{L}_E} + b$, we can just as well regard $\mathcal{L}_E$ as providing a Hamiltonian cobordism from $(L_0, f_0 + b, t_0)$ to $(L_1, f_1 + b, t_1)$.

Remark 9.3.4. Observe that Definition 9.3.1 in particular imposes that

$$E|_{(-\infty, t_0+\epsilon)} = 0 = E|_{(t_1-\epsilon, \infty)}.$$

Conversely, this implies that $\mathcal{L}$ is constant over the two intervals.

Remark 9.3.5. Suppose that we replace E by the modified energy function $\tilde{E} = E + c$, where $c : \mathbb{R} \to \mathbb{R}^\vee$ is any function interpolating between

$$c|_{(-\infty, t_0+\epsilon)} = 0 = c|_{(t_1-\epsilon, \infty)}.$$

Then $\mathcal{L}_{\tilde{E}}$ will coincide with $\mathcal{L}_E$, but will now provide a Hamiltonian cobordism from $(L_0, f_0 + b_0, t_0)$ to $(L_1, f_1 + b_1, t_1)$, where $b_1 - b_0 = \int_{\mathbb{R}} c(t)$.

9.4. **Hamiltonian morphisms.** In order for a Hamiltonian cobordism $\mathcal{L}_E$ to define a morphism, one needs that there exists $c > 0$ such that $\mathcal{L}_E + cdt$ is disjoint from $\Lambda \times \mathbb{R}$.

Definition 9.4.1. Given a a *Hamiltonian cobordism* $\mathcal{L}_E \subset M \times T^*\mathbb{R}$ from (L_0, f_0, t_0) to (L_1, f_1, t_1), we call the locus $\mathcal{L}_E \cap (\Lambda \times \mathbb{R}) \subset M \times T^*\mathbb{R}$ its *critical points*, and the image $E(\mathcal{L}_E \cap (\Lambda \times \mathbb{R})) \subset \mathbb{R}^\vee$ its *critical values.*

Remark 9.4.2. Note that if L_0 or L_1 intersects Λ, then $0 \in \mathbb{R}^\vee$ will be a critical value of any Hamiltonian cobordism $\mathcal{L}_E$ between them due to the boundary requirements on $\mathcal{L}_E$.

Proposition 9.4.3. *Suppose the critical values $E(\mathcal{L}_E \cap (\Lambda \times \mathbb{R}))$ are bounded from below. Then there exists $c > 0$ such that $\mathcal{L}_E + cdt$ is disjoint from $\Lambda \times \mathbb{R}$.*

Proof. Immediate from definitions: take c greater than the absolute value of the minimum of the critical values. ☐

We conclude that the natural class of Hamiltonian isotopies of exact Lagrangians for our story are Hamiltonian cobordisms $\mathcal{L}_E \subset M \times T^*\mathbb{R}$ whose critical values are bounded from below.

Definition 9.4.4. Suppose a *Hamiltonian cobordism* $\mathcal{L}_E \subset M \times T^*\mathbb{R}$ from (L_0, t_0) to (L_1, t_1) has bounded from below critical values. Then we call the resulting morphism in $\mathrm{Hom}(L_0, L_1)$ a *Hamiltonian morphism.*

Remark 9.4.5. One should be careful to note that not all Hamiltonian morphisms are invertible. It is simple to give examples by constructing Hamiltonian cobordisms whose critical values are not bounded from above.

Example 9.4.6. Take $M = \Lambda = L_0 = L_1 = pt$. Then f_0, f_1 are simply constants in $\mathbb{R}$.

9.5. **Higher Hamiltonian morphisms.** It is possible to extend the preceding discussion to higher dimensional families of isotopies. Namely, repeating the above definitions gives the notion of a Hamiltonian $(1+n)$-morphism.

Here is a brief account with an application to invertibility.

Definition 9.5.1. A Δ^n*-family of isotopies of exact Lagrangians* of M is a submanifold $\mathcal{L} \subset M \times \mathbb{R} \times \Delta^n$ such that the projection $p : \overline{\mathcal{L}} \to \mathbb{R} \times \Delta^n$ is a stratified submersion and each fiber $\mathcal{L}_t = p^{-1}(t)$ is an exact Lagrangian.

A Δ^n-family of isotopies of exact Lagrangians $\mathcal{L} \subset M \times \mathbb{R} \times \Delta^n$ canonically defines a section

$$\beta_{\mathcal{L}} \in \Gamma(\mathcal{L}, T^*\mathcal{L}_t \otimes \mathbb{R}^\vee \otimes (\mathbb{R}^n)^\vee)$$

Definition 9.5.2. A Δ^n-family $\mathcal{L} \subset M \times \mathbb{R} \times \Delta^n$ of isotopies of exact Lagrangians is *Hamiltonian* if there is an energy function $E : \mathcal{L} \to \mathbb{R}^\vee \otimes (\mathbb{R}^n)^\vee$ such that the differential dE restricted to the foliation $T\mathcal{L}_t \subset T\mathcal{L}$ is equal to $\beta_{\mathcal{L}}$.

All Δ^n-family of isotopies of exact Lagrangians are Hamiltonian. The energy function is unique (locally) up to the addition of the pullback of a function $\mathbb{R} \times \Delta^n \to \mathbb{R}^\vee$. Given an energy function, we obtain a natural embedding

$$\mathcal{L} \longrightarrow M \times \mathbb{R} \times \Delta^n \times \mathbb{R}^\vee \times (\mathbb{R}^n)^\vee \simeq M \times T^*\mathbb{R} \times T^*\Delta^n$$

and thus can view $\mathcal{L}$ as a submanifold of $M \times T^*\mathbb{R} \times T^*\Delta^n$ which we will denote by $\mathcal{L}_E$.

Now fix a point x in a boundary face $\Delta^k \subset \partial\Delta^n$, and a small $\epsilon > 0$, and consider the small open normal slice

$$\mathcal{N}_x(\epsilon) = \{y \in (\Delta^k)^\perp \cap \Delta^n | \|y - x\| < \epsilon\}.$$

Definition 9.5.3. A Δ^n-family $\mathcal{L} \subset M \times \mathbb{R} \times \Delta^n$ of Hamiltonian isotopies of exact Lagrangians with energy function $E : \mathcal{L} \to \mathbb{R}^\vee \times (\mathbb{R}^n)^\vee$ is said to be *collared in the spatial directions* if for each point x, there is a small $\epsilon > 0$ such that the energy function E is constant above $\mathcal{N}_x(\epsilon) \subset \Delta^n$.

Remark 9.5.4. If $\mathcal{L}$ is collared in the spatial directions, then $\mathcal{L}_E$ has the following structure. For a boundary face $\Delta^k \subset \partial\Delta^n$, and a small normal slice $\mathcal{N}_{\Delta^k} \subset (\Delta^k)^\perp$, over the neighborhood $\Delta^k \times \mathcal{N}_{\Delta^k} \subset \Delta^n$, we have

$$\mathcal{L}_E = \mathcal{L}_E|_{\Delta^k} \times \mathcal{N}_{\Delta^k} \subset (M \times T^*\mathbb{R} \times T^*\Delta^k) \times T^*\mathcal{N}_{\Delta^k}$$

where $\mathcal{L}_E|_{\Delta^k}$ is a Δ^k-family of Hamiltonian isotopies of exact Lagrangians, and we regard $\mathcal{N}_{\Delta^k}$ as the zero section of its cotangent bundle.

Fix $t_0 < t_1 \in \mathbb{R}$, and for $i = 1, 2$, consider an exact Lagrangian $L_i \subset M$ with function $f_i : L_i \to \mathbb{R}$ such that $\alpha|_{L_i} = df_i$.

We will regard $M \times T^*\mathbb{R} \times T^*\Delta^n$ as an exact symplectic manifold with respect to the one-form $\beta = \alpha + \xi dt + \sum_{i=1}^n \xi_i dx_i$. In what follows, given subsets $L \subset M$, $S \subset \mathbb{R}$, $T \subset \Delta^n$, we will write $L \times S \times T$ to denote the corresponding subset of $M \times T^*\mathbb{R} \times T^*\Delta^n$ where we regard $\mathbb{R} \times \Delta^n$ as the zero section of $T^*\mathbb{R} \times T^*\Delta^n$.

Definition 9.5.5. A Δ^n-family $\mathcal{L} \subset M \times \mathbb{R} \times \Delta^n$ of Hamiltonian isotopies of exact Lagrangians with energy function $E : \mathcal{L} \to \mathbb{R}^\vee \times (\mathbb{R}^n)^\vee$ defines a $(1+n)$-*Hamiltonian cobordism* from (L_0, f_0, t_0) to (L_1, f_1, t_1) if it is collared in the spatial directions, for some small $\epsilon \in \mathbb{R}$, we have

$$\mathcal{L}_E|_{(-\infty, t_0+\epsilon)} = L_0 \times (-\infty, t_0 + \epsilon) \times \Delta^n$$

$$\mathcal{L}_E|_{(t_1-\epsilon, \infty)} = L_1 \times (t_1 - \epsilon, \infty) \times \Delta^n$$

and there is a function $f_{\mathcal{L}_E} : \mathcal{L}_E \to \mathbb{R}$ such that $\beta|_{\mathcal{L}_E} = df_{\mathcal{L}_E}$, $f_{\mathcal{L}_E}|\mathcal{L}_{t_0} = f_0$, and $f_{\mathcal{L}_E}|\mathcal{L}_{t_1} = f_1$.

Finally, in order for a $(1+n)$-Hamiltonian cobordism $\mathcal{L}_E \subset M \times T^*\mathbb{R} \times T^*\Delta^n$ to define a morphism, one also needs that there exists $c > 0$ such that $\mathcal{L}_E + cdt$ is disjoint from $\Lambda \times \mathbb{R} \times \Delta^n$.

Definition 9.5.6. Suppose a $(1+n)$-*Hamiltonian cobordism* $\mathcal{L}_E \subset M \times T^*\mathbb{R} \times T^*\Delta^n$ from (L_0, t_0) to (L_1, t_1) has bounded from below critical values. Then we call the resulting morphism in $\mathrm{Hom}(L_0, L_1)$ a $(1+n)$-*Hamiltonian morphism.*

Here is a simple application of the above definitions.

Proposition 9.5.7. *Suppose $\mathcal{L}_E \subset M \times T^*\mathbb{R}$ is a Hamiltonian morphism with critical values $E(\mathcal{L}_E \cap (\Lambda \times \mathbb{R}))$ also bounded from above. Then $\mathcal{L}_E$ is invertible.*

Proof. The inverse to $\mathcal{L}_E$ will be the same Hamiltonian cobordism but run backwards in time. Note that our assumption implies that the critical values of this Hamiltonian cobordism are bounded from below. Then it is an easy exercise to construct a $(1+1)$-morphism connecting the concatenation of $\mathcal{L}_E$ and $\mathcal{L}'_E$ (in either order) with a constant Hamiltonian cobordism. $\square$

References

[AS06a] C. Abbondandalo and M. Schwarz, On the Floer homology of cotangent bundles, Commun. Pure Appl. Math. 59:254-316, 2006.

[AS06b] C. Abbondandolo and M. Schwarz, Notes on Floer homology and loop space homology, in Morse-theoretic methods in nonlinear analysis and in symplectic topology, p.75- 108, Springer, 2006.

[A09] M. Abouzaid, On the wrapped Fukaya category and based loops, arXiv:0907.5606.

[A10a] M. Abouzaid, A geometric criterion for generating the Fukaya category, arXiv:1001.4593.

[A10b] M. Abouzaid, A cotangent fibre generates the Fukaya category, arXiv:1003.4449.

[AS10a] M. Abouzaid and P. Seidel, An open string analogue of Viterbo functoriality. Geom. Topol. 14 (2010), no. 2, 627–718.

[AS10b] M. Abouzaid and P. Seidel, Altering symplectic manifolds by homologous recombination, arXiv:1007.3281.

[Ar80] V.I. Arnold, Cobordismes lagrangiens et legendriens, I et II, Funkt. Anal. Ego Prilozh., 14 no. 3 (1980), 1-13 and no. 4, pp. 8 - 17.

[ArNo01] V.I. Arnold and S.P. Novikov (Eds)., Dynamical Systems IV: Symplectic Geometry and its Applications. Springer-Verlag 2001.

[Au85] M. Audin, Quelques calculs en cobordisme lagrangien, Ann. Inst. Fourier 35(1985) 159-194.

[Au87] M. Audin, Cobordisms of Lagrangian Immersions in the Space of the Cotangent Bundle of a Manifold, Funct. Anal. and App., Vol. 21 Issue 3 (1987).

[Aur10] D. Auroux, Fukaya categories of symmetric products and bordered Heegaard-Floer homology. J. Gökova Geom. Topol. 4 (2010), 1–54.

[AurICM] D. Auroux, Fukaya categories and bordered Heegaard-Floer homology. Proc. International Congress of Mathematicians (Hyderabad, 2010), Vol. II, Hindustan Book Agency, 2010, 917–941.

[Ay08] D. Ayala, Geometric Cobordism Categories, arXiv:0811.2280.

[B06] J. Bergner, A survey of $(\infty, 1)$-categories. arXiv:math/0610239.

[BM88] E. Bierstone and P. Milman, "Semianalytic and subanalytic sets," Inst. Hautes Études Sci. Publ. Math. **67** (1988), 5–42.

[Bi01] P. Biran, Lagrangian barriers and symplectic embeddings. Geom. Funct. Anal. 11 (2001), no. 3, 407–464.

[Ch97] Y. V. Chekanov, Lagrangian embeddings and Lagrangian cobordism. Topics in singularity theory, 1323, Amer. Math. Soc. Transl. Ser. 2, 180, Amer. Math. Soc., Providence, RI, 1997.

[Co] O. Cornea, Lagrangian submanifolds: their fundamental group and cobordism. http://www.dms.umontreal.ca/˜cornea/AbstractOb10.pdf

[DL83] M. De Wilde and P. B. A. Lecomte, Existence of star-products and of formal deformations of the Poisson Lie algebra of arbitrary symplectic manifolds. Lett. Math. Phys. 7 (1983), no. 6, 487–496.

[DS09] D. Dugger and D. Spivak, Rigidifcation of Quasi-categories. arXiv:0910.0814.

[E84] Y. Eliashberg. Cobordisme des solutions de relations diffrentielles. In South Rhone seminar on geometry, I (Lyon, 1983) , Travaux en Cours, pages 1731. Hermann, Paris, 1984.

[E97] Ya. Eliashberg, Symplectic geometry of plurisubharmonic functions, Gauge theory and symplectic geometry, NATO Adv. Sci. Inst. Ser. C Math. Phys. Sci., vol. 488, Kluwer Acad. Publ., 1997, pp. 4967.

[EG91] Ya. Eliashberg and M. Gromov. Convex symplectic manifolds. In Several complex variables, volume 52 of Proc. Symposia Pure Math., pages 135162. Amer. Math. Soc., 1991.

[EKMM] A. Elmendorf, I. Kriz, M. Mandell and J.P. May, Rings, modules, and algebras in stable homotopy theory. With an appendix by M. Cole. Mathematical Surveys and Monographs, 47. American Mathematical Society, Providence, RI, 1997.

[F94] B. V. Fedosov, A simple geometrical construction of deformation quantization. J. Differential Geom. 40 (1994), no. 2, 213–238.

[Fl88a] A. Floer, Morse theory for Lagrangian intersections. J. Differential Geom. 28 (1988), no. 3, 513–547.

[Fl88b] A. Floer, The unregularized gradient flow of the symplectic action. Comm. Pure Appl. Math. 41 (1988), no. 6, 775–813.

[Fl89] A. Floer, Witten's complex and infinite-dimensional Morse theory. J. Differential Geom. 30 (1989), no. 1, 207–221.

[FOOO09] K. Fukaya, Y.-G. Oh, H. Ohta, and K. Ono, "Lagrangian Intersection Floer Theory: Anomaly and Obstruction," Part I & II. AMS/IP Studies in Advanced Mathematics, 46.1 & 46.2. American Mathematical Society, Providence, RI; International Press, Somerville, MA, 2009.

[FO97] K. Fukaya and Y.-G. Oh, "Zero-loop open strings in the cotangent bundle and Morse homotopy," Asian. J. Math. **1** (1997) 96–180.

[FSS08a] K. Fukaya, P. Seidel, and I. Smith, Exact Lagrangian submanifolds in simply-connected cotangent bundles. Invent. Math. 172 (2008), no. 1, 1–27.

[FSS08b] K. Fukaya, P. Seidel, and I. Smith. The symplectic geometry of cotangent bundles from a categorical viewpoint. In Homological Mirror Symmetry: New Developments and Perspectives, volume 757 of Lecture Notes in Physics, pages 126. Springer, 2008.

[Ga06] S. Galatius, Stable homology of automorphism groups of free groups, arXiv:math/0610216, to appear in Ann. of Math.

[GMTW09] S. Galatius, U. Tillmann, I. Madsen, M. Weiss, The homotopy type of the cobordism category. Acta Math. 202 (2009), no. 2, 195–239.

[GM88] M. Goresky and R. MacPherson, *Stratified Morse Theory*. Ergebnisse der Mathematik und ihrer Grenzgebiete (3), 14. Springer-Verlag (1988).

[J02] A. Joyal, Quasi-categories and Kan complexes. *J. Pure Appl. Algebra* **175** (2002) 207–222.

[Kap05] A. Kapustin, "A-branes and noncommutative geometry," arXiv:hep-th/0502212.

[KW07] A. Kapustin and E. Witten, Electric-magnetic duality and the geometric Langlands program. Commun. Number Theory Phys. 1 (2007), no. 1, 1–236.

[KS84] M. Kashiwara and P. Schapira, *Sheaves on manifolds*. Grundlehren der Mathematischen Wissenschaften 292, Springer-Verlag (1994).

[KS85] M. Kashiwara and P. Schapira, "Microlocal study of sheaves," Astérisque No. 128 (1985), 235 pp.

[KO99] R. Kasturirangan and Y.-G. Oh, "Quantization of Eilenberg-Steenrod Axioms via Fary Functors," RIMS preprint (1999).

[KO01] R. Kasturirangan and Y.-G. Oh, "Floer Homology of Open Sets and a Refinement of Arnol'd's Conjecture," Math. Z. **236** (2001), 151-189.

[Ke06] B. Keller, On differential graded categories, International Congress of Mathematicians. Vol. II, 151–190, Eur. math. Soc., Zurich, 2006.

[K03] M. Kontsevich, Deformation quantization of Poisson manifolds. Lett. Math. Phys. 66 (2003), no. 3, 157–216.

[K09] M. Kontsevich, Talk in Paris, 2009.

[L10] I. Losev, Quantized symplectic actions and W-algebras. J. Amer. Math. Soc. 23 (2010), no. 1, 35–59.

[LTop06] J. Lurie, Higher Topos Theory. Annals of Mathematics Studies, 170. Princeton University Press, Princeton, NJ, 2009.

[DAGI] J. Lurie, Stable Infinity Categories, arXiv:math/0608228.

[L11] J. Lurie, Higher Algebra, http://www.math.harvard.edu/ lurie/papers/higheralgebra.pdf.

[L09TFT] J. Lurie, On the Classification of Topological Field Theories, Current developments in mathematics, 2008, 129–280, Int. Press, Somerville, MA, 2009.

[DAGVI] Derived Algebraic Geometry VI: E_k Algebras, arXiv:0911.0018

[M] MacLane, S., 1997, Categories for the Working Mathematician, 2nd edition, New York: Springer-Verlag.

[N09] D. Nadler, Microlocal branes are constructible sheaves, Selecta Math. 15 (2009), no. 4, 563–619.

[N11] D. Nadler, Fukaya categories as categorical Morse homology, in preparation, 35 pages, draft available at

`http://www.math.northwestern.edu/~nadler/`

[NZ09] D. Nadler and E. Zaslow, “Constructible Sheaves and the Fukaya Category,” J. Amer. Math. Soc. 22 (2009), 233–286.

[Oh] Y.-G. Oh, “Floer homology and its continuity for non-compact Lagrangian submanifolds,” arXiv:math/0011116v1.

[S08] P. Seidel, *Fukaya Categories and Picard-Lefschetz Theory*, Zurich Lectures in Advanced Mathematics. European Mathematical Society (EMS), Zrich, 2008.

[S10] P. Seidel, Some speculations on pairs-of-pants decompositions and Fukaya categories, arXiv:1004.0906.

[T09] D. Treumann, Exit paths and constructible stacks. Compos. Math. 145 (2009), no. 6, 1504–1532.

[VM96] L. van den Dries and C. Miller, “Geometric categories and o-minimal structures,” Duke Math. J. **84**, no. 2 (1996), 497–539.

[V94] C. Viterbo, “Generating functions, symplectic geometry, and applications,” Proceedings of the International Congress of Mathematicians, Vol. 1, 2 (Zrich, 1994), 537–547, Birkhuser, Basel, 1995.

[V97] C. Viterbo, “Exact Lagrange submanifolds, periodic orbits and the cohomology of free loop spaces,” J. Differential Geom. 47 (1997), no. 3, 420–468.

[V99] C. Viterbo, Functors and computations in Floer homology with applications. I. Geom. Funct. Anal. 9 (1999), no. 5, 985–1033.

David Nadler, Hiro Lee Tanaka

Department of Mathematics, Northwestern University, 2033 Sheridan Road, Evanston, IL 60208

nadler@math.northwestern.edu, htanaka@math.northwestern.edu